



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

**HEAD-FDR/2245**

**STATE :- BIHAR**

**DISTRICT :- Madhubani**

**CIRCLE :- Darbhanga**

**BLOCK :- Khajauli**

**YEAR:- 2021-22**

**Estimate for Motorable in  
Bhatchaura to kharbona  
under FDR**

**TOTAL LENGTH OF ROAD:-**

**3.10 KM**

**TOTAL COST FOR MOTORABLE**

**Rs. 861059.31**

Submitted by:  
Executive Engineer  
RWD(W) Division, Madhubani

## प्रतिवेदन

|                 |    |                               |
|-----------------|----|-------------------------------|
| पथ का नाम       | :- | <u>Bhatchaura to kharbona</u> |
| पथ की लम्बाई    | :- | <u>3.10 KM</u>                |
| प्राक्कलित राशि | :- | 861059 रु0                    |
| प्रमंडल का नाम  | :- | <u>Madhubani</u>              |
| अंचल का नाम     | :- | <u>Darbhangha</u>             |
| योजना का नाम    | :- | <u>FDR-2245</u>               |

प्रस्तुत प्राक्कलन Bhatchaura to kharbona पथ के लिए तैयार किया गया है जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/जलजमाव/Wave Cut के कारण क्षतिग्रस्त हो गया था। जिसके कारण आवागमन बाधित हो गया था। फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था।

यह प्राक्कलन सचिव, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक-मु0अ0-4 (मु0) विविध (कार्य) -23-60/2020-1937 पटना दिनांक 07.07.2021 के आलोक में तैयार किया गया है।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को मिट्टी एवं ईंट के टुकड़ों से भरकर उसका सम्पीडन किया जाने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन वर्तमान स्वीकृति अनुसूचि दर पर तैयार किया गया है। यह कार्य लोकहित एवं जनहित में अत्यावश्यक है। अतः इस प्राक्कलन की स्वीकृति अपेक्षित है। यह कार्य विभागीय रूप से सम्पादित करा लिया गया है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर जो संवेदक लाभांश को छोड़कर था। उसे प्रावधान करते हुए तैयार किया गया है।

23/10/21  
कनीय अभियंता

30/10/21  
सहायक अभियंता,

30/10/21  
कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमण्डल, मधुबनी

# **Estimate for Motorable in Bhatchaura to kharbona**

**Length:- 3.10 KM**

| Sl No | Item No | Name of Item                                                                                                                                    | Unit | No | Length            | Width | Height | Qty.                        | Rate    | Amount                         |
|-------|---------|-------------------------------------------------------------------------------------------------------------------------------------------------|------|----|-------------------|-------|--------|-----------------------------|---------|--------------------------------|
| 1     |         | Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I. | Cum  |    | As per Appendix 1 |       |        | 114.86<br><del>360.87</del> | 2004.96 | 229688=00<br><del>723530</del> |
|       |         |                                                                                                                                                 |      |    |                   |       |        | Add GST 12%                 |         | <del>86824</del> 27563=00      |
|       |         |                                                                                                                                                 |      |    |                   |       |        | Add L.Cess 1%               |         | <del>7235</del> 2297=00        |
|       |         |                                                                                                                                                 |      |    |                   |       |        | S Fee                       |         | <del>43470</del> 11823=00      |
|       |         |                                                                                                                                                 |      |    |                   |       |        | G. Total:-                  |         | 861059                         |

**271371=00**

*[Signature]*  
22/10/21  
Junior Engineer  
RWD(W) Section  
Khajauli

*[Signature]*  
22/10/21  
Assistant Engineer  
RWD(W) Sub Division  
Khajauli

*[Signature]*  
30/10/21  
Executive Engineer  
RWD(W) Division, Madhubani

कार्यपालक, अभियन्ता, माधकानि, कार्य प्रमाण - विरोल  
के समर्थित जॉय प्रविष्टि के आधार पर -

POST. Fecto T/S for Rs 2,71,371=00 (Rupees -  
two lacs seventy one thousand three hundred -  
seventy one) only.

*[Signature]*  
Superintending Engineer  
RWD Works Circle, Darbhanga  
22/10/21

## Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, ~~Farbhanga~~, Madhubani

Name of Block/Road:- Khagauli / Bhatchaura to Kharbana.

### A. For Road

1. Damage Location Chainage:- 1.8, 1.9, 2.2, 2.4 2.3114
2. Damage Length :- 354m
3. Nature of Damage :- Road cut
4. Details of Restoration Works
  - i. Material being used in Restoration works:- Brick bat
  - ii. Equipment's / Tools being used in Restoration works:-
  - iii. Procedure taken up in Restoration works:- Brick bat filling
  - iv. Restored Length:- 354m

### B. For Bridge

1. Damage Location Chainage:- 354m
2. Damage Length :- 0
3. Nature of Damage :-
4. Details of Restoration Works
  - i. Material being used in Restoration works:-
  - ii. Equipment's / Tools being used in Restoration works:-
  - iii. Procedure taken up in Restoration works:-
  - iv. Restored Length:-

N/A

Satisfactory

Signature of JE/AE/EE

Signature  
(Name of Inspection)