



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

HEAD-FDR/2245

STATE :- BIHAR

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Khajauli

YEAR:- 2021-22

**Estimate for Motorable in
Chanardih to Marukia pmgsy Road
under FDR**

TOTAL LENGTH OF ROAD:-

12.325 km

TOTAL COST FOR MOTORABLE

Rs. 3984576.62

7,37,053

Submitted by:
Executive Engineer
RWD(W) Division, Madhubani

प्रतिवेदन

पथ का नाम	:-	<u>Chanardih to Marukia pmgsy Road</u>
पथ की लम्बाई	:-	<u>12.325 km</u>
प्राक्कलित राशि	:-	<u>3984577</u> रू0 <u>737053</u>
प्रमंडल का नाम	:-	<u>Madhubani</u>
अंचल का नाम	:-	<u>Darbhangha</u>
योजना का नाम	:-	<u>FDR-2245</u>


प्रस्तुत प्राक्कलन Chanardih to Marukia pmgsy Road पथ के लिए तैयार किया गया है जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/जलजमाव/Wave Cut के कारण क्षतिग्रस्त हो गया था। जिसके कारण आवागमन बाधित हो गया था। फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था।


यह प्राक्कलन सचिव, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक-मु0अ0-4 (मु0) विविध (कार्य) -23-60/2020-1937 पटना दिनांक 07.07.2021 के आलोक में तैयार किया गया है।


इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को मिट्टी एवं ईट के टुकड़ों से भरकर उसका सम्पीडन किया जाने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन वर्तमान स्वीकृति अनुसूचि दर पर तैयार किया गया है। यह कार्य लोकहित एवं जनहित में अत्यावश्यक है। अतः इस प्राक्कलन की स्वीकृति अपेक्षित है। यह कार्य विभागीय रूप से सम्पादित करा लिया गया है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर जो संवेदक लाभांश को छोड़कर था। उसे प्रावधान करते हुए तैयार किया गया है।


कनीय अभियंता


महायक अभियंता,


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मधुबनी

Estimate for Motorable in Channarain to Marukia pmgsy Road

Length:- 12.325 km

Sl No	Item No	Name of Item	Unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum					311.15 1682.10	2004.96	623843.50 3372552
									Add GST 12%	404706 7486/20
									Add L.Cess 1%	33726 6238.20
									S Fee	173593 3211/20
									G. Total:-	3984577 7370532

[Signature]
29/10/21
Junior Engineer
RWD(W) Section
Khajauli

[Signature]
30/10/21
Assistant Engineer
RWD(W) Sub Division
Khajauli

[Signature]
30/10/21
Executive Engineer
RWD(W) Division, Madhubani
Total = 7,37,053

कार्यपालक अभियंता द्वारा कृपया कि, कार्य समझौता - विशेष के द्वारा
समर्पित जाँच प्रतिवेदन के आधार पर

past facto T/S For Rs 7,37,053/- (Rupees seven
lakh thirty seven Thousand and thirty three Rupees only)

[Signature]
Superintending Engineer
R.W.D. (W) CIRCLE, DARBHANGA
[Signature]

Inspection Report of Flood Damage work

Name of PIUs:- Madhubani

Name of Block/ Road:- Khajauli/Chanardih to Marukia PMGSY road

A. For Road


1. Damage Location Chainage:- 1.70 km to 12.325
2. Damage Length :- 650m
3. Nature of Damage :- Side cut Slope cut Flank cut.
4. Details of Restoration Works
 - i. Material being used in Restoration works:- Brick Bat ✓
 - ii. Equipments's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:- Brick Bat Filling ✓
 - iv. Restored Length:- 650m

B. For Bridge

1. Damage Location Chainage:-
2. Damage Length :-
3. Nature of Damage :- N/A
4. Details of Restoration Works
 - i. Material being used in Restoration works:-
 - ii. Equipments's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

Satisfactory.


Signature of JE/AE/EE


Signature
(Name of Inspection)