



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

HEAD-FDR/2245

STATE :- BIHAR

AA COPY

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Khajauli

YEAR:- 2021-22

Estimate for Motorable in

T02 to Dholbajja

under FDR

TOTAL LENGTH OF ROAD:-

2.450 KM

TOTAL COST FOR MOTORABLE

Rs. 967444.65

3,66,006 .

Submitted by:

Executive Engineer

RWD(W) Division, Madhubani

प्रतिवेदन

पथ का नाम	:-	<u>T02 to Dholbajja</u>
पथ की लम्बाई	:-	<u>2.450 KM</u>
प्राक्कलित राशि	:-	967445 रु0 <u>3,66006</u>
प्रमंडल का नाम	:-	<u>Madhubani</u>
अंचल का नाम	:-	<u>Darbhanga</u>
योजना का नाम	:-	<u>FDR-2245</u>


प्रस्तुत प्राक्कलन T02 to Dholbajja पथ के लिए तैयार किया गया है जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/जलजमाव/Wave Cut के कारण क्षतिग्रस्त हो गया था। जिसके कारण आवागमन बाधित हो गया था। फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था।

यह प्राक्कलन सचिव, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक-मु0अ0-4 (मु0) विविध (कार्य) -23-60/2020-1937 पटना दिनांक 07.07.2021 के आलोक में तैयार किया गया है।


इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को मिट्टी एवं ईंट के टुकड़ों से भरकर उसका सम्पीडन किया जाने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन वर्तमान स्वीकृति अनुसूचि दर पर तैयार किया गया है। यह कार्य लोकहित एवं जनहित में अत्यावश्यक है। अतः इस प्राक्कलन की स्वीकृति अपेक्षित है। यह कार्य विभागीय रूप से सम्पादित करा लिया गया है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर जो संवेदक लाभांश को छोड़कर था। उसे प्रावधान करते हुए तैयार किया गया है।


कनीय अभियंता


सहायक अभियंता,


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, मधुबनी

Estimate for Motorable in T02 to Dholbajja

Length:- 2.450 KM

SI No	Item No	Name of Item	Unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum		As per Appendix 1			406.66 154.5 m ³	2004.96	815328 3,09,786
								Add GST 12%		97839 27,174
								Add L.Cess 1%		8153 8098
								S Fee		48124 15,948
								G. Total:-		967445

Total = 3,66,006 200

Junior Engineer
RWD(W) Section
Khajauli

Assistant Engineer
RWD(W) Sub Division
Khajauli

Executive Engineer
RWD(W) Division, Madhubani

कार्यपालक अभियंता, राब कान वि, कारी प्रमंडल - बिरोस के हारा
समर्पित गौन्य प्रतिवेदन के आधार पर

post facto T/S For Rs. 3,66,006/- (Rupees Three
lakh sixty six Thousand and six rupees) only

Superintending Engineer
R.W.D. (W) CIRCLE, DARBHANGA

Inspection Report of Flood Damage work

Name of PIUs:- Madhubani

Name of Block/ Road:- Khajauli/T02 to Dholbjja

A. For Road

1. Damage Location Chainage:- 0.200 and 0.800 to 2.45km.
2. Damage Length :- 137m
3. Nature of Damage :- Side slope flk cut side cut
4. Details of Restoration Works

- i. Material being used in Restoration works:- Brick Bat ✓
- ii. Equipments's/Tools being used in Restoration works:-
- iii. Procedure taken up in Restoration works:- Brick Bat Filling ✓
- iv. Restored Length:- 137m.

B. For Bridge


1. Damage Location Chainage:-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works

N/A

- i. Material being used in Restoration works:-
- ii. Equipments's/Tools being used in Restoration works:-
- iii. Procedure taken up in Restoration works:-
- iv. Restored Length:-

Satisfactory


Signature of JE/AE/EE


Signature
(Name of Inspection)