



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

HEAD-FDR/2245

STATE :- BIHAR

AA COPY

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Khajauli

YEAR:- 2021-22

**Estimate for Motorable in
GOBRAURA BRAHMNASTHAN TO KAMLA SHYPHONE
under FDR**

TOTAL LENGTH OF ROAD:-

4.200 KM

TOTAL COST FOR MOTORABLE

Rs. ~~682379.16~~

2,62,061

Submitted by:

Executive Engineer

RWD(W) Division, Madhubani

प्रतिवेदन

पथ का नाम	:-	<u>GOBRAURA BRAHMNASTHAN TO K</u>
पथ की लम्बाई	:-	<u>4.200 KM</u>
प्राक्कलित राशि	:-	682379 रु0 262061
प्रमंडल का नाम	:-	<u>Madhubani</u>
अंचल का नाम	:-	<u>Darbhanga</u>
योजना का नाम	:-	<u>FDR-2245</u>

प्रस्तुत प्राक्कलन **GOBRAURA BRAHMNASTHAN TO** पथ के लिए तैयार किया गया है जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/जलजमाव/Wave Cut के कारण क्षतिग्रस्त हो गया था। जिसके कारण आवागमन बाधित हो गया था। फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था।

यह प्राक्कलन सचिव, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक-मु0अ0-4 (मु0) विविध (कार्य) -23-60/2020-1937 पटना दिनांक 07.07.2021 के आलोक में तैयार किया गया है।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को मिट्टी एवं ईट के टुकड़ों से भरकर उसका सम्पीडन किया जाने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन वर्तमान स्वीकृति अनुसूचि दर पर तैयार किया गया है। यह कार्य लोकहित एवं जनहित में अत्यावश्यक है। अतः इस प्राक्कलन की स्वीकृति अपेक्षित है। यह कार्य विभागीय रूप से सम्पादित करा लिया गया है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर जो संवेदक लाभांश को छोड़कर था। उसे प्रावधान करते हुए तैयार किया गया है।

29/10/21
कनीय अभियंता

30/10/21
सहायक अभियंता,

30/10/21
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, मधुबनी

**Estimate for Motorable in GUBKAUKA
BRAHMNASTHAN TO KAMLA
Length:- 4.200 KM**

Sl No	Item No	Name of Item	Unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	As per Appendix 1				283.35 110.63m ³	2004.96	568102
										2,21,809 = ~
									Add GST 12%	26817 = ~
									Add L.Cess 1%	5681
									S Fee	40424
									G. Total:-	682379

Total = 2,62,061

Wavy
29/10/21
Junior Engineer
RWD(W) Section
Khajauli

Wavy
30/10/21
Assistant Engineer
RWD(W) Sub Division
Khajauli

Wavy
30/10/21
Executive Engineer
RWD(W) Division, Madhubani

कार्यपालक अभियंता, ग्राहक कार वि, कार्य प्रमुख-विशेष के द्वारा
स्वीकृत जाय प्रतिवेदन के आधार पर

post facto T/BR2, 62061—(Rupees)

Two Lakh Sixty two Thousand And sixty one
Rupees) only

Wavy
18/11/21
Superintending Engineer
R.W.D. (W) CIRCLE, DARBHANGA

Inspection Report of Flood Damage work

Name of PIUs:- Madhubani

Name of Block/ Road:- Khajauli/Gobraura Brahmsthan to Kamla shyphone

A. For Road

1. Damage Location Chainage:-

0.45, 1.20, 3.50 4.0.

2. Damage Length

:-

137 m.

3. Nature of Damage

:-

cut side, Road cut, flank cut.

4. Details of Restoration Works

i. Material being used in Restoration works:- Brick Bat ✓

ii. Equipments's/Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:- Brick Bat Filling ✓

iv. Restored Length:-

B. For Bridge

1. Damage Location Chainage:-

2. Damage Length

:-

N/A

3. Nature of Damage

:-

4. Details of Restoration Works

i. Material being used in Restoration works:-

ii. Equipments's/Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:-

iv. Restored Length:-

Handwritten signature
06/12/21
Signature of JE/AE/EE

Satisfactory

Handwritten signature
Signature
(Name of Inspection)