

Name of Road:- Borhar to Simha Tol				Block : HARLAKHI		District: MADHUBANI		Length : 6.890 KM		
Sr No.	Item	Item of Work	Nos	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
1	1.1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching or Boulder Pitching in slope or apron including light ramming etc. all complete as per approved design, specification and direction of E/I								
		CH-0.030 KM	1	24 20.00	1.50	0.30	16.8 12.50			
		CH-0.070 KM	1	1.00	3.75	0.20	0.750			
		CH-0.070 KM	5	1.00	1.00	0.20	1.000			
		CH-0.090 KM	1	3.00	1.00 1.50	0.20	0.200 0.600			
		CH-0.100 KM	1	1.00	1.00	0.15	0.150			
		CH-0.150 KM	2	2.00	1.00	0.15	0.600			
		CH-0.250 KM	4 5	1.00	1.00	0.15	0.750 0.750			
		CH-0.300 KM	3	2.00	1.00	0.15	0.900			
		CH-0.400 KM	1	3.00	1.00	0.15	0.450			
		CH-0.500 KM	3	10.00	1.00 1.50	0.30 0.30	3.000 2.53			
			2	2.00	2.00	0.15	1.200			
		CH-0.550 KM	4	1.00	1.00	0.15	0.600			
		CH-0.600 KM	1	10.00	1.50 1.10	0.15	2.250			
	1300	CH-0.650-KM	1	24.00 20.00	1.00	0.30 0.30	4.8 9.000			
		CH-0.700 KM	1	1.00	1.00	0.15	0.150			
		CH-0.800 KM	1	1.00	1.00	0.15	0.150			
		CH-0.850 KM	1	10.00	1.50	0.30 0.30	3.0 4.500			
		CH-0.900 KM	6	1.00	1.00	0.15	0.900			
		CH-0.950 KM	3	1.00	1.00	0.15	0.450			
		CH-1.000 KM	6	1.00	1.00	0.15 0.15	0.900 0.900			
		CH-1.050 KM	1	3.00	1.50	0.15	0.675			
			8	1.00	1.00	0.15	1.200			
		CH-1.200 KM	1	10.00	1.00	0.30	3.000			
			7	1.50	1.00	0.15	1.575			
		CH-1.300 KM	1	5.00	1.00	0.15	0.750			
			1	8.0 10.00	1.00	0.30 0.30	3.000 3.000			
	1200		2	1.00	1.00	0.15	0.300			
		CH-1.350 KM	1	8.00	3.75	0.15	4.500			
			1	5.00	2.3 3.75	0.15	1.725 2.813			

Ator Rec
Culcut

		1	10.00	1.00	0.30	3.000
		5	1.00	1.00	0.15	0.750
	CH-1.500 KM	1	7.00	1.00	0.15	1.050
		1	1.00	3.75	0.15	0.563
	CH-1.550 KM	1	1.00	1.00	0.15	0.150
	CH-1.600 KM	2	1.00	1.00	0.15	0.300
	CH-1.700 KM	2	8.00	1.00	0.15	2.400
		1	5.00	1.00	0.15	0.750
	CH-1.750 KM	2	10.00	1.00	0.15	3.000
		1	4.00	1.00	0.15	0.600
	CH-1.800 KM	1	1.00	1.00	0.10	0.100
	CH-1.850 KM	2	1.00	1.00	0.15	0.300
		1	1.00	1.00	0.15	0.150
	CH-2.000 KM	1	5.00	3.75	0.20	3.750
		1	2.00	2.00	0.10	0.400
	CH-2.050 KM	2	2.00	1.50	0.15	0.900
	CH-2.100 KM	1	42.00 46.00	3.00	0.20 0.1	18.0 27.600
		1	5.00	3.00	0.10	1.500
	CH-2.200 KM	6	1.00	1.00	0.10	0.600
	CH-2.300 KM	1	3.00	2.00	0.15	0.900
		4	1.00	1.00	0.10	0.400
	CH-2.350 KM	1	2.00	3.00	0.10	0.600
	CH-2.4000 KM	2	3.00	2.50	0.15	2.250
		1	1.00	1.00	0.10	0.100
	CH-2.600 KM	1	4.00	2.00	0.10	0.800
	CH-2.900 KM	3	1.00	1.00	0.10	0.300
	CH-2.950 KM	1	2.00	1.00	0.10	0.200
		4	1.00	1.00	0.10	0.400
	CH-3.000 KM	1	10.00	2.00	0.15 0.1	2.5 2.000
		1	10.00	1.00	0.15	1.500
		1	3.00	1.00	0.10	0.300
	CH-3.300 KM	2	5.00	2.00	0.15	3.000
		2	5.00 10.00	2.50 3.00	0.15 0.1	2.75 4.500

	CH-3.500 KM	1	3.00	1.00	0.20	0.600			
		1	40.00	2.00	0.30	11.700			
	CH-3.600 KM	3	2.00	1.00	0.15	4.200			
	CH-3.650 KM	1	6.00	2.00	0.15	3.450			
						153.925	Cum	1939.93	227591.00

[Signature]
20/11/21
JE
RWD BENIPATTI
HARAKHIS

[Signature]
20/11/21
AE
RWD BENIPATTI
HARAKHIS

117.319 Add GST 12% Rs= 35832- 273112
Add Labour Cess 1% Rs= 2986 22762
Add Signorage Fee (50.025x1032x10%) Rs= 15747 121072
Total Rs= 353169
117.319
EE 30/11/21
RWD BENIPATTI

check & confirm

[Signature]
20.12.2021
JE

[Signature]
20/12/2021
A.E

[Signature]
20/12/21
E.E

Post-facto T/F awarded for dt. 269285.00
(dt. Two lacs sixty nine thousand two hundred
Eighty five only.)
Reference letter no. 233 dated 21/2/22
of EE Darrbanga-2

[Signature]
Superintending Engineer
RWD Works Circle, Darrbanga

11
Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection :- 20.12.21 Name of PIU :- RWD (W) Div. Dankhanya 2
Name of Block :- NARLAKHI
Name of Road :- BORHAR TO SIMHA TOL
For Road :-

1. Damage Location/ Chainage :- from CH- 0.030Km to CH- 3.650km
2. Damage Length :- 466.5m
3. Nature of Damage :- Pot holes due to flood

4. Details of Restoration Works :-

- i. Material being used in Restoration Works : Brick Bats
ii. Equipment's/ Tools being used in Restoration Works : Tractor & Roller
iii. Procedure taken up in Restoration Works : Filling & Compaction
iv. Restored Length : 466.5m

Remarks :- Work found satisfactory

[Signature]
20.12.21
Signature of JE/AE

[Signature]
20/12/21
Signature of E.E