

**Estimate for Restoration work of Road from T02 SH to Gorhaniya Road for the year 2021-2022
in Bisfi Block**

Length-4.597 KM

Sr NO.	Item of Work								
1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching in slope or apron including including light ramming etc. all complete as per approved design,specification and direction of E/I (Brick Bats)								
ch	Nos	Length	Width	Height	Quantity	Unit	Rate	Amounts	
1850-2500	1	9.00 ✓	1.25 ✓	0.15 ✓	1.688 ✓				
	1	22.00 ✓	2.75 ✓	0.30 ✓	18.15 ✓				
	1	5.00 ✓	2.60 ✓	0.60 ✓	7.80 ✓				
	1	9.00 ✓	3.75 ✓	1.00 ✓	33.75 ✓				
	1	25.00 ✓	3.75 ✓	0.30 ✓	28.13 ✓				
	1	6.00 ✓	2.75 ✓	0.75 ✓	12.38 ✓				
less HP	-1	0.503 ✓	3.75 ✓		-1.89 ✓				
	1	L = 76.503 mtr. ✓			76.503	100.00	M3	1939.93	148410 193997.607
2	Supplying and fixing of 600 MM dia Rume Pipeas per dir of E/I 76.503 mtr								
	1	2.50 ✓	2.00 ✓		5.00 ✓	2371.56	RM	11857.8	
	1	(8/60X7.94X25+35.09)							160268 205855
						Total		2470	

Add 12% GST

Add 1% L/Cess

Add Signorance Fee(100x1032x10%)

Total

=Rs

=Rs

=Rs

=Rs

19332.24703

1603 = 2059

7895 = 10320

242937

00. Rs - 188998 = 00

Rhachan
JE
RWD
Bisfi

Amul
20/11/21
A E
RWD
Bisfi

amul
27/11/21
E E
RWD
Benipatti

Damaged length = 76.503 mtr.
HP pipe 600mm = 5.00 mtr.
Respral qty = 100.00 m³.
Verified and found correct


Amul
27/11/21
JE

Amul
27/11/2021
A E / Singhman

amul
27/11/21
E E

In
ate of
ame
ame
r R
1.
2
:

Name of Rd:- 702 SH Road to Goshang road.
Post facto T/B awarded for Rs. 188998.00 (Rs One
Lac eighty eight thousand nine hundred ninety eight
only.) Reference letter no. 233 dated 21/2/22
~~EE Darbhanga-2~~ of EE Darbhanga-2


Superintending Engineer:
RWD Works Circle, Darbhanga


Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection :- 27-11-2021 ^{to 5-11-2022} Name of PIU :- RWD (W) Div. Darbhanga-2
(Inspected)
Name of Block / PIU :- Bisfi (RWD (W) Div. Benipatti)
Name of Road :- T02 SH To Gorhaniya

For Road :-

1. Damage Location/ Chainage :- From ch. 1850 to 2500 Metre

2. Damage Length :- 76 Metre.

3. Nature of Damage :- Due to flood, pot patch develop & one breach found

4. Details of Restoration Works :-

i. Material being used in Restoration Works - Brick Bat and 600mm dia H.P. pipe.

ii. Equipment's/ Tools being used in Restoration Works - Tractor, Roller

iii. Procedure taken up in Restoration Works - Section-wise restoration work initiated/completed

iv. Restored Length - 76 Metre. & 5 Metre long H.P. pipe.

Remarks :- Work found satisfactory.

Signature of E.E.

Signature of JE/AE

W. W. W.
19/02/2022
JE