

Estimate for Restoration work of Road from Khangraitha to Chhotaki Patauna Road for the year 2021-2022 in Bisfi Block

Length-1.884 KM

Sr NO.	Item of Work							
1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching in slope or apron including including light ramming etc. all complete as per approved design, specification and direction of E/I (Brick Bats)							
Ch	Nos	Length	Width	Height	Quantity	Unit	Rate	Amounts
1.60km	1	8.50	3.00	0.90	22.95			
					22.95	Cum	1939.93	44521.3935
2	Supplying and fixing of 600 MM dia Hume Pipe as per direction of E/I							
	4	2.50			10	m	2371.56	23715.6
								68236.9935

L = 8.50 mtr.

Add 12% GST =Rs 8188.44
 Add 1% L/Cess =Rs 682.37
 Add Signorage Fee(174.7x1063x10%) =Rs 2368.44
 Total =Rs 79476.24

Grand Total = 79476.24

[Signature]
20/11/21

JE
RWD
Bisfi

[Signature]
20/11/21

AE
RWD
Bisfi

[Signature]
27/11/21

EE
RWD
Benipatti

Damage length = 8.50 mtr.

Qty = 22.95 m³.

H.P pipe of 600 mm dia
= 10 mtr.

Verified and found correct

[Signature]
27/11/21
JE

[Signature]
27/11/2021
A. Singh

[Signature]
27/11/21
EE

In

Date of

Name

Name


For

1

Name of Road:- Khargaittha To Chhotka
Palang Road.

Post facto T/s awarded for Rs. 79476.00
(Rs. Seventy nine thousand four hundred seventy
Six only.)

Reference letter no. 233 dated 21/2/22
of EE Darbhanga-2


Superintending Engineer
RWD Works Circle, Darbhanga


Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection :- 27.11.2021 Name of PIU :- RWD (W) Div. Darbhanga-2
 to 5.12.2021 (Inspected).
 Name of Block / PIU :- Bisti (RWD (W) Div. Benipatti.
 Name of Road :- Khangratha to Chhotaki Pithana.
 For Road :-

1. Damage Location/ Chainage :- CH 1.60 KM.

2. Damage Length :- 8.50 mtr.

3. Nature of Damage :- Due to flood, heavy rain part length of such road got damaged.

4. Details of Restoration Works :-

i. Material being used in Restoration Works :- Brick bats & NP3 pipe.

ii. Equipment's/ Tools being used in Restoration Works :- Tractor & Roller.

iii. Procedure taken up in Restoration Works :- section wise restoration work initiated/completed.

iv. Restored Length :- 8.50 meter, and 600 mm HR pipe - 5 Meter long.

Remarks :- none found satisfactory.

(Signature)
 19/10/22
 Signature of E.E

Signature of JE/AE

(Signature)
 19/10/22
 JE