



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

**HEAD-FDR/2245**

**STATE :- BIHAR**

**AA COPY**

**DISTRICT :- Madhubani**

**CIRCLE :- Darbhanga**

**BLOCK :- KHAJAULI**

**YEAR:- 2021-22**

**Estimate for Motorable in  
BIKRA BHATTA TO GOBRAURA CHAUCK  
under FDR**

**TOTAL LENGTH OF ROAD:-**

**1.009 KM**

**TOTAL COST FOR MOTORABLE**

**Rs. 494017.91**

**1,10,765**

Submitted by:  
Executive Engineer  
RWD(W) Division, Madhubani

## प्रतिवेदन

पथ का नाम	:-	<u>BIKRA BHATTA TO GOBRAURA CHA</u>
पथ की लम्बाई	:-	<u>1.009 KM</u>
प्राक्कलित राशि	:-	<u>494018- रु0</u> <u>1,10,765</u>
प्रमंडल का नाम	:-	<u>Madhubani</u>
अंचल का नाम	:-	<u>Darbhangha</u>
योजना का नाम	:-	<u>FDR-2245</u>


प्रस्तुत प्राक्कलन BIKRA BHATTA TO GOBRAURA CHAUCK पथ के लिए तैयार किया गया है जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/जलजमाव/Wave Cut के कारण क्षतिग्रस्त हो गया था। जिसके कारण आवागमन बाधित हो गया था। फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था।


यह प्राक्कलन सचिव, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक—मु0अ0—4 (मु0) विविध (कार्य) —23—60/2020—1937 पटना दिनांक 07.07.2021 के आलोक में तैयार किया गया है।


इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को मिट्टी एवं ईट के टुकड़ों से भरकर उसका सम्पीडन किया जाने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन वर्तमान स्वीकृति अनुसूचि दर पर तैयार किया गया है। यह कार्य लोकहित एवं जनहित में अत्यावश्यक है। अतः इस प्राक्कलन की स्वीकृति अपेक्षित है। यह कार्य विभागीय रूप से सम्पादित करा लिया गया है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर जो संवेदक लाभांश को छोड़कर था। उसे प्रावधान करते हुए तैयार किया गया है।

  
कनीय अभियंता

  
सहायक अभियंता

  
कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमण्डल, मधुबनी

**Estimate for Motorable in** BIKKA BHATTIA TO  
GORRAIRA CHAIICK

Length:- 1.009 KM

Item No	Name of Item	Unit	No	Length	Width	Height	Qty.	Rate	Amount
	Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I,	Cum	As per Appendix 1				<del>200.21</del> 46.76 m <sup>3</sup>	2004.96	<del>401411</del> 93,752 = 00
							Add GST 12%		<del>48169</del> 11 250
							Add L.Cess 1%		<del>4014</del> 938
							S Fee		<del>40424</del> 4825
							G. Total:-		<del>494018</del>

Total = 1,10,765

*[Signature]*  
23/10/21  
Junior Engineer  
RWD(W) Section  
KHAJAULI

*[Signature]*  
23/10/21  
Assistant Engineer  
RWD(W) Sub Division  
KHAJAULI

*[Signature]*  
23/10/21  
Executive Engineer  
RWD(W) Division, Madhubani

कुर्थापाल अग्रिमता क्लाउ का, वि. कार्य मॉडल - बिरोल के हाल  
समर्पित जाँच सतिवेदन के आधार पर

post facto T/S for, Rs. 10,765/- (Rupees  
ONE Lakh Ten Thousand And Seven Hundred sixty  
five) only

*[Signature]*  
Superintending Engineer  
R.W.D. (W) CIRCLE, DARBHANGA  
*[Signature]*



## Inspection Report of Flood Damage work

Name of PIUs:- Madhubani

Name of Block/ Road:- Khajauli/Bikra Bhatta to Gobaura Chowk

### A. For Road

1. Damage Location Chainage:- 0 to 1.00 km.
2. Damage Length :- 354 m
3. Nature of Damage :- Road with slope cuts
4. Details of Restoration Works


- i. Material being used in Restoration works:- Brick Bat ✓
- ii. Equipments's/Tools being used in Restoration works:-
- iii. Procedure taken up in Restoration works:- Brick Bat Filling ✓
- iv. Restored Length:- 354 m

### B. For Bridge


1. Damage Location Chainage:-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works

- i. Material being used in Restoration works:-
- ii. Equipments's/Tools being used in Restoration works:-
- iii. Procedure taken up in Restoration works:-
- iv. Restored Length:-

N/A

  
Signature of JE/AE/EE

Satisfactory

  
Signature  
(Name of Inspection)