

Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, Darbhanga Inspected by Benipur

Name of Block/Road:- Harpatti to Biuni

A. For Road

1. Damage Location Chainage:- 0 - 1.0, 4.0 - 5.0 km

2. Damage Length :- 335 m

3. Nature of Damage :- Road Surface damage

4. Details of Restoration Works

i. Material being used in Restoration works:- Brick bats

ii. Equipment's /Tools being used in Restoration works:- J.C.B / Tractor / Labour

iii. Procedure taken up in Restoration works:- Laying of brick bats with light tamping

iv. Restored Length:- 335 m

B. For Bridge

1. Damage Location Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works

i. Material being used in Restoration works:-

ii. Equipment's /Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:-

iv. Restored Length:-

N/A

Work Found Satisfactory.

Signature of JE/AE/EE

Shashi
11/12/21
AB

Signature

(Name of Inspection)

30/12/22

FDR

DISTRICT :-	DARBHANGA	
BLOCK :-	BAHADURPUR	
Name of Raad :-	Harpatti to Biuni.	
	Length of the Road:-	4.380 KM.
	Effective Length	0.335 KM.

GENERAL ABSTRACT OF COST

Sl No.	Item of Work				Amount
					(in Rs.)
1	Cost for restoration				3,70,609.13 / 3,92,606.05
2	Add 12 % GST				44,473.09 / 47,112.73
3	Add 1 % Labour Cess				3706.09 / 3,926.06
4	Seigniorage Fee	Quantity (in cum)	Rate (in Rs.)	%	
	(Br. Bats) in cum	200.192 189.22	1032.00	10.00	19,527.50 / 20,659.80
	Total cost:-				4,38,315.81 / 4,64,304.64
	Say Rs.				4,38,316.20 / 4,64,305.00

[Signature]
66.11.2021
Junior Engineer
Bahadurpur

[Signature]
6/11/21
Assistant Engineer
Bahadurpur

[Signature]
6/11/21
Executive Engineer
R.W.D.(W) Division, Darbhanga-1

कार्यपालक अभियंता बनीपुर के जॉय प्रतिकेदन के आधार पर
Technically sanctioned for Rs 4,38,316 = 00 (Rupees
four lac thirty eight thousand three hundred sixteen
only)

[Signature]
अधिक्षण अभियंता
कार्य अंचल, दरभंगा
Abhinav
26/02/22

Detailed estimate for making moterable road.

Name of Raad :- Harpatti to Biuni.
 BLOCK :- BAHADURUR
 DISTRICT :- DARBHANGA
 R.W.D. Works Division Darbhanga-1

Sl. No.	Item	Unit	No.	L		B		D/H				Quantity	Rate	Amount
				Length (m)	Breadth (m)	Breadth (m)	Av. Breadth (m)	Depth / Height (m)	Depth / Height (m)	Depth / Height (m)	Av. Depth / Height (m)			
1	Labour and Placing Brick Bats with Light raming including cost of brick bats by tractor													
				1st KM										
				Start from Fekla-Andama RD.										
		cum	1	7.00			1.30				0.075	0.683		
		cum	1	13.70			1.00				0.075	1.028		
		cum	1	10.50			0.90				0.075	0.709		
		cum	1	30.00	1.50	1.30	1.40				0.075	3.150		
		cum	1	11.00	0.50	1.50	1.00				0.075	0.825		
		cum	1	29.00			3.75	0.200	0.150		0.175	19.031		
		cum	1	15.00			1.00				0.150	2.250		
		cum	1	28.00	3.75	4.00	3.88	0.200	0.300		0.250	27.125		
		cum	1	30.00	3.75	4.00	3.88	0.250	0.300		0.275	31.969		
		cum	1	14.00	3.75	4.00	3.88	3.77		0.250	0.300	16.275	10.97	
		cum	1	15.00		3.8	3.75	0.200	0.300		0.250	14.063		
		cum	1	15.00			3.00	0.300	0.200		0.250	11.250		
		cum	1	5.50			3.30	0.150	0.200		0.175	3.176		
		cum	1	5.00			1.00	0.100	0.150		0.125	0.625		
		cum	1	5.00	0.90	1.00	0.95	0.100	0.150		0.125	0.594		
											121.78	432.751	2004.96	266160.95
														29976.00
				at Biuni in 5th KM										
		cum	1	23.50			3.75	0.150	0.200		0.175	15.422		
		cum	1	14.00	1.00	2.75	1.88	0.100	0.250		0.175	4.594		
		cum	1	2.00			1.00				0.200	0.400		
		cum	1	5.00			0.90				0.200	0.900		
		cum	1	29.00			3.30	0.300	0.200		0.250	23.925		
		cum	1	4.00			1.50				0.200	1.200		
		cum	1	24.00			3.50	0.200	0.300		0.250	21.000		
											67.441	1874.91	126445.10	
														392606.05

62.13

3,70,609.13

[Signature]
 06.11.2021
 Junior Engineer
 Bahadurpur

[Signature]
 6/11/21
 Assistant Engineer
 Bahadurpur

[Signature]
 Executive Engineer
 R.W.D.(W) Division, Darbhanga-1

Verified & found correct

[Signature]
 11-12-21
 JE

[Signature]
 11/12/21
 AE

[Signature]
 11/12/21
 JE