

ग्रामीण कार्य विभाग
बिहार, सरकार

पत्रांक - मु0अ0-4 (मु0) विविध कार्य-23-60/2020 -1937

पटना, दिनांक 07/07/2021

प्रेषक,

पंकज कुमार पाल (भा0प्र0से0)
सचिव

सेवा में,

सभी कार्यपालक अभियंता
ग्रामीण कार्य विभाग,

विषय- बाढ़ अतिवृष्टि से क्षतिग्रस्त पथों/पुलियों को यातायात लायक (Motorable) करने के संबंध में।

महाशय,

उपर्युक्त विषय के संबंध में निदेश दिया जाता है कि प्रमंडल अन्तर्गत सभी अभियंता बाढ़/अतिवृष्टि से क्षतिग्रस्त पथों का शत प्रतिशत निरीक्षण करेंगे। पथों/पुलियों के क्षतिग्रस्त भाग से पानी उतरते ही उसे यातायात लायक बनाने की कारवाई एवं Motorable किये जाने से पहले तथा Motorable कार्य के बाद का Real time, Geo tagged photographs को MIS पर तत्क्षण अपलोड किया जाना सुनिश्चित करेंगे। इन कार्यों को कराने हेतु कार्यपालक अभियंता पूर्ण रूप से जिम्मेवार होंगे। कार्य न कराने की स्थिति में उनके विरुद्ध अनुशासनिक कार्रवाई की बाध्यता होगी।

विश्वासभाजन

(पंकज कुमार पाल)

सचिव

ज्ञापांक- मु0अ0-4 (मु0) विविध कार्य-23-60/2020 -1937

पटना, दिनांक 07/7/2021

प्रतिलिपि:-सभी अधीक्षण अभियंता को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित। साथ ही उन्हें निदेश दिया जाता है कि वे लगातार अनुश्रवण एवं निरीक्षण करते हुए क्षतिग्रस्त भाग को अतिशीघ्र यातायात लायक बनवाने की कार्रवाई सुनिश्चित करेंगे।

सचिव

ज्ञापांक-मु0अ0-4 (मु0) विविध कार्य-23-60/2020 -1937

पटना, दिनांक 07/7/2021

प्रतिलिपि:-सभी मुख्य अभियंता, ग्रामीण कार्य विभाग को सूचनार्थ एवं लगातार अनुश्रवण करने हेतु प्रेषित।

सचिव

प्रतिवेदन

पथ का नाम :- L.R.P. (Taran) Balua Path including 3 Link Road Sityampur Sukhscha Daulatpur Bk
कार्य का नाम :- Daulatpur Karnad.

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।


संलग्न प्राक्कलन 14.07.2021 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त L.R.P. Taran Balua Path including 3
...पथ... में बाढ़ क्षतिग्रस्त मरम्मत मद से यातायात चालू करने हेतु तैयार किया गया है
जिसकी प्राक्कलित लागत 10.113 लाख है।
उक्त पथ का निर्माण MR 3054 योनान्तर्गत हुआ है एवं योजना अनुरक्षण
अवधि में 2021 पथ के कटे (क्षतिग्रस्त)

भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद
यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट
रूप से प्राक्कलन में दर्शाया गया है।

प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।


कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा,।


सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल, जोकिहाट


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, अररिया

Inspection Report for Flood Damage Work

1. Name of PIUs

: EE RWD WD Araria

2. Name Of Block / Road

: LRP (Tarai) - Balua path including 3 link
Roads: Shyampur - Sukhsena, Daulatpur link
Daulatpur - Karmad

A. For Road

1. Damage Location / Chainage

: Ch-5200

2. Damage Length

: 60.04

3. Nature Of Damage

: Flood

4. Details Of Restoration

:

i) Material Being Used In Restoration

: L-sand & Brick Bats

ii) Equipment / Tools Being Used In Restoration Works

: Tractor & JCB

iii) Procedure Taken Up In Restoration Works

: Filling all damaged portion of
Cust and flank with above materials

iv) Restored Length

: 60.04

B. For Bridge

1. Damage Location / Chainage

:

2. Damage Length

:

3. Nature Of Damage

:

4. Details Of Restoration

:

i) Material Being Used In Restoration

:

ii) Equipment / Tools Being Used in Restoration Works

:

iii) Procedure Taken Up In Restoration Works

:

iv) Restored Length

:

Work found satisfactory

Signature

Executive Engineer
(Name of Inspector)
Kishanganj-2

Signature of JE / AE / EE

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :-	LRP (Taran) - Balua Path via deulatpur including 3 Link Road Shyam Pur - Sukhseng, Dalatpur Link Daulatpur - Kamad,	
DISTRICT :-	Araria	
BLOCK :-	Jokihat	
Length of Road:-	13.25 km	
Length of Cutting:-	60.00Mtr	
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
Phase-1 & Phase-2		
1	Filling of local sand	288595.23
2	Labour for cutting 62mm to 75mm dia bamboo	0.00
3	Labour for fitting 62mm to 75mm dia bamboo	0.00
4	Labour for filling empty cement bags with local sand Nylon crate	0.00
5	Supplying of EC bag, of local sand	0.00
6	Supply and Carriage of brick bats	574710.80
7	Supply, laying and carriage of 1000 mm HPC	0.00
8	Granular Sub-base	0.00
	SUB TOTAL COST =	863306.03
	ADD GST @12% =	103596.72
	Add Labour cess @ 1% =	8633.06
	Seigniorage Fees @10% =	35782.79
	TOTAL (RS.) =	1011319.60

J.E. 20/12/21


20.12.2021
A.E.


20/12/21
E.E.

Ref. E.E. Letter No. 1457 Dt. 28.04.22

Technically Sanctioned For Rs. 10,11,319.60

(Rupees. Teen Lacs eleven thousand)


29/4/22
A.E.

Three hundred Ninety


Suprintending Engineer
Rural Works Department
Work Circle Kishanganj

ESTIMATE FOR REPAIRING / RESTORATION/ MAKING MOTORABLE ROADS DAMAGED DURING FLOOD

Phaes-1

NAME OF ROAD :-		LRP (Taran) - Balua Path via daulatpur									
DISTRICT :-		Araria									
BLOCK :-		Jokihat									
Length of Cutting:-		60.00 mtr									
Sl. No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)		
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge										
	At ch:-5200 m	cum	1	60.00	5.50	1.70	561.00				
	Deductionfor H.P 1000MM dia (1.23 x 1.23)=1.52	cum	0	0.79	1.52	7.50	0.00				
		cum			total qty :-		561.000	514.43	288595.23		

Sl. No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.								
	5250 H At ch. 2550 m	cum	1	60.00	5.00	0.88	265.00		

[illegible]

Calculation of Seigniorage Fees

NAME OF ROAD :-		LRP (Taran) - Balua Path via daulatpur			
DISTRICT :-		Araria			
BLOCK :-		Jokihat			
Sl. No.	DESCRIPTION OF ITEMS	QUANTITY	Unit	RATE (Rs.)	AMOUNT (Rs.)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge	561.00	cum	141.85	79577.85
2	Labour for fitting empty cement bags with loocal sand, stitching the bags and placing in Nylon crate of size (1 m X 1 m X 1 m)with lead of 150 M including supply of sutli etc. at site in dry portion all complete as per approved design, specification and direction of E/I	0.00	cum	141.85	0.00
3	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.	0.00	cum	141.85	0.00
4	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	265.00	cum	1050.00	278250.00
5	Granular Sub-base with Well Graded Material (Table 400.1)	0.00	cum	384.12	0.00
		A) SUB TOTAL =			357827.85
	Seigniorage Fees @10% of Basic Amount =				35783


J.E.


20.12.2021
A.E.

E.E