

RURAL WORKS DEPARTMENT

GOVT OF BIHAR



NAME OF WORKS :-

Bhuna - Masuria via Majgawan Part A

BLOCK :-

Jokihat

FDR

Rs. 4249122.30

YEAR(2021-22)

R.W.D., WORKS CIRCLE, Kishanganj

R.W.D., WORKS DIVISION, Araria

ग्रामीण कार्य विभाग
बिहार, सरकार

पत्रांक - मु0अ0-4 (मु0) विविध कार्य-23-60/2020 -1937

पटना, दिनांक 07/07/2021

प्रेषक,

पंकज कुमार पाल (भा0प्र0से0)
सचिव

सेवा में,


सभी कार्यपालक अभियंता
ग्रामीण कार्य विभाग,

विषय- बाढ़ अतिवृष्टि से क्षतिग्रस्त पथों/पुलियों को यातयात लायक (Motorable) करने के संबंध में।

महाशय,

उपर्युक्त विषय के संबंध में निदेश दिया जाता है कि प्रमंडल अन्तर्गत सभी अभियंता बाढ़/अतिवृष्टि से क्षतिग्रस्त पथों का शत प्रतिशत निरीक्षण करेंगे। पथों/पुलियों के क्षतिग्रस्त भाग से पानी उतरते ही उसे यातायात लायक बनाने की कारवाई एवं Motorable किये जाने से पहले तथा Motorable कार्य के बाद का Real time, Geo tagged photographs को MIS पर तत्क्षण अपलोड किया जाना सुनिश्चित करेंगे। इन कार्यों को कराने हेतु कार्यपालक अभियंता पूर्ण रूप से जिम्मेवार होंगे। कार्य न कराने की स्थिति में उनके विरुद्ध अनुशासनिक कार्रवाई की बाध्यता होगी।

विश्वासभाजन



(पंकज कुमार पाल)

सचिव

ज्ञापांक- मु0अ0-4 (मु0) विविध कार्य-23-60/2020 -1937

पटना, दिनांक 07/7/2021


प्रतिलिपि:-सभी अधीक्षण अभियंता को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित। साथ ही उन्हें निदेश दिया जाता है कि वे लगातार अनुश्रवण एवं निरीक्षण करते हुए क्षतिग्रस्त भाग को अतिशीघ्र यातायात लायक बनवाने की कार्रवाई सुनिश्चित करेंगे।


सचिव

ज्ञापांक-मु0अ0-4 (मु0) विविध कार्य-23-60/2020 -1937

पटना, दिनांक 07/7/2021

प्रतिलिपि:-सभी मुख्य अभियंता, ग्रामीण कार्य विभाग को सूचनार्थ एवं लगातार अनुश्रवण करने हेतु प्रेषित।


सचिव

22

प्रतिवेदन

पथ का नाम :- Bhuma Masuria Via Maghagawan Part - A

कार्य का नाम :-

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संलग्न प्राक्कलन 14.07.2021 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त Bhuma Masuria v/a Maghagawan
Part-A में बाढ़ क्षतिग्रस्त मरम्मति मद से यातायात चालू करने हेतु तैयार किया गया है

जिसकी प्राक्कलित लागत 42,49,122 मात्र है।

उक्त पथ का निर्माण MR.3654 योनान्तर्गत हुआ है एवं योजना अनुरक्षण

अवधि में नहीं पथ के कटे (क्षतिग्रस्त)

भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद
यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट

रूप से प्राक्कलन में दर्शाया गया है।

प्राक्कलन मदो का दर वर्तमान अनुसूचित दर के अनुरूप है।

20/12/21
कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा,

20.12.2021
सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल, जोफिया

20/12/21
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, अररिया

Inspection Report for Flood Damage Work

1. Name of PIUs

: E.E. R.W.D. Work's Dev. Area

2. Name Of Block / Road

: Jolihat / Bhung - Masuriga
Maggawan Part-A

A. For Road

1. Damage Location / Chainage

: Ch. 500m, 580m, 700m, 1600m, 1700m, 1710m,
2300m, 2400m, 2500m, 2550m,

2. Damage Length

: 183m.

3. Nature Of Damage

: crust Damaged

4. Details Of Restoration

:

i) Material Being Used In Restoration

: Local Sand, Bamboo, E.C. bag, Brick Bats

ii) Equipment / Tools Being Used In Restoration Works

: Tractor with Trolley

iii) Procedure Taken Up In Restoration Works

: filling all damaged portion of crust
and flank with above materials.

iv) Restored Length

: 183m.

B. For Bridge

1. Damage Location / Chainage

:

2. Damage Length

:

3. Nature Of Damage

:

4. Details Of Restoration

:

i) Material Being Used In Restoration

:

NA

ii) Equipment / Tools Being Used in Restoration Works

:

iii) Procedure Taken Up In Restoration Works

:

iv) Restored Length

:

Work found satisfactory

Signature


Executive Engineer
(In-charge of Inspector)
Kishanganj-2

Signature of JE / AE / EE

SUMMARY OF COST ESTIMATE FOR THE PROJECT		
NAME OF ROAD :-	Bhuna - Masuria via Majgawan Part A	
DISTRICT :-	Araria	
BLOCK :-	Jokihat	
Length of Road:-	3.25km	
Length of Cutting:-	183.0Mtr	
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
Phase-1		
1	Filling of local sand	935879.99
2	Labour for cutting 62mm to 75mm dia bamboo	227347.75
3	Labour for fitting 62mm to 75mm dia bamboo	36087.03
4	Labour for filling empty cement bags with local sand Nylon crate	0.00
5	Supplying of EC bag, of local sand	901234.94
6	Supply and Carriage of brick bats	1559946.74
7	Supply, laying and carriage of 1000 mm HPC	0.00
8	Granular Sub-base	0.00
	SUB TOTAL COST =	3660496.45
	ADD GST @12% =	439259.57
	Add Labour cess @ 1% =	36604.96
	Seigniorage Fees @10% =	112761.30
	TOTAL (RS.) =	4249122

J.E 20/12/21


20.12.2021
A.E


E.E 20/12/21

Ref. E.E. Letter No. 1457 Dt. 28/4/22

Technically Sanctioned For Rs. 42,49,122.00

(Rupees. Forty two Lacs forty nine thousand and

one hundred twenty two) Only


29/4/22


Superintending Engineer
Rural Works Department
Work Circle Kishanganj

ESTIMATE FOR REPAIRING / RESTORATION/ MAKING MOTORABLE ROADS DAMAGED DURING FLOOD

Phaes-1

NAME OF ROAD :-		Bhuna - Masuria via Majgawan Part A							
DISTRICT :-		Araria							
BLOCK :-		Jokihat							
Length of Cutting:-		183.00 Km							
Sl. No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge								
	At ch:-500 m	cum	1	18.00	(3+4.5)/2	(1.75+2.5+1.85)/3	137.25		
	At ch:-580 m	cum	1	19.50	(3.5+5.5)/2	(1.5+2.25+1.85)/3	163.80		
	At ch:-700 m	cum	1	15.00	(7+9.5)/2	(1.75+2.85+1.85)/3	266.06		
	At ch:-1600 m	cum	1	8.00	(6.5+8.5)/2	(1.95+2.65+1.85)/3	129.00		
	At ch:-1700 m	cum	1	15.00	(3+4.5)/2	(1.5+2.85+2.65)/3	131.25		
	At ch:-1710 m	cum	2	4.00	(2+3.5)/2	(1.75+2.6+0.85)/3	38.13		
	At ch:-2300 m	cum	2	16.00	(2+3.5)/2	(1.65+2.25+1.85)/3	168.67		
	At ch:-2400 m	cum	1	9.00	(7+9.5)/2	(1.65+2.85+1.85)/3	157.16		
	At ch:-2400 m	cum	1	15.50	(3+4.5)/2	(1.95+2.65+1.85)/3	124.97		
	At ch:-2500 m	cum	1	41.00	(3+4.5)/2	(1.5+2.5+1.65)/3	289.56		
	At ch:-2500 m	cum	2	11.00	(2.5+3.5)/2	(1.5+2.6+1.85)/3	130.90		
	At ch:-2550 m	cum	2	11.00	(2.5+3.5)/2	(0.65+2.25+0.85)/3	82.50		
		cum	total qty :-				1819.26	514.43	935879.99
2	Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- in -charge.								
	At ch:-500 m		1	75.00	3.50		262.50		

Sl. No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
	At ch:-700 m		2	75.00	3.50		525.00		
	At ch:-1600 m		2	40.00	3.50		280.00		
	At ch:-1700 m		1	75.00	3.50		262.50		
	At ch:-1710 m		2	20.00	3.50		140.00		
	At ch:-2300 m		2	80.00	3.50		560.00		
	At ch:-2400 m		2	45.00	3.50		315.00		
	At ch:-2400 m		1	77.50	3.50		271.25		
	At ch:-2500 m		1	205.00	3.50		717.50		
	At ch:-2500 m		2	55.00	3.50		385.00		
	At ch:-2550 m		2	55.00	3.50		385.00		
		Mtr.	total qty:-				4103.75	55.40	227,347.75
3	Labour for fitting & fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-charge.								
	At ch:-500 m		1	4.00	15.00		60.00		
	At ch:-700 m		2	5.00	15.00		150.00		
	At ch:-1600 m		2	6.00	8.00		96.00		
	At ch:-1700 m		1	4.00	15.00		60.00		
	At ch:-1710 m		2	5.00	4.00		40.00		
	At ch:-2300 m		2	6.00	16.00		192.00		
	At ch:-2400 m		2	4.00	9.00		72.00		
	At ch:-2400 m		1	6.00	15.50		93.00		
	At ch:-2500 m		1	4.00	41.00		164.00		
	At ch:-2500 m		2	5.00	11.00		110.00		
	At ch:-2550 m		2	6.00	11.00		132.00		
		Mtr.	total qty :-				1169.00	30.87	36087.03

Sl. No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
4	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.								
	At ch:-500 m	cum	1	15.00	(2.5+1.5)/2	(0.85+2.95+2.5)/3	63.00		
	At ch:-700 m	cum	2	15.00	(2.5+1.5)/2	(0.85+2.65+1.7)/3	104.00		
	At ch:-1600 m	cum	2	8.00	(1.85+0.9)/2	(0.75+3.5+2.25)/3	47.67		
	At ch:-1700 m	cum	1	15.00	(1.65+0.9)/2	(1.5+2.5+2.25)/3	39.84		
	At ch:-1710 m	cum	2	4.00	(2+0.9)/2	(1.6+2.25+2.25)/3	23.59		
	At ch:-2300 m	cum	2	16.00	(1.5+0.9)/2	(1.15+2.25+2.25)/3	72.32		
	At ch:-2400 m	cum	2	9.00	(2.5+1.5)/2	(2.5+2.85+1.75)/3	85.20		
	At ch:-2400 m	cum	1	15.50	(2+0.9)/2	(1.65+2.25+1.5)/3	40.46		
	At ch:-2500 m	cum	1	41.00	(2+1.25)/2	(2.75+2.5+1.5)/3	149.91		
	At ch:-2500 m	cum	2	11.00	(2+0.9)/2	(1.5+2.25+1.75)/3	58.48		
	At ch:-2550 m	cum	2	11.00	(2+2.5)/2	(2.65+2.25+2.45)/3	121.28		
	Total No of E C Bags(3.4cum=100Bags) =			805.74	/	0.034	23698.00		
		Each		Say No of Bage :-			23698.00	38.03	901234.940
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.								
	At ch:-500 m	cum	1	18.00	(3+3.5)/2	(0.75+0.75+0.85)/3	45.83		
	At ch:-580 m	cum	1	19.50	(3.5+4.5)/2	(0.5+0.75+0.85)/3	54.60		
	At ch:-700 m	cum	1	15.00	(7+8.5)/2	(0.75+1.15+0.85)/3	106.56		
	At ch:-1600 m	cum	1	8.00	(6.5+7.5)/2	(0.75+1.65+0.85)/3	60.67		

Sl. No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
	At ch:-1700 m	cum	1	15.00	(3+3.5)/2	(0.5+1.5+1.65)/3	59.31		
	At ch:-1710 m	cum	2	4.00	(2+2.5)/2	(0.75+1.45+0.85)/3	18.30		
	At ch:-2300 m	cum	2	16.00	(2+2.5)/2	(0.65+1.05+0.85)/3	61.20		
	At ch:-2400 m	cum	1	9.00	(7+8.5)/2	(0.65+0.95+0.85)/3	56.96		
	At ch:-2400 m	cum	1	15.50	(3+3.5)/2	(0.45+0.65+0.85)/3	32.74		
	At ch:-2500 m	cum	1	41.00	(3+3.5)/2	(0.5+1.5+0.65)/3	117.70		
	At ch:-2500 m	cum	2	11.00	(2.5+2.5)/2	(0.5+1.65+0.85)/3	55.00		
	At ch:-2550 m	cum	2	11.00	(2.5+2.5)/2	(0.65+1.25+0.85)/3	50.42		
		cum	total qty :-				719.29	2,168.72	1559946.74
							A) SUB TOTAL =		3660496.45
							TOTAL COST =		3660496.45

[Signature]
20.12.2024

Asstt. Engineer

[Signature]

Executive Engineer

[Signature]

Junior Engineer

S.E
Kishanganji

Calculation of Seigniorage Fees

NAME OF ROAD :-		Bhuna - Masuria via Majgawan Part A			
DISTRICT :-		Araria			
BLOCK :-		Jokihat			
Sl. No.	DESCRIPTION OF ITEMS	QUANTITY	Unit	RATE (Rs.)	AMOUNT (Rs.)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge	1819.26	Cum	141.85	258061.50
2	Labour for fitting empty cement bags with loocal sand, stitching the bags and placing in Nylon crate of size (1 m X 1 m X 1 m)with lead of 150 M including supply of sutli etc. at site in dry portion all complete as per approved design, specification and direction of E/I	0.00	Cum	141.85	0.00
3	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.	805.73	Cum	141.85	114293.08
4	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	719.29	Cum	1050.00	755258.44
5	Granular Sub-base with Well Graded Material (Table 400.1)	0.00	Cum	384.12	0.00
		A) SUB TOTAL =			1127613.02
		Seigniorage Fees @10% of Basic Amount =			112761

J.E


 20.12.2024
 A.E


 E.E

Bill of Quantity**Phase-1**

NAME OF ROAD :-		Bhuna - Masuria via Majgawan Part A		
DISTRICT :-		Araria		
BLOCK :-		Jokihat		
Sl. No.	DESCRIPTION OF ITEMS	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge	1819.26	514.43	935879.99
2	Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- in -charge.	4103.75	55.40	227347.75
3	Labour for fitting & fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-charge.	1169.00	30.87	36087.03
4	Labour for fitting empty cement bags with local sand, stitching the bags and placing in Nylon crate of size (1 m X 1 m X 1 m)with lead of 150 M including supply of sutli etc. at site in dry portion all complete as per approved design, specification and direction of E/I	0.00	1249.46	0.00
5	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.	23698.00	38.03	901234.94
6	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	719.29	2168.72	1559946.74

7	Supplaying and carriage of hume pipe 1000 mm dia , all complete job.	0.00	4425.07	0.00
8	Granular Sub-base with Well Graded Material (Table 400.1)	0.00	2,564.86	0.00
		A) SUB TOTAL =		3660496.45
		TOTAL COST =		3660496

 20/12/21
J.E

 20.12.2021
A.E


E.E

Bhuna - Masuria via Majgawan Part A

Executive Engineer
RWD (W) DIVISION
Araria

Assistant Engineer
RWD (W) DIVISION
Araria

J.E. 20112424
RWD (W) DIVISION
Araria