



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

MEHNDIBARI TO BELUNDA

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 5880		
DISTRICT	KATIHAR		
BLOCK	AZAMNAGAR		
DIVISION	MANIHARI		
TOTAL LENGTH OF ROAD		5.880	KM
TOTAL COST OF F.D.R. PART - A		Rs. 28.006	Lacs
ADD G.S.T @ 12%		Rs. 3.361	Lacs
ADD Labour Cess @ 1%		Rs. 0.280	Lacs
ADD Seigniorage Fee @ 10%		Rs. 1.456	Lacs
TOTAL COST OF RESTORATION WORK In Rs.		Rs. 33.102	Lacs


SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मगिइरी अन्तर्गत आन्नमनगर प्रखंड
पथ MEHANDIBARR TO BELAUNDA (.....) जो
विभागीय Online Morititring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के
कारण यातायात लायक Moterale हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य
विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-
2/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान
अपलोड करते हुए (Moterale) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में 2021 अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के
खड़े के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterale कार्य कराया गया है। MIS में
अपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से
नेकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में
आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का
हाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए
ए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की
छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन
में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।



ज्नीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशाखा,



सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल,

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल,

Inspection Report for flood damage work

Date:

1. Name of PIUs-

E.E. RND Nandikani

2. Name of Block/Road-

Azamnagar.

Mekandi beam TO Belawade.

A. For Road

1. Damage Location/Chainage :

500-21.

2. Damage Length :

81.70 m.

3. Nature of Damage :

Road cuts

4. Details of Restoration :

i Material being used in Restoration :

Tractor, Poth Patcher JCB, Bamboo

ii Equipment/Tools being used in Restoration works :

Bar.

iii Procedure taken up in Restoration works :

Manual.

iv Restored Length :

81.70 m.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works :

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AE/EE


Signature

(Name of Inspector)


GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : MEHNDIBARI TO BELUNDA
DISTRICT KATIHAR
DIVISION MANIHARI
BLOCK AZAMNAGAR
LENGTH OF ROAD (IN KM) 5.880

SI. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	2.245
2	HUME PIPE	0.242
3	BRIKCK BAT	23.095
4	SAND BAGS	1.689
5	BAMBOO WORK	0.735
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		28.006
Add G.S.T. @ 12%		3.361
Add Labour Cess @ 1%		0.280
Add Seigniorage Fee @ 10%		1.456
Total Cost of Restoration Work =		33.102


J.E.
RWD


A.E.
RWD


E.E.
RWD

Technically Sanctioned for Rs 33.102 lacs.
(Rupees thirty three lacs. ten thousand &
two hundred) only.


Superintendent Engineer
Rural Works Department
Works Circle, Purnea