

RURAL WORKS DEPARTMENT

GOVT OF BIHAR



NAME OF WORKS :- Hatta Chowk se Dugar Bandh Via Forbesganj part-A path

BLOCK :- Kursakanta

FDR

Rs. 4868389.10

YEAR(2021-22)

R.W.D., WORKS CIRCLE, Kishanganj

R.W.D., WORKS DIVISION, Araria

ग्रामीण कार्य विभाग
बिहार, सरकार

पत्रांक - मु0अ0-4 (मु0) विविध कार्य-23-60/2020 -1937

पटना, दिनांक 07/07/2021

प्रेषक,

पंकज कुमार पाल (भा0प्र0से0)
सचिव

सेवा में,

सभी कार्यपालक अभियंता
ग्रामीण कार्य विभाग,

विषय- बाढ़ अतिवृष्टि से क्षतिग्रस्त पथों/पुलियों को यातायात लायक (Motorable) करने के संबंध में।

महाशय,

उपर्युक्त विषय के संबंध में निदेश दिया जाता है कि प्रमंडल अन्तर्गत सभी अभियंता बाढ़/अतिवृष्टि से क्षतिग्रस्त पथों का शत प्रतिशत निरीक्षण करेंगे। पथों/पुलियों के क्षतिग्रस्त भाग से पानी उतरते ही उसे यातायात लायक बनाने की कारवाई एवं Motorable किये जाने से पहले तथा Motorable कार्य के बाद का Real time, Geo tagged photographs को MIS पर तत्क्षण अपलोड किया जाना सुनिश्चित करेंगे। इन कार्यों को कराने हेतु कार्यपालक अभियंता पूर्ण रूप से जिम्मेवार होंगे। कार्य न कराने की स्थिति में उनके विरुद्ध अनुशासनिक कार्रवाई की बाध्यता होगी।

विश्वासभाजन

(पंकज कुमार पाल)

सचिव

ज्ञापांक- मु0अ0-4 (मु0) विविध कार्य-23-60/2020 -1937

पटना, दिनांक 07/7/2021

प्रतिलिपि:-सभी अधीक्षण अभियंता को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित। साथ ही उन्हें निदेश दिया जाता है कि वे लगातार अनुश्रवण एवं निरीक्षण करते हुए क्षतिग्रस्त भाग को अतिशीघ्र यातायात लायक बनवाने की कार्रवाई सुनिश्चित करेंगे।

सचिव

ज्ञापांक-मु0अ0-4 (मु0) विविध कार्य-23-60/2020 -1937

पटना, दिनांक 07/7/2021

प्रतिलिपि:-सभी मुख्य अभियंता, ग्रामीण कार्य विभाग को सूचनार्थ एवं लगातार अनुश्रवण करने हेतु प्रेषित।

सचिव

Inspection Report for Flood Damage Work

1. Name of PIUs : E.E.R.I.D (W) division, Arasia.
2. Name Of Block / Road : Kussabanta / Hattia Chowk to dungar baidh
via fortifying post - A.
- A. For Road
1. Damage Location / Chainage : CH - 5900 M, 5100 M
2. Damage Length : 310 M.
3. Nature Of Damage : flank & crust washed out.
4. Details Of Restoration :
- i) Material Being Used In Restoration : Local sand & Brick bats.
- ii) Equipment / Tools Being Used In Restoration Works : Tractor & others.
- iii) Procedure Taken Up In Restoration Works : manual.
- iv) Restored Length : 310 M.

B. For Bridge

1. Damage Location / Chainage :
2. Damage Length :
3. Nature Of Damage :
4. Details Of Restoration :
- i) Material Being Used In Restoration :
- ii) Equipment / Tools Being Used in Restoration Works :
- iii) Procedure Taken Up In Restoration Works ::
- iv) Restored Length :

wash found satisfactory.

Signature of JE / AE / EE

Signature
Executive Engineer
(Name of Inspector)
Kishanganj-2

SUMMARY OF COST ESTIMATE FOR THE PROJECT		
NAME OF ROAD :-	Hatta Chowk se Dugar Bandh Via Forbesganj part-A path	
DISTRICT :-	Araria	
BLOCK :-	Kursakanta	
Length of Road:-	6.80km	
Length of Cutting:-	310Mtr	
Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Filling of local sand	954370.54
2	Labour for cutting 62mm to 75mm dia bamboo	0.00
3	Labour for fitting 62mm to 75mm dia bamboo	0.00
4	Labour for filling empty cement bags with local sand Nylon crate	0.00
5	Supplying of EC bag, of local sand	0.00
6	Supply and Carriage of brick bats	3193808.88
7	Supply, laying and carriage of 1000 mm HPC	0.00
8	Granular Sub-base	0.00
	SUB TOTAL COST =	4148179.42
	ADD GST @12% =	497781.53
	Add Labour cess @ 1% =	41481.79
	Seigniorage Fees @10% =	180946.36
	TOTAL (RS.) =	4868389

[Signature]
28/12/02
J.E

[Signature]
A.E

[Signature]
29/12/02
E.E

Ref. E.E. Letter No. 145-T Dt. 28/04/022

S.E (48,68,389 ~)

Technically Sanctioned For Rs. forty eight lakh

(Rupees. sixty eight thousand three hundred)

28
29/12/22
A.E




eighty nine Only

[Signature]
28/12/02

अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज

ESTIMATE FOR REPAIRING / RESTORATION/ MAKING MOTORABLE ROADS DAMAGED DURING FLOOD


NAME OF ROAD :-		Hatta Chowk se Dugar Bandh Via Forbesganj part-A path							
DISTRICT :-		Araria							
BLOCK :-		Kursakanta							
Length of Cutting:-		310Mtr							
Sl. No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge								
	At ch:-5900M	cum	1	12.00	(5.5+7.5)/2	(1.45+2.15+1.85)/3	141.70		
	At ch:-6100M	cum	1	298.00	(5+6.5)/2	(0.85+1+1.15)/3	1713.50		
		cum		total qty :-			1855.20	514.43	954370.54
2	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.								
	At ch:-5900M	cum	1	12.00	(5.5+7.5)/2	(0.6+1.15+0.85)/3	67.60		

Sl. No.	DESCRIPTION OF ITEMS	Unit	Nos.	L(m)	B(m)	D(m)	QUANTITY	RATE (Rs.)	AMOUNT (Rs.)
	At ch:-6100M	cum	1	298.00	(5+6.5)/2	(0.85+0.86+0.75)/3	1405.07		
		cum	total qty :-				1472.67	2,168.72	3193808.88
							A) SUB TOTAL =		4148179.42
							TOTAL COST =		4148179.42
	<div style="display: flex; justify-content: space-between; align-items: center;"> <div>  Junior Engineer </div> <div>  Asstt. Engineer </div> <div>  Executive Engineer </div> </div>								

S.E
Kishanganj

Calculation of Seigniorage Fees

NAME OF ROAD :-					
Hatta Chowk se Dugar Bandh Via Forbesganj part-A path					
DISTRICT :-					
Araria					
BLOCK :-					
Kursakanta					
Sl. No.	DESCRIPTION OF ITEMS	QUANTITY	Unit	RATE (Rs.)	AMOUNT (Rs.)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge	1855.20	cum	141.85	263160.12
4	Labour for fitting empty cement bags with loocal sand, stitching the bags and placing in Nylon crate of size (1 m X 1 m X 1 m)with lead of 150 M including supply of sutli etc. at site in dry portion all complete as per approved design, specification and direction of E/I	0.00	cum	141.85	0.00
5	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.	0.00	cum	141.85	0.00
6	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	1472.67	cum	1050.00	1546303.50
8	Granular Sub-base with Well Graded Material (Table 400.1)	0.00	cum	384.12	0.00
A) SUB TOTAL =					1809463.62
Seigniorage Fees @10% of Basic Amount =					180946



J.E



A.E




E.E

Bill of Quantity


NAME OF ROAD :-					Hatta Chowk se Dugar Bandh Via Forbesganj part-A path				
DISTRICT :-					Araria				
BLOCK :-					Kursakanta				
Sl. No.	DESCRIPTION OF ITEMS				QUANTITY	RATE (Rs.)		AMOUNT (Rs.)	
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge				1855.20	514.43		954370.54	
2	Labour for cutting 62 mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer- in -charge.				0.00	55.40		0.00	
3	Labour for fitting & fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-charge.				0.00	30.87		0.00	
4	Labour for fitting empty cement bags with local sand, stitching the bags and placing in Nylon crate of size (1 m X 1 m X 1 m)with lead of 150 M including supply of sutli etc. at site in dry portion all complete as per approved design, specification and direction of E/I				0.00	1249.46		0.00	
5	Supplying of EC bag, filling of local sand stitching and placing in position as the direction of Engineer-in-charge.				0.00	38.03		0.00	
6	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				1472.67	2168.72		3193808.88	

7	Supplaying and carriage of hume pipe 1000 mm dia , all complete job.	0.00	4425.07	0.00
8	Granular Sub-base with Well Graded Material (Table 400.1)	0.00	2,564.86	0.00
		A) SUB TOTAL =		4148179.42
		TOTAL COST =		4148179


28/12/07

J.E


A.E


29/12
B.E

RATE ANALYSIS FOR CARRIAGE OF BASE MATERIAL
Hatta Chowk se Dugar Bandh Via Forbesganj part-A path

Hatta Chowk se Dugar Bandui via 100																
---	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

J.E
J.E
 RWD (W) DIVISION
 Araria

[Signature]
Assistant Engineer
 RWD (W) DIVISION
 Araria

Executive Engineer
 RWD (W) DIVISION
 Araria