



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L076- T02 TO BISARE (DIVERSION)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1763	
DISTRICT	KATIHAR	
BLOCK	PRANPUR	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	1.763	KM
TOTAL COST OF F.D.R. PART - A	Rs. 25.737	Lacs
ADD G.S.T @ 12%	Rs. 3.088	Lacs
ADD Labour Cess @ 1%	Rs. 0.257	Lacs
ADD Seigniorage Fee @ 10%	Rs. 1.401	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 30.483	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मनिहारी अन्तर्गत प्राणपुर प्रखण्ड
के पथ 1076-702 से विसार (.....) जो

विभागीय Online Monitoring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक **Moterable** हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में2021..... अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु **Moterable** कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक 29/10/21 का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, प्राणपुर


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, प्राणपुर


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date:

1. Name of PIUs-

→ E.C. RD, Manihari

2. Name of Block/Road-

→ Prampur, Lot 6 - 102 to Bigare

A. For Road

1. Damage Location/Chainage : CH — 1.0 km.

2. Damage Length : 127 m

3. Nature of Damage : wash out to

4. Details of Restoration : Bricks bag filling

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Brick bag
Trowel, JCB,
127 m

B. For Bridge

1. Damage Location/Chainage : N/A

2. Damage Length

3. Nature of Damage

4. Details of Restoration

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L076- T02 TO BISARE (DIVERSION)

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK PRANPUR

LENGTH OF ROAD (IN KM) 1.763

SI. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRIKCK BAT	25.737
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		25.737
Add G.S.T. @ 12%		3.088
Add Labour Cess @ 1%		0.257
Add Seigniorage Fee @ 10%		1.401
Total Cost of Restoration Work =		30.483

[Signature]
J.E.
RWD

[Signature] 20/11/24
A.E.
RWD

[Signature] 20/11
E.E.
RWD

*Technically Sanction for Rs 30.483 lacs (Rupees
thirty lacs forty eight thousand three
Hundred) only.*


[Signature] 14/11/24
Superintendent Engineer
Rural Works Department
Works Circle, Purnea


निरीक्षण प्रतिवेदन


अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ के पत्रांक 1388 दिनांक 01.12.2021 में दिये गये निर्देश के आलोक में दिनांक 15/12/22 से दिनांक 20/12/22 तक ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ अन्तर्गत ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी, में प्राणपुर प्रखंड के वर्ष 2021 की बाढ़ से निम्नलिखित क्षतिग्रस्त पथों के Temporary Restoration कार्य के स्थल का निरीक्षण किया गया एवं इन कार्यों को प्राक्कलन के अनुरूप पाया गया। कार्य की वर्तमान स्थिति संतोषजनक है एवं पथ इस स्थलो पर मोटेरेबल है।

Sl No	Block	Name of Road	Length	T.A. Amount
1	Pranpur	L059-T02 Balua Santhali	1.067	29.938
2	Pranpur	L076-T02 To Bisare (Diversion)	1.763	30.483
3	Pranpur	L022 To Bhembra (Diversion)	3.100	35.852
4	Pranpur	Sahaja Halt To Chikni Tola Satara Road	4.000	37.282
5	Pranpur	S069 PWD Roshna To Teli Tola Ward No. 1,2	1.157	13.227
6	Pranpur	Kewatia Bastaul To Sonaili PWD Road To Baina	10.000	49.511
7	Pranpur	L061-T02 To Guni Tola (Diversion)	0.761	39.482
8	Pranpur	S070 MMGSY Road To Sikatiya Santhali	1.311	20.293
9	Pranpur	L032-T02 To Amdaul (Track 12)	2.250	39.829
10	Pranpur	RWD Road Barbitta To Pachbargah	6.000	3.570
11	Pranpur	L038 Khushru Chowk To Khurah Tola Hawar	1.600	26.061
12	Pranpur	L038 To Jhapra Tola	1.447	4.845
13	Pranpur	L038 To Pokhar Tola	1.150	8.772
14	Pranpur	Hafila To Pranpur	14.400	7.128
15	Pranpur	T02 To Sadapur	1.885	12.510
16	Pranpur	NH-81 Khushapur To Sonaila	4.950	14.561
17	Pranpur	T02 To Belgachhi	0.730	13.617


कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल प्राणपुर


सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल प्राणपुर


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल मनिहारी


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल बारसोई