



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

S0136 URAOON TOLA TO CHAMAPARA ^{ISHERMARA} ~~BHEMMARA~~

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1500	
DISTRICT	KATIHAR	
BLOCK	MANSAHI	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	1.500	KM
TOTAL COST OF F.D.R. PART - A	Rs. 3.033	Lacs
ADD G.S.T @ 12%	Rs. 0.364	Lacs
ADD Labour Cess @ 1%	Rs. 0.030	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.165	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 3.592	Lacs


SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मनिहारी अन्तर्गत मनसाही..... प्रखंड के पथSO136 URAON TOLA TO CHAMAPARA BHERMARA.. (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में2021..... अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक 21.11.21..... का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।


प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।


25/11/21

कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशाखा, मनसाही.....


25-11-21

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल, मनसाही.....


25/11/21

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल, मनिहारी.....

Inspection Report for Flood Damage work

Date:

1. Name of PIUs- E.E. RND, Wode's Division Nausahi,

2. Name of Block/Road- Nausahi,

A. For Road 50136 Uraen Tola To Champara Bhermarra.

1. Damage Location/Chainage : At 0 to 150 M

2. Damage Length : 40 M.

3. Nature of Damage : road cutting

4. Details of Restoration : Brick Bats

i Material being used in Restoration : Brick Bats

ii Equipment/Tools being used in Restoration works: Tractor, JCB etc.

iii Procedure taken up in Restoration works : Brick bats filling and rolling.

iv Restored Length : 40 M.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :


i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :


Signature of JE/AE/EE


25.11.21
JE


Signature

(Name of Inspector)


26/11

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : S0136 URAOON TOLA TO CHAMAPARA BHEMMRA

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK MANSAHI

LENGTH OF ROAD (IN KM) 1.500

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRIKCK BAT	3.033
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		3.033
Add G.S.T. @ 12%		0.364
Add Labour Cess @ 1%		0.030
Add Seigniorage Fee @ 10%		0.165
Total Cost of Restoration Work =		3.592

[Signature]
J.E.
RWD

[Signature]
25-11-21
A.E.
RWD

[Signature]
E.E.
RWD

Technically Sanction for Rs. 3.592 Lac (Rs.)

Crare. Three Lac Fifty Nine


Thousand. Two Hundred.) Only

[Signature]
Superintendent Engineer
Rural Works Department
Works Circle, Purnea

निरीक्षण प्रतिवेदन

अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ के पत्रांक 1388 दिनांक 01.12.2021 में दिये गये निर्देश के आलोक में दिनांक 25/12/22 से दिनांक 30/12/22 तक ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ अन्तर्गत ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिसाही, में मनसाही प्रखंड के वर्ष 2021 की बाढ़ से निम्नलिखित क्षतिग्रस्त पथों के Temporary Restoration कार्य के स्थल का निरीक्षण किया गया एवं इन कार्यों को प्राक्कलन के अनुरूप पाया गया। कार्य की वर्तमान स्थिति संतोषजनक है एवं पथ इस स्थलों पर मोटरेबल है।

SI No	Block	Name of Road	Length	T.A. Amount
1	Mansahi	L057-T05 To Kajra	1.700	9.248
2	Mansahi	S036 (Parastawit Sampark) Chamapara (Bhemra) Sadak More To Raghobpur	1.500	29.267
3	Mansahi	PMGSY Mansahi Kursel Rakha Tola To Ramiya Tola Miyapur	1.896	9.564
4	Mansahi	S0136 Uraon Tola To Chamapara Bhemra	1.500	3.592
5	Mansahi	L043-T03 To Bhemra	3.500	6.828
6	Mansahi	Katihar Sarifganj To Mansahi (Marangi)	6.500	4.095
7	Mansahi	L073-Mansahi Kewala Situated On Mansahi Hat To Kursel To Saheb Nagar (Track 73)	2.300	14.493 7.930
8	Mansahi	PMGSY Lahsa To Gobra Ghat	2.041	8.431
9	Mansahi	Nawabganj Mansahi REO Road To Uraon Tola	3.250	9.524
10	Mansahi	PWD Road Bakhripur To Katihar Manihari RCD Road At Kajra (RRP-II) Bridge Diversion	0.066	20.777 10.541
11	Mansahi	Mansahi Hat To Kursel	4.600	4.075


06/01/22
कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल मनसाही


06.01.22
सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल मनसाही


06.01.22
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल मनिसाही


कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल बारसोई