



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

DAMAIKOL TO GOJHAWAT

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 3564	
DISTRICT	KATIHAR	
BLOCK	AZAMNAGAR	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	3.564	KM
TOTAL COST OF F.D.R. PART - A	Rs. 21.442	Lacs
ADD G.S.T @ 12%	Rs. 2.573	Lacs
ADD Labour Cess @ 1%	Rs. 0.214	Lacs
ADD Seigniorage Fee @ 10%	Rs. 1.141	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 25.370	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मनिहारी अन्तर्गत आजमगार प्रखंड पथ दुमई कील से राजौरा (.....) जो भागीय Online Morititring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य भाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक- /10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान ग्लोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

स्त निर्देश के आलोक में 2021 अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के डबे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में ग्लोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से कलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में वश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का इल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

नीय अभियंता

मीण कार्य विभाग

कार्य प्रशाखा, आजमगार

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल, आजमगार

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date:

1. Name of PIUs-

EE RWD HANIHARI

2. Name of Block/Road-

Azamnagar

Damachol To Washnol

A. For Road

1. Damage Location/Chainage : 0.750 M

2. Damage Length : 24 M

3. Nature of Damage : sand cut

4. Details of Restoration :

i Material being used in Restoration Brick balls

ii Equipment/Tools being used in Restoration works: Tractor & JCB

iii Procedure taken up in Restoration works : Manual

iv Restored Length : 24 M

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AE/EE

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : DANDAROL TO GOWANAHAT
DISTRICT : PATNABUR
DIVISION : MANMADH
BLOCK : AZARABAGAN
LENGTH OF ROAD (IN KM) : 3.554


Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	5.555
2	TRUNK PIPE	5.485
3	BRICK BAT	20.557
4	SAND BAGS	5.555
5	BAMBOO WORK	5.555
6	STEEL LATHA SHEET	5.555
TOTAL COST OF PROJECT =		21.442
Add G.S.T. @ 12%		2.573
Add Labour Cost @ 1%		0.214
Add Salvageage Fee @ 10%		1.141
Total Cost of Restoration Work =		25.370


J.E.
RWD


A.E.
RWD


RWD

Technically Sanctioned for Rs. 25.370 lac.
(Rupees. Twenty five hundred thirty seven thousand) only


Superintendent Engineer
Rural Works Department
Works Circle, Purnea