



# ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

## DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

KUMARIPUR RCD ROAD BHADUPRPUR

### DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

|                                       |            |      |
|---------------------------------------|------------|------|
| ROAD LENGTH                           | 0 TO 14100 |      |
| DISTRICT                              | KATIHAR    |      |
| BLOCK                                 | MANIHARI   |      |
| DIVISION                              | MANIHARI   |      |
| TOTAL LENGTH OF ROAD                  | 14.100     | KM   |
| TOTAL COST OF F.D.R. PART - A         | Rs. 35.765 | Laes |
| ADD G.S.T @ 12%                       | Rs. 4.292  | Laes |
| ADD Labour Cess @ 1%                  | Rs. 0.358  | Laes |
| ADD Seigniorage Fee @ 10%             | Rs. 1.939  | Laes |
| TOTAL COST OF RESTORATION WORK In Rs. | Rs. 42.354 | Laes |

SUBMITTED BY  
The Executive Engineer,  
Works Division, Manihari

## प्रतिवेदन


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मनिहारी अन्तर्गत मनिहारी प्रखण्ड के पथ Kumarapur Bcd Road to Bahadurpur (.....) जो विभागीय Online Monitoring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में मनिहारी अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के रोड़वे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक 10-11-2021 का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

  
कनीय अभियंता

ग्रामीण कार्य विभाग  
कार्य प्रशाखा, मनिहारी

  
सहायक अभियंता

ग्रामीण कार्य विभाग  
कार्य अवर प्रमंडल, मनिहारी

  
कार्यपालिका अभियंता

ग्रामीण कार्य विभाग  
कार्य प्रमंडल, मनिहारी

Inspection Report for Flood damage work

Date:

1. Name of PUs- RWD Manihari

2. Name of Block/Road- Manihari/ Kumaripur RCD Road to Bahadurpur

A. For Road

1. Damage Location/Chainage : At different Chainage

2. Damage Length : 279m 153M

3. Nature of Damage : Shoulder, surface of Road

4. Details of Restoration

i Material being used in Restoration

: Brick Puts,

ii Equipment/Tools being used in Restoration works

: Trowel

iii Procedure taken up in Restoration works

iv Restored Length

: 279m 153M

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works

iii Procedure taken up in Restoration works

iv Restored Length

  
Signature of JE/AE/EE

Sat 25/11/24  
AR

  
28/11

  
Signature

(Name of Inspector)

# GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD: KUMARPUR BCT ROAD BHADRAJPHUR

DISTRICT: KATHMANDU


DIVISION: MANHARI

BLOCK: MANHARI

LENGTH OF ROAD (IN KM): 14.100

| Sl. No.                          | ITEM OF WORK     | AMOUNT (LAKHS) |
|----------------------------------|------------------|----------------|
| 1                                | EARTH WORK       | 0.000          |
| 2                                | HUMI PIPE        | 0.182          |
| 3                                | BRICK BAT        | 15.803         |
| 4                                | SAND BAGS        | 0.000          |
| 5                                | BAMBOO WORK      | 0.000          |
| 6                                | STEEL DRUM SHEET | 0.000          |
| TOTAL COST OF PROJECT =          |                  | 35.785         |
| Add G.S.T. @ 12%                 |                  | 4.292          |
| Add Labour Cess @ 1%             |                  | 0.358          |
| Add Seigniorage Fee @ 10%        |                  | 1.939          |
| Total Cost of Restoration Work = |                  | 42.354         |

  
J.E.  
RWD

  
A.E.  
RWD

  
E.E.  
RWD

Technically Sanction for Rs. 42.354 Lacs (Rupees)

Cost Rs. Forty two Lacs Thirteen Paise

Total Rs. Four Hundred

  
Superintendent Engineer  
Rural Works Department  
Works Circle, Purnea

## निरीक्षण प्रतिवेदन

अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ के पत्रांक 1388 दिनांक 01.12.2021 में दिये गये निर्देश के आलोक में दिनांक 15.12.2021 से दिनांक 28.12.2021 तक ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ अन्तर्गत ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी, में अमदाबाद, मनसाही, मनिहारी, प्राणपुर एवं आजमनगर प्रखंड के वर्ष 2021 की बाढ़ से निम्नलिखित क्षतिग्रस्त पथों के Temporary Restoration कार्य के स्थल का निरीक्षण किया गया एवं इन कार्यों को प्राक्कलन के अनुरूप पाया गया। कार्य की वर्तमान स्थिति संतोषजनक है एवं पथ इस स्थलो पर मोटेरेबल है।

### प्रखंड :- मनिहारी


| Sl No | Block    | Name of Road                                                                                           | Length | T.A. Amount |
|-------|----------|--------------------------------------------------------------------------------------------------------|--------|-------------|
| 1     | Manihari | MMGSY Road To Badi Baigachi Gaon                                                                       | 0.960  | 3.437       |
| 2     | Manihari | PWD Road To Mirkil Tola                                                                                | 1.200  | 6.680       |
| 3     | Manihari | MMGSY Road To Sreejan Tola                                                                             | 0.100  | 2.126       |
| 4     | Manihari | MMGSY Road To Kaliganj                                                                                 | 0.105  | 1.452       |
| 5     | Manihari | Malkain Ghat To Terasi Tola                                                                            | 1.100  | 15.212      |
| 6     | Manihari | Kumaripur To Adiwasi Tola Hote Hue Baigachi Tak                                                        | 3.450  | 3.126       |
| 7     | Manihari | HL RCC Bridge With Approach Road On Near Tinkoriya Gram In To Narayan Gram Panchayat On Tinkoriya Dhar | 0.071  | 12.815      |
| 8     | Manihari | PMGSY Kumaripur To Sikarganj                                                                           | 1.115  | 5.132       |
| 9     | Manihari | S0100 To Mandir (Lakhi Tola Raghopur)                                                                  | 0.555  | 4.924       |
| 10    | Manihari | Dilarpur To Mahiyarpur                                                                                 | 4.500  | 5.263       |
| 11    | Manihari | Katihar Manihari PWD Road Mahiyarpur To Manoharpur                                                     | 6.180  | 4.420       |
| 12    | Manihari | PMGSY Road To English Tola                                                                             | 0.400  | 2.425       |
| 13    | Manihari | L045 Dilarpur Harl Chowk To Sahpur                                                                     | 12.490 | 49.087      |
| 14    | Manihari | Katihar Manihari PWD Road To Chaudhary Tola                                                            | 3.600  | 7.483       |
| 15    | Manihari | REO Road Baldiyabari Mirzapur To Kinara Tola                                                           | 2.350  | 12.876      |
| 16    | Manihari | PmanoharMMGSY Pagalbari Road To Sirsawadi Tak                                                          | 1.650  | 12.635      |
| 17    | Manihari | Approach on RCC Bridge On Kumaripur On RCD Road To Bhadurpur (Part II)                                 | 58.620 | 16.191      |



|    |          |                                                                                 |        |        |
|----|----------|---------------------------------------------------------------------------------|--------|--------|
| 18 | Manihari | Proposed PMGSY Road To Sohradangi Purab Tola Up To Kusha Ghat                   | 2.250  | 11.596 |
| 19 | Manihari | Bairgachhi To Kusha Tak Path Me Kusha Dhar Par 3x25 HL Bridge                   | 0.091  | 15.175 |
| 20 | Manihari | T05 To Abdullahpur                                                              | 0.972  | 7.730  |
| 21 | Manihari | PWD Manihari Amdabad Road To Chowdhari Tola Manoharpara Proposed Road Mali Tola | 2.108  | 12.459 |
| 22 | Manihari | Kumaripur Bhadurpur Road To Teghra Muslim Tola                                  | 1.170  | 8.275  |
| 23 | Manihari | MMGSY Borni To Borni Santhali                                                   | 0.696  | 1.457  |
| 24 | Manihari | Baghmara To Manihari                                                            | 3.000  | 5.438  |
| 25 | Manihari | Katihar Manihari PWD Road To Mara Tola                                          | 1.887  | 7.745  |
| 26 | Manihari | Kumaripur RCD Road To Bhadurpur                                                 | 14.100 | 42.354 |
| 27 | Manihari | PWD Lalbagh Chowk To Sij Ratanpur                                               | 1.988  | 12.462 |
| 28 | Manihari | PMGSY Road Bangri Tal To Bakar Tola                                             | 1.250  | 6.553  |
| 29 | Manihari | MMGSY Road Borni To Sohradangi Paschim Tola Maszid Tak                          | 1.350  | 3.429  |
| 30 | Manihari | Babu Lal Rishi To Karwar Dhar Kewala Panchayat                                  | 3.000  | 14.610 |
| 31 | Manihari | PMGSY Amdabad Road To Parasbani Santhali (Khajuriya Bishanpur)                  | 0.900  | 5.851  |
| 32 | Manihari | MMGSY Gogajhill Road To Surapur                                                 | 4.250  | 19.651 |
| 33 | Manihari | T04 To Dilarpur Seej                                                            | 2.950  | 10.647 |
| 34 | Manihari | PWD Katihar Manihari Road To Dagra Tola                                         | 1.433  | 18.992 |
| 35 | Manihari | REO Mansahi Road To Katothiya                                                   | 2.008  | 37.017 |
| 36 | Manihari | Surapar To Lahi Tola                                                            | 1.615  | 11.584 |
| 37 | Manihari | REO Road Nawaganj To Mansahi To Baghmara Milik                                  | 0.950  | 11.809 |
| 38 | Manihari | Pagalbari To Mahuar                                                             | 4.800  | 9.337  |
| 39 | Manihari | PMGSY Kuamripur Bhadurpur Road To Tinkoriya Uttar Tola                          | 1.210  | 15.796 |
| 40 | Manihari | Parasbani Santhali Tola To Bishanpur Manjhi Tola                                | 1.650  | 21.867 |
| 41 | Manihari | Katihar Manihari RCD Road Narayanpur Mushari                                    | 0.650  | 9.765  |
| 42 | Manihari | Kuamripur RCD Road To Bhadurpur Maltipur Bridge                                 | 0.059  | 9.458  |
| 43 | Manihari | Nawaganj To Marangi Road                                                        | 14.600 | 14.584 |
| 44 | Manihari | PMGSY Road To Mahuar                                                            | 0.720  | 4.321  |

|    |          |                                                                               |        |        |
|----|----------|-------------------------------------------------------------------------------|--------|--------|
| 45 | Manihari | PMGSY Nawabganj Simlapara Road To Nishad Tola                                 | 1.590  | 14.341 |
| 46 | Manihari | LO50-T03 Mednipur                                                             | 1.988  | 14.401 |
| 47 | Manihari | Karma Tola To Tala Tola                                                       | 1.350  | 4.520  |
| 48 | Manihari | REO Road Mirzapur To Lila Tola                                                | 2.983  | 19.331 |
| 49 | Manihari | PMGSY Road To Dilarpur Hat Chowk                                              | 1.980  | 9.196  |
| 50 | Manihari | Katihar Manihari RCD Road Nawabganj To Simlapara                              | 15.600 | 21.044 |
| 51 | Manihari | PMGSY Mahiyarpur To Baghaila Santhali                                         | 2.993  | 19.149 |
| 52 | Manihari | Mahiyarpur To Jagbatti                                                        | 2.500  | 6.010  |
| 53 | Manihari | Katihar Manihari PWD Road Balu Tola Kuti Tola                                 | 1.570  | 8.478  |
| 54 | Manihari | MMGSY Road To Kusha Ghat Choti Bairachi                                       | 4.450  | 28.113 |
| 55 | Manihari | Olipur Kundi To Chenga Gopalpur Luwa Road                                     | 2.900  | 34.825 |
| 56 | Manihari | PMGSY Kumaripur Bhadurpur Road To Chikni Santhali                             | 1.740  | 12.576 |
| 57 | Manihari | PMGSY Road Nawabganj Simlapara To Brindawan                                   | 1.790  | 23.741 |
| 58 | Manihari | Seej Moti Dhala Bandh Proposed Safi Santhali Road To Madari Chowk To Gopalpur | 1.150  | 4.055  |
| 59 | Manihari | Gogan Sah Inara At Manihari Amdabad PWD Road To Gogabil Jhil                  | 3.500  | 11.922 |

  
06/01/22  
कनीय अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल मनिहारी

  
06/01/22  
सहायक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल मनिहारी

  
06.01.22  
कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल मनिहारी

  
कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमंडल बारसोई