



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works & Development Department, Government of Bihar

48.

✶✶

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Madhepur

Estimate for Mortable of the Road from Lofa to Pachahi FDR at
Block- **Madhepur** in Madhubani District.

TOTAL COST FOR MOTORABLE Rs.

~~1-05004~~

~~2.86296~~ lac.

1.04867

Submitted by:
Executive Engineer
RWD(W) Division, Jhanjharpur

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- Madhepur

Name of Road :- Lofa to Pachahi

A. For Road

1. Damage Location Chainage (km):- 0.100, 0.25, 0.450, 0.85, 0.900

2. Damage Length :- ~~110 Mtr~~ 85.00m

3. Nature of Damage :-

4. Details of Restoration Works

i. Materials being used in restoration works:- Brick Ball

ii. Equipment's/Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:- 44.27 cum

iv. Restored Length:- ~~110 Mtr~~ 85.00m

B. For Bridge

1. Damage Location Chainage :-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works

i. Materials being used in restoration works:-

ii. Equipment's/Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:-

iv. Restored Length:-


C. Requirement Of New CD/ Bridges


i. Name of Road:-

ii. Location/ Chainage:-

iii. Type of CD Work/ Length required:-

Signature of JE/AE/EE


20/4/22
RR


26/04/20 22
JE

— S —


26/4
Signature
(Name of Inspection)

तकनीकी प्रतिवेदन

पथ का नाम :- Lofa to Pachahi

प्राक्कलित राशि :- 104867 lac

प्रमण्डल का नाम:- झंझारपुर

अंचल का नाम :- दरभंगा

योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक Lofa to pachahi पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।

यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीड़न किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लामांश छोडकर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।

3/5/11/21

कनीय अभियंता

5/11/21

सहायक अभियंता

5/11/21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर

Estimate for Motorability of road damaged by flood from Lofa to Pachahi For Year 2021

ad > FDR 2245

Length :- 1.38 km

Item No.	Name of Item	Unit	Quantity As per Appendix - I	Rate	Amount
	Providing and filling brick bats in ditches/damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	44.27 120.70	2004.96	88759.58 242004.94

88759.58
 Add 12 % GST ₹ 10651.15
 Add 1 % L.C ₹ 887.60
 Add S. Fee (120.70 x 1063.00) x 10 % ₹ 12830.74
 Total ₹ 105004.23
 Say ₹ 2,86,296.00

104867=00
 100756=00
 100757=00
 Executive Engineer
 R.W.D (W) Division,
 Jhanjharpur

05/11/21
 Junior Engineer
 R.W.D, Works Section,
 Madhepur

05/11/21
 Assistant Engineer
 R.W.D, Work sub Div.
 Madhepur


कार्यपालक अभियंता, मा. का. वि., जयनगर के द्वारा जंचोपरान्त
 पत्रांक- दिनांक- के आधार पर
 Technically Sanctioned for Rs. 105004 (Rupees One
 Lac five thousand four) only. for Rs. 100756=00 for Rs. 100757=00
 (Rupees one lac seven hundred fifty seven only) Abhinav

Superintending Engineer
 RWD Work Circle, Darbhanga

Abhinav
 05/10/22

कार्यपालक आशियाता ग्राम कान्विन जमनागर के जंचोपरात
पत्रांक 673(अ) दिनांक 29/04/22 के आधार पर

Technically sanctioned for Rs 104,867=00 (Rupees
one lac four thousand eight hundred sixty seven
—only)


Superintending Engineer
RWD Work Circle, Darbhanga

-Abhinav
05/05/22

Superintending Engineer
RWD Work Circle, Darbhanga

Name of Road :- Lofa to Pachahi

Length :- 1.38 km

Block :- Madhepur

Appendix - I

Measurement for restoration of Embankment and shoulder with Brick Bat (Measurement in mtr.)

Chainage	Nos.	Length (in Mtr.)	Bidth (in Mtr.)	Thickness (in Mtr.)	Quantity
ch. 900	2	17.00	(2.80+1.80)/2	2.30	(0.15+0.30)/2
ch. 900	1	15.00	(2.80+2.50)/2	2.65	(0.45+0.60)/2
ch. 900	4	8.00	(2.10+1.80)/2	1.95	(0.30+0.90)/2
ch. 850	1	2.00	(0.80+0.40)/2	1.50	0.15
ch. 450	1	20.00	(2.50+3.75+4.00)/2	5.62	(0.60+0.45)/2
ch. 450	1	19.00	(2.50+3.75)/2	4.45	0.60
ch. 250	1	10.00	(0.80+0.60)/2	0.70	0.15
ch. 100	1	12.00	(0.40+0.30)/2	0.35	(0.15+0.30)/2
ch. 100	1	14.00	(0.80+1.50)/2	1.15	0.30
Total qty.					120.70 cum

2.88 ✓
0.45 ✓
3.60 ✓
21.38 ✓
4.50 ✓
4.32 ✓
7.14 ✓

44.27 cum

26/04/21

35/11/21

Junior Engineer
R.W.D. Works Section,
Madhepur

26/11/21

Assistant Engineer
R.W.D. Work sub Div.
Madhepur

26/04/21

Executive Engineer
R.W.D (W) Division,
Jhanjharpur

26/04/21

26/4