



बिहार सरकार
ग्रामीण कार्य विभाग
Rural Work Department, Govt. of Bihar

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Madhepur

Estimate for Mortable of the Road from PARBALPUR - Kossi Bandh under FDR at Block- Madhepur in Madhubani District.

TOTAL COST FOR MOTORABLE	Rs.	0.70238 1.17403 lac.
--------------------------	-----	------------------------------------

Submitted by:
Executive Engineer
RWD(W) Division, Jhanjharpur

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- *Madhepur*

Name of Road :- *Parbalspur - kashi Bandh*

A. For Road

1. Damage Location Chainage :-
2. Damage Length :- *39.00 m*
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:- *Brick Bats*
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:- *28.910 m*
 - iv. Restored Length:-

B. For Bridge

1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required:-

— "S" —

[Signature]
29/04/22

Signature of JE/AE/EE

[Signature]
2056,
20/4/22
RR

[Signature]
29/4/22

Signature
(Name of Inspection)

तकनीकी प्रतिवेदन

पथ का नाम :- Parbalspur - Koshi Bandh

प्राक्कलित राशि :- 1.17403 Lacs

प्रमण्डल का नाम:- झंझारपुर

अंचल का नाम :- दरभंगा

योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक Parbalspur - Koshi Bandh पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।

यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीडन किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।

कनीय अभियंता

सहायक अभियंता

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर

Estimate for Motorability of road damaged by flood from PARBALPUR - Koss; Bandh For Year 2021

Head :- FDR 2245

Length :- 2.884 km

SI No.	Item No.	Name of Item	Unit	Quantity As per Appendix - 1	Rate	Amount
1		Providing and filling brick bats in ditches/ damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	49.52 28.917	2004.00	57977.43 99238.08

	₹	57977.43
		99,238.08
		6957.29
Add 12 % GST	₹	11,908.57
		2313.10
Add 1 % L.C	₹	992.38
28.917 1032		2984.23
Add S. Fee (15.60 x 1063.00) x 10 %	₹	5,263.98
		70238.05
Total	₹	1,17,403.01
		70238.00
Say	₹	1,17,403.00

Junior Engineer
R.W.D, Works Section,
Madhepur

Assistant Engineer
R.W.D, Work sub Div.
Madhepur

Executive Engineer
R.W.D (W) Division,
Jhanjharpur

कंसिपलक अभियंता, का का वि, जयनगर
जमीनपत्र नं. 678 के द्वारा दिनांक 4/5/2022
के आधार पर।

Seventy thousand two hundred thirty
eight (70,238.00) Only.

Superintending Engineer
RWD Work Circle, Darbhanga

Abhinav
07/05/22

Name of Road :- PARBALPUR - Kossi Bandh

Scheme :- **PMGSY** Length :- **2.884 km** Block :- **Madhepur**

Appendix - I

**Measurement for restoration of Embankment and shoulder with Brick Bat
(Measurement in mtr.)**

Chainage	Nos.		Length (in Mtr.)		Bidth (in Mtr.)		Thickness (in Mtr.)			Quantity	
ch. 550	1	x	4.00 ✓	x	$(0.5+1.5)/2$ ✓	x	$\frac{1.50+0.3}{2}$	av.	=	6.00	cum 3.60
ch. 500	1	x	2.00 ✓	x	2.00 ✓	x	$\frac{1.50+0.3}{2}$	av.	=	6.00	cum 3.60
ch. 450	1	x	8.00 ✓	x	$(0.5+1.0)/2$ ✓	x	$\frac{0.60+0.3}{2}$	av.	=	3.60	cum 2.70
ch. 1300	1		12.00 ✓	x	$\frac{1.80+0.3}{2}$ ✓	x	$(0.60+1.00)/2$	av.	=	17.28	cum 10.08
ch. 1700	1		13.00 ✓	x	$\frac{1.60+0.60}{2}$ ✓	x	$\frac{0.80+0.45}{2}$	av.	=	16.64	cum 8.937
							Total qty.		=	49.52	cum 28.917 ²³

Junior Engineer
R.W.D, Works Section,
Madhepur

Assistant Engineer
R.W.D, Work sub Div.
Madhepur

Executive Engineer
R.W.D (W) Division,
Jhanjharpur

[Signature]
25/04/22
28.

[Signature]
29/4

[Signature]
05/11/21

[Signature]
20/5/22
18/11/22