



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

162

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Madhepur

Estimate for Mortable of the Road from Daldal to Daldal
Mahadalit Tol **under FDR at Block- Madhepur** in Madhubani
District.

TOTAL COST FOR MOTORABLE Rs.

~~0.92338~~

3.79368 Lac.

0.92218

Submitted by:
Executive Engineer
RWD(W) Division, Jhanjharpur

तकनीकी प्रतिवेदन

पथ का नाम :- Daldal to Daldal Mahadalit Tol

प्राक्कलित राशि :- 3.79368

0.92218 lac

प्रमण्डल का नाम:- झंझारपुर

अंचल का नाम :- दरभंगा

योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक Daldal to Daldal Mahadalit Tol पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।

यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीडन किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।

31/11/21

कनीय अभियंता

31/11/21

सहायक अभियंता

31/11/21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- Madhepur

Name of Road :- Daldal to Daldal Mahadali to tol

A. For Road

1. Damage Location Chainage :-
2. Damage Length :- 124.00 m
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:- Brick Bat
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:- 38.93 cum
 - iv. Restored Length:- 485m


B. For Bridge


1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-


C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required:-

Signature of JE/AE/EE


24/4/22
RR


26/4/2022
JE


26/4/22
Signature
(Name of Inspection)

Estimate for Motorability of road damaged by flood from Daldal to Daldal Mahadalit Tol For Year 2021

Lead :- FDR 2245

Length :- 0.963 km

SI No.	Item No.	Name of Item	Unit	Quantity As per Appendix - 1	Rate	Amount
1		Providing and filling brick bats in ditches/damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	38.93 159.94	2004.96	78053.10 320678.31

₹ 78053.10
 320,678.31
 9366.37
 Add 12 % GST ₹ 38,481.40
 780.53
 Add 1 % L.C ₹ 3,206.78
 38.93 1032.00
 Add S. Fee (159.94 x 1063.00) x 10 % ₹ 17,001.89
 92338.26
 Total ₹ 3,79,368.38-92217.53
 92338.00
 Say ₹ 3,79,368.00
 92218.00

8511/21

Junior Engineer
R.W.D, Works Section,
Madhepur

(Signature)

Assistant Engineer
R.W.D, Work sub Div.
Madhepur

(Signature)
Executive Engineer
R.W.D (W) Division,
Jhanjharpur

कार्यालयक अवधिमा, गण का वि, जमनगर के द्वारा मौजूदा
पत्रांक - 671 (अ.प्र) दिनांक - 29/4/22 के आधार पर

Technically Sanction for Rs-92218.00 (Rupees Ninty
two thousand two hundred eighteen) Only.

(Signature)
Superintending Engineer
RWD Work Circle, Darbhanga
Abhinav
05/05/22

Name of Road :- Daldal to Daldal Mahadalit Tol


me :-
MMGSY[SC]
Length :- 0.963 km
Block :- Madhepur

Appendix - I

**Measurement for restoration of Embankment and shoulder with Brick Bat
(Measurement In mtr.)**

Chainage	Nos.	Length (In Mtr.)	Bldth (In Mtr.)	Thickness (In Mtr.)	Quantity
CH.	1	22.00	(1.5+0.9)/2	1.20	27.06 cum
	1	6.00	(1+1.5)/2	1.25	7.88 cum
	1	7.00	(0.4+0.3)/2	0.35	1.47 cum
	1	22.00	(3.2+2.8)/2	3.00	36.30 cum
	1	15.00	(1+1.2)/2	1.10	9.90 cum
	1	9.50	(2.5+0.8)/2	1.15	12.88 cum
	1	10.00	(1.8+1.6)/2	1.65	11.20 cum
	1	10.00	(1.00+2.20)/2	2.80	18.20 cum
	1	14.00	(1.5+2.0)/2	2.40	20.40 cum
	1	15.00	(3.5+2.6)/2	3.50	27.30 cum
		48.50m			
				Total qty.	159.94 cum


38.93 Cum


 05/11/21
 Junior Engineer
 R.W.D, Works Section,
 Madhepur


 5/11/21
 Assistant Engineer
 R.W.D, Work sub Div.
 Madhepur


 26/04/2022
 3-369
 19/4/22
 Executive Engineer
 R.W.D (W) Division,
 Jhanjharpur


 26/04/22
 JE


 26/4/22