



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

142

**HEAD-FDR**

STATE :- BIHAR

**DETAILED PROJECT REPORT**

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Madhepur

Estimate for Motorable of the Road from Paswan to Mallah Tol  
under FDR at **Block- Madhepur** in Madhubani District.

TOTAL COST FOR MOTORABLE Rs.

0.23356

4.98930 lac.

Submitted by:

Executive Engineer

RWD(W) Division, Jhanjharpur

## Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- Madhepur

Name of Road :- Paswan To Mallah Tol

### A. For Road

1. Damage Location Chainage :- 0-200, 250, 270, 320
2. Damage Length :- ~~83.0m~~ 15.90m
3. Nature of Damage :- Flood
4. Details of Restoration Works
  - i. Materials being used in restoration works:- Brick Bats
  - ii. Equipment's/Tools being used in Restoration works:- Tractor
  - iii. Procedure taken up in Restoration works:- 9.86 Cum
  - iv. Restored Length:- ~~83.0m~~ 15.90m


### B. For Bridge

1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
  - i. Materials being used in restoration works:-
  - ii. Equipment's/Tools being used in Restoration works:-
  - iii. Procedure taken up in Restoration works:-
  - iv. Restored Length:-

### C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required:- \_\_\_\_\_ 8 \_\_\_\_\_

Signature of JE/AE/EE

  
ER

  
29/01/23 JB

  
Signature  
(Name of Inspection)

तकनीकी प्रतिवेदन

पथ का नाम :- Parwan To Mallah Tol

प्राक्कलित राशि :- 4.98930 Lacs

प्रमण्डल का नाम:- झंझारपुर

अंचल का नाम :- दरभंगा

योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक Parwan To Mallah

Tol

पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।

यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईंट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीडन किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।



कनीय अभियंता



सहायक अभियंता



कार्यपालक अभियंता  
ग्रामीण कार्य विभाग,  
कार्य प्रमण्डल, झंझारपुर


Estimate for Motorability of road damaged by flood from Paswan to Mallah Tol For Year 2021


Length :- 2.115 km


ad :- FDR 2245

Item No.	Name of Item	Unit	Quantity As per Appendix - 1	Rate	Amount
1	Providing and filling brick bats in ditches/damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E.I.	Cum	9.86 <del>210.35</del>	2004.96	19768.91 <del>421743.34</del>

₹ 19768.91  
~~421743.34~~  
 Add 12 % GST ₹ 2272.27  
 Add 1 % L.C ₹ 197.65  
 Add S. Fee 10 % ₹ 4217.43  
 Total ₹ 1017.55  
~~22360.21~~  
~~23356.42~~  
 Total ₹ 498,930.17  
 Say ₹ 23356.00  
~~498,930.00~~


  
 Junior Engineer  
 R.W.D, Works Section,  
 Madhepur

  
 Assistant Engineer  
 R.W.D, Work sub Div.  
 Madhepur

  
 Executive Engineer  
 R.W.D (W) Division,  
 Jhanjharpur

कार्यवाहक अभियंता, रा. का. वि., ज.  
 जहाँजहारपुर पं. 678 के कार्यालय में 4/5/22  
 के कार्यालय पर।

Estimated For Rs. 23356=00  
 Twenty three thousand three hundred fifty  
 Six Only  
 Only

  
 Superintending Engineer  
 RWD Work Circle, Darbhanga

Abhinav  
 07/05/22

Name of Road :- Paswan to Mallah Tol

MINSY

Length :- 2.115 km

Block :- Madhepur

Appendix - I

Measurement for restoration of Embankment and shoulder with Brick Bat  
(Measurement in mtr.)

Chainage	Nos.	Length (in Mtr.)	Bidth (in Mtr.)	Thickness (in Mtr.)	Quantity	
ch 0	1	15.00 <del>20.00</del>	2.40 <sup>3.50</sup>	0.45 0.20	av. = 20.50	cum 3.40
ch 200 m	1	15.00 <del>20.00</del>	2.40 0.80	0.45 0.20	av. = 20.95	cum 0.24
ch 250 m	1	8.00	2.00	0.80	av. = 12.80	cum
ch 270 m	2	18.00 <del>16.00</del>	2.00 <sup>3.10</sup>	0.75 0.15	av. = 48.00	cum 1.22
ch 320 m	2	13.00	3.00	1.00	av. = 78.00	cum
					Total qty.	= 210.35 cum 9.86

*[Signature]*  
3/5/11/21

Junior Engineer  
R.W.D, Works Section,  
Madhepur

*[Signature]*  
5/11/21

Assistant Engineer  
R.W.D, Work sub Div.  
Madhepur

*[Signature]*  
29/04/22  
JE

Executive Engineer  
R.W.D (W) Division,  
Jhanjharpur

*[Signature]*  
29/04/22  
JE

*[Signature]*  
29/04/22