



बिहार सरकार

ग्रामीण कार्य विभाग

(Rural Works Department, Government of Bihar)

766

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Madhepur

Estimate for Mortable of the Road from Kushwaha Tol
Sarswati Chowk to Bhaluahi Tola Pachahi **under FDR at**
Block- Madhepur in Madhubani District.

TOTAL COST FOR MOTORABLE	Rs.	2.83561 lac.
		0.49792

Submitted by:
Executive Engineer
RWD(W) Division, Jhanjharpur

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- Madhepur

Name of Road :- Kushwaha tol Sariswati chowk to Bhaluahi tol
Pachahi

A. For Road

1. Damage Location Chainage :-
2. Damage Length :- 54.50 m
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:- Brick Bats
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:- 21.02 cum
 - iv. Restored Length:- 44.0m

B. For Bridge


1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-


C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required:-

Signature of JE/AE/EE


26/04/22
JE


27/4/22
RB


Signature
(Name of Inspection)

तकनीकी प्रतिवेदन

पथ का नाम :- Kushnaha Tol Sarswati Chowk to Bhalahi Tola Pachahi

प्राक्कलित राशि :- 2.83561 lac

प्रमण्डल का नाम:- झांझारपुर

अंचल का नाम :- दरभंगा


योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक Kushnaha Tol Sarswati Chowk to Bhalahi पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।

यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीड़न किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।



कनीय अभियंता



सहायक अभियंता



कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झांझारपुर

**Estimate for Motorability of road damaged by flood from Kushwaha Tol Sarswati Chowk to
Bhaluahi Tola Pachahi For Year 2021**

Lead :- FDR 2245

Length :- 0.650 km

Sl No.	Item No.	Name of Item	Unit	Quantity As per Appendix - I	Rate	Amount
1		Providing and filling brick bats in ditches/ damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/L.	Cum	21.02 119.55	2004.96	42144.26 239692.97

42144.26
₹ 2,39,692.97

Add 12 % GST ₹ 5057.31

Add 1 % L.C ₹ 2169.26

Add S. Fee (21.02 x 1032) x 10 % ₹ 2169.26

Total ₹ 2,83,561.22

Say ₹ 2,83,561.00

[Signature]

Junior Engineer
R.W.D, Works Section,
Madhepur

[Signature]

Assistant Engineer
R.W.D, Work sub Div.
Madhepur

[Signature]

Executive Engineer
R.W.D (W) Division,
Jhanjharpur

कार्यपालक अभियंता, ग्रा. का. वि., नयनगर के द्वारा
जांचोपरांत पत्रांक-671(मधुबनी) दि. 4/5/22 के आधार पर

Technically Sanctioned for Rs 49792.00 (Rupees
Forty nine thousand seven hundred ninety two) only.

[Signature]
Superintending Engineer
RWD Work Circle, Darbhanga

[Signature]
Abhinav
Assistant

Name of Road :- Kushwaha Tol Sarswati Chowk to Bhaluahi Tola Pachahi

ie :- GTSNY Length :- 0.650 km Block :- Madhepur

Measurement for restoration of Embankment and shoulder with Brick Bat
(Measurement in mtr.)

Chainage	Nos.		Length (in Mtr.)		Bldth (in Mtr.)		Thickness (in Mtr.)			Quantity	
ch. 0.165 km	1	x	14.00 14.00	x	1.00+0.3/2 $(1.00+2.50+1.50)/3$	x	0.45 0.45	0.57 0.57	av.	=	4.10 4.10 cum
ch. 0.636 km	1	x	6.00	x	(2.85+3.75)/2 0.3+0.4/2	x	0.60 0.60	0.57 0.57	av.	=	13.50 13.50 cum
ch. 0.642 km	1	x	8.00	x	(0.60+0.90+0.60)/2 0.3	x	0.45 0.45	0.90 0.90	av.	=	1.26 1.26 cum
ch. 0.619 km	✓	x	16.00 16.00		(0.60+0.90+0.60)/2 0.3		0.45 0.45	0.70 0.70	av.	=	2.16 2.16 cum
			44.00m				Total qty.			=	119.55 cum

21.02 ✓

26/11/21
JE

3/5/11/21

Junior Engineer
R.W.D. Works Section,
Madhepur

26/11/21

Assistant Engineer
R.W.D. Work sub Div.
Madhepur

26/11/21
Executive Engineer
R.W.D (W) Division,
Jhanjharpur

26/11/21
JE

26/11/21