



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Madhepur

Estimate for Mortable of the Road from Madhepur Triveni chowk to Yadav tol under FDR at **Block- Madhepur** in Madhubani District.

TOTAL COST FOR MOTORABLE Rs.

0.06491 lac

~~3.19128~~ lac.

Submitted by:

Executive Engineer

RWD(W) Division, Jhanjharpur

तकनीकी प्रतिवेदन

पथ का नाम :- Madhepur Triveni Chowk to yadantol

प्राक्कलित राशि :- 0.06491 lac

प्रमण्डल का नाम:- झंझारपुर

अंचल का नाम :- दरभंगा

योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक Madhepur
Chowk
Triveni to yadantol. पथ के लिए तैयार किया गया है, जो

कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।

यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीडन किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।


कनीय अभियंता

सहायक अभियंता


20/4/21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर

Estimate for Motorability of road damaged by flood from Madhepur Triveni chowk to Yadav tol For Year 2021

Head :- FDR 2245

Length :- 1.125 km

SI No.	Item No.	Name of Item	Unit	Quantity As per Appendix - 1	Rate	Amount
1		Providing and filling brick bats in ditches/damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	2.74 134.55	2004.96	5493.59 269757.34

₹ 5493.59
~~2,69,757.34~~
 Add 12 % GST ₹ 659.23
~~32,370.88~~
 Add 1 % L.C ₹ 54.94
~~2,69,757.34~~
 Add S. Fee (134.55 x 1063.00) x 10 % ₹ 282.77
~~11,302.13~~
 2.74 1032
 Total ₹ 6490.53
~~3,19,127.93~~
 Say ₹ 6491.00
~~3,19,128.00~~

05/11/21

Junior Engineer
R.W.D, Works Section,
Madhepur

Assistant Engineer
R.W.D, Work sub Div.
Madhepur

20/11/21
 Executive Engineer
R.W.D (W) Division,
Jhanjharpur

कार्यालय कार्यपालक अभियंता, ग्रा. का. वि., जयनगर
 के द्वारा जाँचोपरांत पत्रांक - 673(म.प्र.) दिनांक 29/04/2022 के आधार पर

Technically Sanctioned for Rs. 6491.00 (Rupees
 Six thousand four hundred ninety one) only.

05/05/22
 Superintending Engineer
RWD Work Circle, Darbhanga

Name of Road :- Madhepur Triveni chowk to Yadav tol

Scheme :- MMGSY Length :- 1.125 km Block :- Madhepur

Appendix - I

Measurement for restoration of Embankment and shoulder with Brick Bat (Measurement in mtr.)

Chainage	Nos.	Length (In Mtr.)	Bidth (In Mtr.)	Thickness (In Mtr.)	Quantity	
ch. 200 to 900 m	2	3.00 3.00	2.80 0.40	0.15 0.65	av. = 12.74	cum 0.36
	1	8.00	(1.80+2.10+2.40)/3	0.85	av. = 14.28	cum
	1	5.00	2.50 0.40	0.25 0.75	av. = 9.38	cum 0.50
	1	12.00	2.80+3.10+2.50 0.45	0.80+0.70 0.25	av. = 25.20	cum 1.35
	1	10.00	2.80	0.65	av. = 18.20	cum
	1	5.90 15.00	2.60 0.60	0.15 0.85	av. = 33.15	cum 0.53
	1	12.00	2.40	0.75	av. = 21.60	cum
Total qty.					= 134.55	cum 2.74 cum

Junior Engineer
R.W.D. Works Section.
Madhepur

Assistant Engineer
R.W.D. Work sub Div.
Madhepur

Executive Engineer
R.W.D (W) Division.
Jhanjharpur

28/11/21
JE

28/11/21

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- Madhepur

Name of Road :- Madhepur Triveni Chowk to Yadav tal.

A. For Road

1. Damage Location Chainage :- 200 to 900M.
2. Damage Length :- ~~0.069 KM~~ 28.90m
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:- Brick - Bal's
 - ii. Equipment's/Tools being used in Restoration works:- Tractor & JCB.
 - iii. Procedure taken up in Restoration works:- 2.74 cum
 - iv. Restored Length:- ~~0.069 KM~~ 28.90m

B. For Bridge

1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required:-

Signature of JE/AE/EE


23/4/22
JE


23/4/22
RR


Signature
(Name of Inspection)