



बिहार सरकार

ग्रामीण कार्य विभाग

From Work to Welfare

117

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Andhrathari

Estimate for Mortable of the Road from L029-T01 TO
RAKHWARI (VR029) under FDR at Block- Andhrathari in
Madhubani District.

TOTAL COST FOR MOTORABLE Rs.

219488.00

5.68071-lac.

Submitted by:
Executive Engineer
RWD(W) Division, Jhanjharpur

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- *Andhrathan*

Name of Road :- *L029-TOL TO Rakhwan (VR029)*

A. For Road

1. Damage Location Chainage :- *0.25, 0.96, 1.050, 2.750, 3.500*
2. Damage Length :- *0.230 KM 156.00m*
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:- *Brick Bat*
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:- *92.63 cum*
 - iv. Restored Length:- *156.00 m*

B. For Bridge

1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required:-

Signature of JE/AE/EE

30/4/22
RR

N/A

52
02.5 m
m

Signature
(Name of Inspection)

तकनीकी प्रतिवेदन

पथ का नाम :- L029-T01 TO RAKHWARI (VR029)

प्राक्कलित राशि :- 5.68071

प्रमण्डल का नाम:- झंझारपुर

अंचल का नाम :- दरभंगा

योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक L029-T01 TO RAKHWARI (VR029) पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।

यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईंट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीड़न किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।

25/11/21

कनीय अभियंता

25/11/21

सहायक अभियंता

20/11/21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर

Estimate for Motorability of road damaged by flood from L029-T01 TO RAKHWARI (VR029) For Year 2021


Head :- FDR 2245


Length :-3.721 km

SI No.	Item No.	Name of Item	Unit	Quantity As per Appendix - I	Rate	Amount
1		Providing and filling brick bats in ditches/damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E ⁿ .	Cum	92.63 239.50	2004.96	185719.44 480187.92

₹ 185719.44
~~4,80,187.92~~
 22286.33
 Add 12 % GST ₹ ~~57,622.55~~
 18571.94
 Add 1 % L.C ₹ ~~4,801.88~~
 3559.42
 Add S. Fee (239.50 x 1063.00) x 10 % ₹ ~~25,458.85~~
 219422.39
 Total ₹ ~~5,68,071.20~~
 219422.00
 Say ₹ ~~5,68,071.00~~

8/11/21
Junior Engineer
R.W.D, Works Section,
Andhrathari



Assistant Engineer
R.W.D, Work sub Div.
Andhrathari


Executive Engineer
R.W.D (W) Division,
Jhanjharpur

नगरपालिका कार्यपालिका, काठमाडौं, नेपाल

जघोपस्थापना पत्र (628/31/22) द्वारा दिनांक 06/05/2022
के अन्तर्गत छ ।

Technically Sanctioned for Rs. 219422.00 (Two Lakh
nineteen thousand four hundred twenty two
Rupees Only).


Superintending Engineer
RWD Work Circle, Darbhanga

Abhinav
07/05/22

Name of Road :- L029-T01 TO RAKHWARI (VR029)

PMGSY

Length :- 3.721 km

Block :- Andhrathari

Appendix - I

Measurement for restoration of Embankment and shoulder with Brick Bat
(Measurement in mtr.)

Chainage	Nos.		Length (in Mtr.)		Bidth (in Mtr.)		Thickness (in Mtr.)		Quantity	
ch. 0.250 km	1	x	80.00 51.00	x	(2.50+1.00)/2 1.75	x	0.60 0.45	av. =	04.00	cum
ch. 0.960 km	1	x	10.00	x	(2.00+1.00)/2	x	1.50	0.50	av. =	7.50 cum
ch. 1.050 km	1	x	20.00 15.00	x	(2.50+1.50)/2 1.50	x	2.00 0.50	av. =	108.00	cum
ch. 2.750 km	1	x	10.00 10.00	x	(2.50+1.00)/2 1.75	x	0.50	av. =	35.00	cum
ch. 3.500 km	1	x	10.00	x	1.00	x	1.00	0.50	av. =	5.00 cum
Total qty.									=	239.50 cum

27.00

46.88

6.25

92.63

8/5/11/21

Junior Engineer
R.W.D, Works Section,
Andhrathari

8/5/11/21

Assistant Engineer
R.W.D, Work sub Div.
Andhrathari

2/5/11/21

Executive Engineer
R.W.D (W) Division,
Jhanjharpur

2/5/11/21