



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

CONSTRUCTION OF HL BRIDGE L030 OYA HAZI TOLA 2ND CUT (BR-16R-376)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 2875		
DISTRICT	KATIHAR		
BLOCK	AMDABAD		
DIVISION	MANIHARI		
TOTAL LENGTH OF ROAD	2.875	KM	
TOTAL COST OF F.D.R. PART - A	2.655 Rs. 4.048	Lacs	
ADD G.S.T @ 12%	Rs. 0.486 0.319	Lacs	
ADD Labour Cess @ 1%	Rs. 0.040 0.026	Lacs	
ADD Seigniorage Fee @ 10%	Rs. 0.189 0.025	Lacs	
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 4.763 3.025	Lacs	

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari


प्रतिवेदन

पथ का नाम :- L030 Oya Hazi Tola 2nd Cut (BR-16R-376)
पथ की लम्बाई :- 2.875 KM
प्राक्कलित राशि :- 3,02,54,763 Lac
वित्तीय वर्ष :- 2021-22 / FDR-2021
प्रखंड :- Amdabad


प्रस्तुत प्राक्कलन मो 4.763 लाख (चार लाख छियत्तर हजार तीन सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के L030 Oya Hazi Tola 2nd Cut पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)- 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में पुल के डायवर्सन कार्य हेतु तैयार किया गया है जिसमें मिट्टी भरकर पथ में आवागमन चालू किया गया है तथा नदी के तरफ Sand-Bag देकर डायवर्सन को कटाव से बचाया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs Manihari
2. Name of Block/Road Amdabad / LO30 oya hazi Tola 2nd Cut

A for Road

1. Damage location : At Diverion
2. Damage Length : 0.105 Km
3. Nature of Damage : Diverion
4. Details of Restoration :
 - i. Material being used in Restoration E/W, Sand bag
 - ii. Equipment/Tools being used in Restoration Works : Tractor
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length 0.105

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/AE/EE

Executive Engineer
Rural Works Department
Manihari

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : CONSTRUCTION OF HL BRIDGE L030 OYA HAZI TOLA 2ND CUT (BR-16R-376)

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 2.875

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	2.655
2	HUME PIPE	0.000
3	BRICK BAT	0.000
4	SAND BAGS	1.293
5	G.S.B.	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		4.048 2.655
Add G.S.T. @ 12%		0.486 0.319
Add Labour Cess @ 1%		0.040 0.026
Add Seigniorage Fee @ 10%		0.489 0.025
Total Cost of Restoration Work =		4.763

3.025

[Signature]
26/11/21
J.E.
RWD

[Signature]
26/11/21
A.E.
RWD

[Signature]
26/11
E.E.
RWD

Technically Sanction for Rs. 3.025 Lac (Rs.
 Crore. Three Lac. Two
 Thousand. Five Hundred. Only

[Signature]
Superintendent Engineer
Rural Works Department
Works Circle, Purnea