



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

CONSTRUCTION OF HL BRIDGE L030 OYA HAZI TOLA 3RD CUT (BR-16R-381)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 34.18		
DISTRICT	KATIHAR		
BLOCK	AMDABAD		
DIVISION	MANIHARI		
TOTAL LENGTH OF ROAD	0.034		KM
TOTAL COST OF F.D.R. PART - A	Rs. 11.588		Lacs
ADD G.S.T @ 12%	Rs. 1.391		Lacs
ADD Labour Cess @ 1%	Rs. 0.116		Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.570		Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 13.665		Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

पथ का नाम	:- L030 Oya Hazi Tola 3 rd Cut (BR-16R-381)
पथ की लम्बाई	:- 0.034 KM
प्राक्कलित राशि	:- 13.665 Lac
वित्तीय वर्ष	:- 2021-22 / FDR-2021
प्रखंड	:- Amdabad

प्रस्तुत प्राक्कलन मो0 13.665 लाख (तेराह लाख छियासठ हजार पाँच सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के L030 Oya Hazi Tola 3rd Cut पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक— मु0अ0-4 (मु0) विविध (कार्य)— 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन को पुल के डायवर्सन कार्य हेतु तैयार किया गया है जिसमें मिट्टी भरकर ब्रीक बैट का प्रावधान है तथा नदी के तरफ Sand Bag देकर डायवर्सन को कटाव से बचाया गया है।


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।



कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद



सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद



कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PUs Manihari
2. Name of Block/Road Amdabad / L030 Oya Hazi Tola 3rd cl.

A for Road

1. Damage location : At Diversion (4.5 km)
2. Damage Length : 0.175 km.
3. Nature of Damage : Diversion
4. Details of Restoration :
 - i. Material being used in Restoration Elw, Sand bags, brick bats
 - ii. Equipment/Tools being used in Restoration Works : Tractor, JCB
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length 0.175 km

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/AE/EE

Executive Engineer
Rural Works Department
Works Division, Manihari

Signature
(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : CONSTRUCTION OF HL BRIDGE L030 OYA HAZI TOLA 3Rd CUT (BR-16R-381)

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 0.034

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	4.424
2	HUME PIPE	0.000
3	BRICK BAT	4.975
4	SAND BAGS	2.189
5	G.S.B.	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
	TOTAL COST OF PROJECT =	11.588
	Add G.S.T. @ 12%	1.391
	Add Labour Cess @ 1%	0.116
	Add Seigniorage Fee @ 10%	0.570
	Total Cost of Restoration Work =	13.665

Cypre
26/11/21
J.E.
RWD

Cypre
26/11/21
A.E.
RWD

EE
26/11/21
RWD

Technically Sanctioned for Rs 13.665 Lac (Rs Thirteen
lacs Sixty Six Thousand Five hundred) only

[Signature]
Superintendent Engineer
Rural Works Department
Works Circle, Purnea