



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

CHANNI MORE PWD NEERPUR TO PAHARPUR

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1575	
DISTRICT	KATHIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	1.575	KM
TOTAL COST OF F.D.R. PART - A	Rs. 2.170	Laes
ADD G.S.T @ 12%	Rs. 0.260	Laes
ADD Labour Cess @ 1%	Rs. 0.022	Laes
ADD Seigniorage Fee @ 10%	Rs. 0.054	Laes
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 2.506	Laes

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन


पथ का नाम	:- Channi More PWD Neerpur To Pharpur
पथ की लम्बाई	:- 1.575 KM
प्राक्कलित राशि	:- 2.506 Lac
वित्तीय वर्ष	:- 2021-22 / FDR-2021
प्रखंड	:- Amdabad


प्रस्तुत प्राक्कलन मो0 2.506 लाख (दो लाख पचास हजार छः सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के **Channi More PWD Neerpur To Pharpur** पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)- 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में पथ के कटे हुए स्थान पर ब्रीक बैट एवं पथ में बने हुए गढ़ों में GSB डालकर पथ में आवागमन चालू किया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs Manihari
2. Name of Block/Road Amdabad / Channi More Road near Pan To Pharpur

A for Road

1. Damage location : 0.2, 0.85, 1.180
2. Damage Length : 0.105 km.
3. Nature of Damage : Ditches different places.
4. Details of Restoration :
 - i. Material being used in Restoration Bricks bats, G.S.B
 - ii. Equipment/Tools being used in Restoration Works : Tractor
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length 0.105 km

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/AE/EE

26/11/12
Executive Engineer
Rural Works Department
Manihari

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : CHANNI MORE PWD NEERPUR TO PAHARPUR

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 1.575

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BAT	0.188
4	SAND BAGS	0.000
5	G.S.B.	1.982
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		2.170
Add G.S.T. @ 12%		0.260
Add Labour Cess @ 1%		0.022
Add Seigniorage Fee @ 10%		0.054
Total Cost of Restoration Work =		2.506


J.E.
RWD



A.E.
RWD


E.E.
RWD

Technically Sanction for Rs. 2.506 Lac (Rs.

Crors. TWO Lac. Fifty

Thousand. SIX Hundred.


Superintendent Engineer
Rural Works Department
Works Circle, Purnea