



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

UTTARI AMDABAD TO TRIMOHANI MORE

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 2300		
DISTRICT	KATIHAR		
BLOCK	AMDABAD		
DIVISION	MANIHARI		
TOTAL LENGTH OF ROAD	2.300	KM	
TOTAL COST OF F.D.R. PART - A	Rs. 7.057	Lacs	
ADD G.S.T @ 12%	Rs. 0.847	Lacs	
ADD Labour Cess @ 1%	Rs. 0.071	Lacs	
ADD Seigniorage Fee @ 10%	Rs. 0.392	Lacs	
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 8.367	Lacs	

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

पथ का नाम	Uttari Amdabad To Trimohani More
पथ की लम्बाई	2.300 KM
प्राक्कलित राशि	8.267 Lac
वित्तीय वर्ष	2021-22 / FDR-2021
प्रखंड	Amdabad


प्रस्तुत प्राक्कलन मो 8.267 लाख (आठ लाख अठ्ठस हजार सात सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के Uttari Amdabad To Trimohani More पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाद एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)- 23/291/2019 -4275/ चटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपरोक्त प्राक्कलन में पथ के फ्लैंक में कटाव के स्थान पर Sand Bag डाल कर कटाव को रोका गया है तथा पथ में बने हुए गड्ढों को GSB से भरकर पथ में आवागमन चालु किया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कर्मचारी अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल प्रमंडल, अमदाबाद


कार्यप्रमुख अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs Manihari
2. Name of Block/Road Amdabad / ^{Uttam} Amdabad To Trimohani
Home

A for Road

1. Damage location : 0.260, 1.5 - 2.1 km.
2. Damage Length : 0.466 km
3. Nature of Damage : Partially Sowing, deep ditches at different places.
4. Details of Restoration :
 - i. Material being used in Restoration Sand bags, E/W, G.S.B.
 - ii. Equipment/Tools being used in Restoration Works : Tractor, roller, JCB
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/AE/EE

Executive Engineer

Rural Works Department
Rural Division, Manihari

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : UTTARI AMDABAD TO TRIMOHANI MORE

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 2.300

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BAT	0.000
4	SAND BAGS	2.479
5	G.S.B.	4.578
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		7.057
Add G.S.T. @ 12%		0.847
Add Labour Cess @ 1%		0.071
Add Selgnlorage Fee @ 10%		0.392
Total Cost of Restoration Work =		8.367

[Signature]
J.E.
RWD

[Signature]
A.E.
RWD

[Signature]
E.E.
RWD

Technically Sanction for Rs. 8.367 Lac (Rs.
 Crore. Eight Lac. Thirty six Thousand. Seven Hundred.) Only

[Signature]
Superintendent Engineer
Rural Works Department
Works Circle, Purnea