



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Andhrarthari

Estimate for Mortable of the Road from L043-L030 TO GODAM
TOLA (VR43) FDR at **Block- Andhrarthari** in Madhubani
District.

TOTAL COST FOR MOTORABLE Rs.

52161.00
~~5.00940 lac.~~

Submitted by:

Executive Engineer

RWD(W) Division, Jhanjharpur

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- Andhraithari

Name of Road :- L043 - L030 to Godam +ala (VR 43)

A. For Road

1. Damage Location Chainage :- ch. 200 to 400, 600 to 800
2. Damage Length :- 0.141 km
3. Nature of Damage :- Shoulder cutting,
4. Details of Restoration Works
Price bata fiding qty = 22.02 m³
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:- (Tractor, JCB)
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-
0.141 km 0.022 km or 22 m

B. For Bridge

1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

N/A

C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required:-

(S)

Signature of JE/AE/EE
30/4/22
MR

30/3/22
23/4/22
ER

Signature
(Name of Inspection)

तकनीकी प्रतिवेदन

पथ का नाम :- 1043-1030 To Grodam Tola (VR43)

प्राक्कलित राशि :- ^{500940.00}
~~423442.54~~

प्रमण्डल का नाम:- झंझारपुर

अंचल का नाम :- दरभंगा

योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक 1043-1030
To Grodam Tola (VR43) पथ के लिए तैयार किया गया है, जो

कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।

यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।


इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीड़न किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (सवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।



कनीय अभियंता

सहायक अभियंता



कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर

**Estimate for Motorability of road damaged by flood from L043-L030 TO GODAM TOLA (VR43) For
Year 2021**

Lead :- FDR 2245

Length :- 1.024 km

Sl No.	Item No.	Name of Item	Unit	Quantity As per Appendix - 1	Rate	Amount
1		Providing and filling brick bats in ditches/ damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	$\frac{22.02}{211.20}$ Sq	2004.96	$\frac{44149.22}{423442.54}$

Add 12 % GST ₹

Add 1 % L.C ₹

Add S. Fee (7.89 x 1065.00) x 10 % ₹

Total ₹

Say ₹

PSM/21

Junior Engineer
R.W.D, Works Section,
Andhrarthari

Assistant Engineer
R.W.D, Work sub Div.
Andhrarthari

Executive Engineer
R.W.D (W) Division,
Jhanjharpur

वि. 04/05/2022
678(356)
के आधार पर।

Technically Sanctioned for Rs. Fifty two thousand
One hundred and fifty One
Rupees Only.

Superintending Engineer
RWD Work Circle, Darbhanga

Name of Road :- L043-L030 TO GODAM TOLA (VR43)

me :-	PMGSY	Length :- 1.024 km	Block :- Andhrarthari
-------	-------	--------------------	-----------------------

ndix - I

Measurement for restoration of Embankment and shoulder with Brick Bat (Measurement in mtr.)

Chainage	Nos.		Length (in Mtr.)		Bidth (in Mtr.)		Thickness (in Mtr.)		Quantity	
ch. 200 to 400	1	x	18.00 8.0	x	2.50 1.5	x	0.90 0.3	av.	=	3.5 40.50 cum
	2	x	12.00 5	x	2.70 1.5	x	1.25 0.1	av.	=	1.5 40.50 cum
	2	x	13.00 6.5	x	2.40	x	0.30	av.	=	9.36 cum
	2	x	9.00	x	2.30	x	0.23	av.	=	4.66 cum
ch. 600 to 800	1	x	15.00	x	0.50	x	0.60	av.	=	4.50
	2	x	16.00 3	x	2.10	x	0.60	av.	=	40.32 7.56 cum ✓
	1	x	14.00	x	2.00	x	0.55	av.	=	15.40
	1	x	16.00	x	2.60	x	0.50	av.	=	20.80
	1	x	15.00	x	2.40	x	0.50	av.	=	18.00
	1	x	13.00	x	2.20	x	0.60	av.	=	17.16
			141.00				Total qty.	=	-211.20	cum

22.02 cum.

See
30.4m

26/5/21

Junior Engineer
R.W.D. Works Section,
Andhrarthari

Assistant Engineer
R.W.D. Work sub Div.
Andhrarthari

20/5/22
20/4/22
Executive Engineer
R.W.D (W) Division,
Jhanjharpur

3/4/22