



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

I

157

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Lakhnaur

Estimate for Mortable of the Road from Madhubani jila antargat lakhnaur ke harbhanga bajrangbali asthan se makkari mahadalit tola tak path nirmaan. FDR at Block- Lakhnaur in Madhubani District.

TOTAL COST FOR MOTORABLE Rs.

~~151209~~ lac.

0.06396 lac

Submitted by:

Executive Engineer

RWD(W) Division, Jhanjharpur

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- Lakhnau

Name of Road :- Madhubani Tilantargat Lakhnau ke Harbhanga Bajrangbali
Asthan Se Makkeori Mahadevit Tola

A. For Road

1. Damage Location Chainage :- 300, 350 m
2. Damage Length :- 25.0 m
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:- Brick Bats
 - ii. Equipment's/Tools being used in Restoration works:- Tractor
 - iii. Procedure taken up in Restoration works:- 2.70 m³
 - iv. Restored Length:- 25.0 m

B. For Bridge

1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required:-

Signature of JE/AE/EE

Signature
(Name of Inspection)

तकनीकी प्रतिवेदन

पथ का नाम :- मधुबनी जिलान्तर्गत लखनौर के हरभंगा बजरंगबली स्थान से मक्करी
प्राक्कलित राशि :- महादलित टीला नक
प्रमण्डल का नाम:- झंझारपुर 6,396 = 00
अंचल का नाम :- दरभंगा
योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक मधुबनी जिलान्तर्गत लखनौर के हरभंगा बजरंगबली स्थान से मक्करी महादलित टीला नक पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।

यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीडन किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।

कनीय अभियंता

सहायक अभियंता

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर

Estimate for Motorability of road damaged by flood from Madhubani jila antargat lakhnaur ke harbhanga bajrangbali asthan se makkari mahadalit tola tak path nirmaan. For Year 2021

d :- SCP

Length :- 1.66 km

Item No.	Name of Item	Unit	Quantity As per Appendix - 1	Rate	Amount
	Providing and filling brick bats in ditches/ damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	63.75 2.70	2004.96	5413.39 127816.20

5413.39
₹ 1,27,816.20

Add 12 % GST ₹ 649.61
~~15,337.94~~

2.70 Add 1 % L.C ₹ 54.13
~~1,278.16~~

Add S. Fee (63.75 x 1063.00) x 10 % ₹ 278.64
~~6,776.63~~

1032 Total ₹ 1,51,208.93
~~6395.77~~

Say ₹ 1,51,209.00

Rs = 6396.00

5/11/21

Junior Engineer
R.W.D, Works Section,
Lakhnaur

5/11/21

Assistant Engineer
R.W.D, Work sub Div.
Lakhnaur

2036
19/11/21

Executive Engineer
R.W.D (W) Division,
Jhanjharpur

अभिप्रेत, नमो का. नि. नयनगर
पत्रांक 673 के द्वारा दिनांक 29-4-22
व. आधार पर]

Technically Sanctioned for Rs. 6396.00

Six thousand three hundred ninety Six
Rupees Only.

2036
7/5/22

Superintending Engineer
R.W.D Work Circle, Darbhanga

oad : Madhubani jila antargat lakhnaur ke harbhanga bajrangbali asthan se makkari mahadalit tola tak path nirmaa

SCP Length :- 1.66 km Block :- Lakhnaur

-1

Measurement for restoration of Embankment and shoulder with Brick Bat
(Measurement in mtr.)

Chainage	Nos.		Length (in Mtr.)		Bldth (in Mtr.)		Thickness (in Mtr.)			Quantity	
CH. 300M	1	x	10.00	x	3.00	x	0.30	0.15	av.	=	2.70 cum
CH. 350M	1	x	15.00	x	3.00	x	0.85	0.85	av.	=	38.25 cum
Total qty.										=	63.75 cum

2.70 m³

29/11/21

Junior Engineer
R.W.D, Works Section,
Lakhnaur

29/11/21

Assistant Engineer
R.W.D, Work sub Div.
Lakhnaur

29/4/22
J-E

Executive Engineer
R.W.D (W) Division,
Jhanjharpur

29/4/22

29/4/22
J-E

29/4