

Name of Road:- Khirhar to Tisiyahi
Purvi Tol


Block : HARLAKHI District: MADHUBANI Length : 4.277 KM

Sr No.	Item	Item of Work	Nos	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
1	1.1	Labour for lying dry graded Jhama khoa or Stone filter under Brick pitching or Boulder Pitching in slope or apron Including light ramming etc. all complete as per approved design, specification and direction of E/I								
		CH-0.00 KM	1	50.00	3.75	0.15	56.56			
		CH-0.200 KM	1	10.00	1.50	0.15	2.250			
		CH-0.400 KM	1	2.00	3.00	0.15	0.900			
		CH-3.507 KM	1	5.00	3.00	0.15	2.250			
		CH-4.077 KM	2	5.00	3.00	0.15	4.500			
		CH-4.277 KM	1	20.00	3.00	0.20	12.000			
							50.025	Cum	1939.93	110138.00

Add GST 12% Rs= 11645
 Add Labour Cess 1% Rs= 970
 Add Signorage Fee (50.025x1032x10%) Rs= 5118
 Total Rs= 114778
 110138.00 + 11645 + 970 + 5118 = 130315.00


 JE
 RWD HARLAKI



 AE
 RWD HARLAKHI


 EE
 RWD BENIPATTI

check & verified


 20.12.2021
 J.E


 20/12/2021
 A.E


 20/12/21
 E.E

Post-facto T/s awarded for Rs. 130315.00 (Rs one lac thirty thousand three hundred fifteen rupees only)
 Reference letter no. 233 dated 21/2/22
 of EE darbhanga-2


 Superintending Engineer
 RWD Works Circle, Darbhanga
 21/2/22

(8)

Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection :- 20/12/2021 Name of PIU :- RWD (W) Div. Darbhanga-2

Name of Block :- Harlakhi

Name of Road :- Khyhar to Hisingahi Purbi Kol

For Road :-

1. Damage Location/ Chainage :- 0 to 4.277 k.m

2. Damage Length :- 88 m

3. Nature of Damage :- Breches & pot holes due to flood.

4. Details of Restoration Works :-


i. Material being used in Restoration Works Brick-Bats

ii. Equipment's/ Tools being used in Restoration Works . Tractor & Roller


iii. Procedure taken up in Restoration Works Filling & Compaction

iv. Restored Length — 88 m.

Remarks :- work found Satisfactory.


20.12.21
JE

Signature of JE/AE


20/12/21
Signature of E.E