



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L030-T03 TO OXA HAZI TOLA (TRACK 6)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 4445		
DISTRICT	KATIHAR		
BLOCK	AMDABAD		
DIVISION	MANIHARI		
TOTAL LENGTH OF ROAD		4.445	KM
TOTAL COST OF F.D.R. PART - A		Rs. 10.792	Lacs
ADD G.S.T @ 12%		Rs. 1.295	Lacs
ADD Labour Cess @ 1%		Rs. 0.108	Lacs
ADD Seigniorage Fee @ 10%		Rs. 0.324	Lacs
TOTAL COST OF RESTORATION WORK In Rs.		Rs. 12.519	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari


प्रतिवेदन

पथ का नाम	:— L030-T03 To Oxa Hazi Tola (Track 6)
पथ की लम्बाई	:— 4.445 KM
प्राक्कलित राशि	:— 12.519 Lac
वित्तीय वर्ष	:— 2021-22 / FDR-2021
प्रखंड	:— Amdabad


प्रस्तुत प्राक्कलन मो0 12.519 लाख (बारह लाख एकावन हजार नौ सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के **L030-T03 To Oxa Hazi Tola (Track 6)** पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक— मु0अ0-4 (मु0) विविध (कार्य)— 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में नदी के तरफ कटाव के स्थान पर बम्बू पाईलिंग, रनर दे कर Sand Bag डाल कर मिट्टी का प्रावधान किया गया है। कटे हुए स्थान पर ब्रीक बैट डालकर पथ में आवागमन चालू किया गया है।


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


26/11/21

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


26/11/21

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


26/11/21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs Mani haru
2. Name of Block/Road Amdabad/L030-T03 To oxa Hazi Tola.

A for Road

1. Damage location : 0.35 - 1.70
2. Damage Length : 0.689 km
3. Nature of Damage : Scouring of Edges of road, at river side.
4. Details of Restoration :
 - i. Material being used in Restoration Bamboo, Sand bags, E/w, Bricks bats
 - ii. Equipment/Tools being used in Restoration Works : Tractor Trolley.
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length 0.689 km

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/AE/EE

Executive Engineer

Rural Works Department
Rural Works Division, Manihar


Signature


(Name of Inspector)


GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L630-T03 TO OXA HAZI TOLA (TRACK 6)
DISTRICT KATIHAR
DIVISION MANIHARI
BLOCK AMDABAD
LENGTH OF ROAD (IN KM) 4.445

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	6.230
2	HUME PIPE	0.000
3	BRICK BAT	3.222
4	SAND BAGS	0.764
5	G.S.B.	0.000
5	BAMBOO WORK	0.576
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		10.792
Add G.S.T. @ 12%		1.295
Add Labour Cess @ 1%		0.108
Add Seigniorage Fee @ 10%		0.324
Total Cost of Restoration Work =		12.519


J.E.
RWD


A.E.
RWD


E.E.
RWD

Technically Sanction for Rs. 12.519 Lac (Rs.
Crore. Twelve Lac. Fifty one
Thousand. Nine Hundred. Only


Superintendent Engineer
Rural Works Department
Works Circle, Purnea