



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L034 TO JIYAMARI BARIA

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 740	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	0.740	KM
TOTAL COST OF F.D.R. PART - A	Rs. 7.158	Lacs
ADD G.S.T @ 12%	Rs. 0.859	Lacs
ADD Labour Cess @ 1%	Rs. 0.072	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.402	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 8.491	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन


पथ का नाम	:- L034 To Jiamari Bairia
पथ की लम्बाई	:- 0.740 KM
प्राक्कलित राशि	:- 8.491 Lac
वित्तीय वर्ष	:- 2021-22 / FDR-2021
प्रखंड	:- Amdabad


प्रस्तुत प्राक्कलन मो0 8.491 लाख (आठ लाख उन्चास हजार एक सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के L034 To Jiamari Bairia पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)- 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में कटे हुए स्थान पर मिट्टी भरकर ईट का टुकड़ा डाल कर पथ को आवागमन लायक बनाया गया है तथा पथ के स्कोवरिंग अंश पर बम्बू पाईलिंग, चचरी दे कर Sand Bag से पथ को कटाव से बचाने का कार्य किया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs Manihari
2. Name of Block/Road Amdabad / L034 To Jiamari Baria

A for Road

1. Damage location : 0.100, 0.22, 0.5-0.7 km
2. Damage Length : 0.182 mtr
3. Nature of Damage : Cross Cut & Scouring both Sides PCE & Current
4. Details of Restoration :
 - i. Material being used in Restoration E/W, Sand bag, bamboo
 - ii. Equipment/Tools being used in Restoration Works : Tractor, JCB
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length 0.182 mtr

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/AE/EE

[Signature]
26/11/21
Executive Engineer
Rural Works Department
Manihari Division, Manihari

Signature

(Name of Inspector)

[Signature]
26/11/21

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L034 TO JIYAMARI BARIA

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 0.740

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	1.520
2	HUME PIPE	0.000
3	BRICK BAT	2.141
4	SAND BAGS	2.307
5	G.S.B.	0.000
5	BAMBOO WORK	1.190
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		7.158
Add G.S.T. @ 12%		0.859
Add Labour Cess @ 1%		0.072
Add Seigniorage Fee @ 10%		0.402
Total Cost of Restoration Work =		8.491

[Signature]
J.E.
RWD

[Signature]
A.E.
RWD

[Signature]
E.E.
RWD

Technically Sanction for Rs. 8.491 Lac (Rs.)

Eight Crore. Lac. Forty nine

Thousand. One Hundred.

[Signature]
Superintendent
Rural Works Department
Works Circle, Purnea