



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

DURGAPUR TO GOPI TOLA RATANPUR

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 750	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	0.750	KM
TOTAL COST OF F.D.R. PART - A	Rs. 3.782	Lacs
ADD G.S.T @ 12%	Rs. 0.454	Lacs
ADD Labour Cess @ 1%	Rs. 0.038	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.180	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 4.453	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari


प्रतिवेदन


पथ का नाम	:- Durgapur To Gopi Tola Ratanpur
पथ की लम्बाई	:- 0.750 KM
प्राक्कलित राशि	:- 4.453 Lac
वित्तीय वर्ष	:- 2021-22 / FDR-2021
प्रखंड	:- Amdabad


प्रस्तुत प्राक्कलन मो0 4.453 लाख (चार लाख पैतालिस हजार तीन सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के **Durgapur To Gopi Tola Ratanpur** पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)- 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में पथ के स्कोवरिंग अंश पर बम्बू पाईलिंग एवं रनर का प्रावधान करते हुए Sand Bag भरते हुए पथ को कटाव से बचाया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs Manihari
2. Name of Block/Road Andabad / Gurgapur To Gopi Tola
Ratanpur

A for Road

1. Damage location : 0.30 - 0.70
2. Damage Length : 0.221
3. Nature of Damage : Scouring both sides PCC Road
4. Details of Restoration :
 - i. Material being used in Restoration Bamboo, Sand bags
 - ii. Equipment/Tools being used in Restoration Works : Tractor Trolley
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length 0.221

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/AE/EE
Executive Engineer
Rural Works Department
Manihari

Signature
(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : DURGAPUR TO GOPI TOLA RATANPUR


DISTRICT KATIHAR


DIVISION MANIHARI


BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 0.750

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BAT	0.000
4	SAND BAGS	2.091
5	G.S.B.	0.000
5	BAMBOO WORK	1.691
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		3.782
Add G.S.T. @ 12%		0.454
Add Labour Cess @ 1%		0.038
Add Seigniorage Fee @ 10%		0.180
Total Cost of Restoration Work =		4.453


J.E.
RWD



A.E.
RWD


E.E.
RWD

Technically Sanction for Rs. 4.453 Lac (Rs.)

Crore..... Four Lac..... Forty five

Thousand..... Three Hundred. Only


Superintendent Engineer
Rural Works Department
Works Circle, Purnea