



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

MOHANKUPPI CHOWK TO LAKHI TOLA (ST) VILLAGE

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1350	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	1.350	KM
TOTAL COST OF F.D.R. PART - A	Rs. 9.925	Lacs
ADD G.S.T @ 12%	Rs. 1.191	Lacs
ADD Labour Cess @ 1%	Rs. 0.099	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.388	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 11.603	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari


प्रतिवेदन


पथ का नाम	:- Mohankuppi Chowk To Lakhi Tola (ST) Village
पथ की लम्बाई	:- 1.350 KM
प्राक्कलित राशि	:- 11.603 Lac
वित्तीय वर्ष	:- 2021-22 / FDR-2021
प्रखंड	:- Amdabad


प्रस्तुत प्राक्कलन मो0 11.603 लाख (ग्यारह लाख साठ हजार तीन सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के Mohankuppi Chowk To Lakhi Tola (ST) Village पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)- 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में पथ के गहरे कटाव स्थान पर बम्बू पाईलिंग, चचरी के पश्चात Brick Bat डाल कर पथ को कटाव से बचाया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs Manihari
2. Name of Block/Road Amdabad / Mohan Kuppi Chowk To
Lakhi Tola (ST) village

A for Road

1. Damage location : 0.100 — 0.75 Km
2. Damage Length : 0.363 Km.
3. Nature of Damage : Side crust & flank Cut
4. Details of Restoration : 0.363 Km
 - i. Material being used in Restoration Bamboo, Brick bats
 - ii. Equipment/Tools being used in Restoration Works : Tractor, JCB
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length 0.363 Km

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of

Executive Engineer
Rural Works Department
Works Division, Manihari

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : MOHANKUPPI CHOWK TO LAKHI TOLA (ST) VILLAGE

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 1.350

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BAT	7.134
4	SAND BAGS	0.000
5	G.S.B.	0.000
5	BAMBOO WORK	2.791
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		9.925
Add G.S.T. @ 12%		1.191
Add Labour Cess @ 1%		0.099
Add Seigniorage Fee @ 10%		0.388
Total Cost of Restoration Work =		11.603

[Signature]
J.E.
RWD

[Signature]
A.E.
RWD

[Signature]
E.E.
RWD

Technically Sanction for Rs. 11.603 Lac (Rs.
 Crore. Eleven Lac. Sixty
 Thousand. Three Hundred.) Only

[Signature]
Superintendent
Rural Works Department
Works Circle, Purnea