



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

MOHANKUPPI CHOWK TO RAICHAND TOLA PANCHAYAT
BHAWANIPUR SIMA TAK

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1150	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	1.150	KM
TOTAL COST OF F.D.R. PART - A	Rs. 4.173	Lacs
ADD G.S.T @ 12%	Rs. 0.501	Lacs
ADD Labour Cess @ 1%	Rs. 0.042	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.204	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 4.920	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

पथ का नाम	:- Mohankuppl Chowk To Raichand Tola Panchayat Bhawanipur Sima Tak
पथ की लम्बाई	:- 1.150 KM
प्राक्कलित राशि	:- 4.92 Lac
वित्तीय वर्ष	:- 2021-22 / FDR-2021
प्रखंड	:- Amdabad


प्रस्तुत प्राक्कलन मो0 4.92 लाख (चार लाख बेरानवे हजार) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के Mohankuppl Chowk To Raichand Tola Panchayat Bhawanipur Sima Tak पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाद एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक— मु0अ0-4 (मु0) विविध (कार्य)— 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन डायवर्सन में एक तरफ बम्बू पाईलिंग और Sand bag के पश्चात मिट्टी कार्य कर डायवर्सन चालू किया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कर्मचारी अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs Manihari
2. Name of Block/Road Amdabad / Mohankuppi Chowk To Raichand
Tola Panchayat Bhawanipur Sima Tak.

A for Road

1. Damage location : 0.175 mtr, 0.3 mtr, 0.35, 0.5 km, 1.0 km
2. Damage Length : 0.275 km
3. Nature of Damage : Crows, Scouring where embankment side
4. Details of Restoration : E/W, Sand bag, Bamboo pile & chaakrey
 - i. Material being used in Restoration E/W, Sand bag, bamboo
 - ii. Equipment/Tools being used in Restoration Works : JCB, Tractor Trolley
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length 0.275 km

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/AE/EE

क्रिये 26/11/21
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, मनिहारी (कटिहार)

Signature
(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : MOHANKUPPI CHOWK TO RAICHAND TOLA PANCHAYAT BHAWANIPUR
SMA TAK

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 1.150

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BAT	0.000
4	SAND BAGS	2.236
5	G.S.B.	0.000
5	BAMBOO WORK	1.937
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		4.173
Add G.S.T. @ 12%		0.501
Add Labour Cess @ 1%		0.042
Add Seigniorage Fee @ 10%		0.204
Total Cost of Restoration Work =		4.920

[Signature]
J.E.
RWD

[Signature]
A.E.
RWD

[Signature]
E.E.
RWD

Technically Sanction for Rs. 4.920 Lac (Rs.

Cre. Four Lac. ninety two

Thousand. Hundred.

[Signature]
Superintendent Engineer
Rural Works Department
Works Circle, Purnea