



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

T01 TO JHULA EAST TOLA

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1700	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	1.700	KM
TOTAL COST OF F.D.R. PART - A	Rs. 8.668	Lacs
ADD G.S.T @ 12%	Rs. 1.040	Lacs
ADD Labour Cess @ 1%	Rs. 0.087	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.788	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 10.582	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari


प्रतिवेदन

पथ का नाम :- T01 To Jhula East Tola
पथ की लम्बाई :- 1.700 KM
प्राक्कलित राशि :- 10.582 Lac
वित्तीय वर्ष :- 2021-22 / FDR-2021
प्रखंड :- Amdabad

प्रस्तुत प्राक्कलन मो0 10.582 लाख (दस लाख अठावन हजार दो सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के T01 To Jhula East Tola पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)- 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में पथ के स्कोवरिंग अंश पर बम्बू पाईलिंग, रनर के पश्चात Sand Bag डालकर पथ को कटाव से बचाया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs Manihar
2. Name of Block/Road Amdabad / Toi Tojhula East Tola

A for Road

1. Damage location : 0.1, 0.35, 0.475, 0.575, 0.650, 0.675, 0.80, 0.9
0.100, 0.1472
2. Damage Length : 0.256 km
3. Nature of Damage : Scouring both sides p/c Road.
4. Details of Restoration :
 - i. Material being used in Restoration Bamboo, Sand bags
 - ii. Equipment/Tools being used in Restoration Works : Tractor
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length 0.256 km

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of

Executive Engineer
Rural Works Department
Manihar

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : T01 TO JHULA EAST TOLA

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 1.700


Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BAT	0.000
4	SAND BAGS	6.708
5	G.S.B.	0.000
5	BAMBOO WORK	1.960
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		8.668
Add G.S.T. @ 12%		1.040
Add Labour Cess @ 1%		0.087
Add Seigniorage Fee @ 10%		0.788
Total Cost of Restoration Work =		10.582


J.E.
RWD


A.E.
RWD


E.E.
RWD

Technically Sanction for Rs. 10.582 Lac (Rs.
 Crore. Ten Lac. Fifty eight
 Thousand. Two Hundred.) Only


 Superintendent Engineer
 Rural Works Department
 Works Circle, Purnea