



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L030 TO JHULA SOUTH

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1200	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	1.200	KM
TOTAL COST OF F.D.R. PART - A	Rs. 15.044	Lacs
ADD G.S.T @ 12%	Rs. 1.805	Lacs
ADD Labour Cess @ 1%	Rs. 0.150	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.769	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 17.769	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari


प्रतिवेदन

पथ का नाम :- L030 To Jhula South
पथ की लम्बाई :- 1.200 KM
प्राक्कलित राशि :- 17.769 Lac
वित्तीय वर्ष :- 2021-22 / FDR-2021
प्रखंड :- Amdabad


प्रस्तुत प्राक्कलन मो0 17.769 लाख (सतराह लाख छियत्तर हजार नौ सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के L030 To Jhula South पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)- 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में बने हुए बड़े-बड़े गढ़े के दोनो तरफ बम्बू पाईलिंग, रनर के पश्चात Sand Bag का प्रयोग किया गया है तथा गढ़ो में ब्रीक बैट डालकर पथ को आवागमन लायक बनाया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs M An. hani
2. Name of Block/Road Amdabad / Lo30 To Jhula South.

A for Road

1. Damage location : 0.0 - 0.6 km
2. Damage Length : 0.428
3. Nature of Damage : Deep ditch, Scouring & Cross Cut.
4. Details of Restoration :
 - i. Material being used in Restoration Sand bag, bamboo
 - ii. Equipment/Tools being used in Restoration Works : Tractor, Trolley, JCB, Roller.
 - iii. Procedure taken up in Restoration works: Mannuel
 - iv. Restored Length 0.428

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/AE/EE

Executive Engineer
Rural Works Department
Rural Works Division, Manihar

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L030 TO JHULA SOUTH
DISTRICT : KATIHAR
DIVISION : MANIHARI
BLOCK : AMDABAD
LENGTH OF ROAD (IN KM) : 1.200

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	1.543
2	HUME PIPE	0.000
3	BRICK BAT	11.517
4	SAND BAGS	1.087
5	G.S.B.	0.000
5	BAMBOO WORK	0.897
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		15.044
Add G.S.T. @ 12%		1.805
Add Labour Cess @ 1%		0.150
Add Seigniorage Fee @ 10%		0.769
Total Cost of Restoration Work =		17.769

[Signature]
J.E.
RWD

[Signature]
J.E.
RWD

[Signature]
J.E.
RWD

Technically Sanction for Rs. 17.769 Lac (Rs.
Crore. seventeen Lac. seventy six ...
Thousand. nine Hundred. Only

[Signature]
Superintendent Engineer
Rural Works Department
Works Circle, Purnea