



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

MOHANKUPPI CHOWK TO GAURI KANT HOTE HUE DURGAPUR
PANCHAYAT BHAWAN

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1250	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	1.250	KM
TOTAL COST OF F.D.R. PART - A	Rs. 4.737	Lacs
ADD G.S.T @ 12%	Rs. 0.568	Lacs
ADD Labour Cess @ 1%	Rs. 0.047	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.276	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 5.628	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari


प्रतिवेदन


पथ का नाम	:- Mohankuppi Chowk To Gaurikant Hote Hue Durgapur Panchayat Bhawan
पथ की लम्बाई	:- 1.250 KM
प्राक्कलित राशि	:- 5.628 Lac
वित्तीय वर्ष	:- 2021-22 / FDR-2021
प्रखंड	:- Amdabad


प्रस्तुत प्राक्कलन मो0 5.628 लाख (पाँच लाख बासठ हाजर आठ सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के Mohankuppi Chowk To Gaurikant Hote Hue Durgapur Panchayat Bhawan पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)- 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में कटे हुए स्थान पर मिट्टी भरकर ईट का टुकड़ा डाल कर पथ को आवागमन लायक बनाया गया है तथा पथ के स्कोवरिंग अंश पर बम्बू पाईलिंग, चचरी दे कर Sand Bag से पथ को कटाव से बचाने का कार्य किया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs Manihari
2. Name of Block/Road Amdeabad / Mohankuppi chowk To
Gramikant Hote rue Jangapur Bhowan.

A for Road

1. Damage location : 0.05, 0.3, 0.38, 0.50, 1.00 Km
2. Damage Length : 0.204 Km
3. Nature of Damage : Gull & Scouring Partially wash out Road
4. Details of Restoration :
 - i. Material being used in Restoration E/w, Sand bags, bamboo, Brick bats
 - ii. Equipment/Tools being used in Restoration Works : Tractor, JCB
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length 0.204 Km.

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/AE/EE

Executive Engineer
Rural Works Department
Rural Works Division, Manihari

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : MOHANKUPPI CHOWK TO DAURI KANT HOTE HUE DURGAPUR
PANCHAYAT BHAWAN

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 1.250

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.690
2	HUME PIPE	0.000
3	BRICK BATS	1.336
4	SAND BAGS	1.676
5	G.S.B.	0.000
5	BAMBOO WORK	1.036
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		4.737
Add G.S.T. @ 12%		0.568
Add Labour Cess @ 1%		0.047
Add Selgnorage Fee @ 10%		0.276
Total Cost of Restoration Work =		5.628

[Signature]
26/11/11
J.E.
RWD

[Signature]
26/11/11
A.E.
RWD

[Signature]
26/11
E.E.
RWD

Technically Sanction for Rs. 5.628 Lac (Rs.,,
Crore. Five Lac. sixty two,
Thousand. eighty Hundred.)

[Signature]
Superintendent Engineer
Rural Works Department
Works Circle, Purnea