



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

BHARATKOL PRANPUR TO SHERSAWADI MASJID TAK

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 550	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	0.550	KM
TOTAL COST OF F.D.R. PART - A	Rs. 17.303	Lacs
ADD G.S.T @ 12%	Rs. 2.076	Lacs
ADD Labour Cess @ 1%	Rs. 0.173	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.427 0.63	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 19.979 20.183	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari


प्रतिवेदन


पथ का नाम	:- Bharatkol Pranpur To Shersawadi Masjid Tak
पथ की लम्बाई	:- 0.550 KM
प्राक्कलित राशि	:- 19.979 Lac
वित्तीय वर्ष	:- 2021-22 / FDR-2021
प्रखंड	:- Amdabad

प्रस्तुत प्राक्कलन मो 19.979 लाख (उन्नीस लाख संतानवे हजार नौ सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के Bharatkol Pranpur To Shersawadi Masjid Tak पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)- 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त पथ में बाढ़ के कारण बहुत बड़े-बड़े गढ़ा बन चुका था जिसको दोनों तरफ से बम्बू पाईलिंग एवं रनर देने के पश्चात Sand Bag दे कर बीच में मिट्टी भरकर आवागमन चालु किया गया है तथा मिट्टी के उपर में ईट का टुकड़ा का प्रावधान किया गया है। पार्ट 2 कटाव में एक स्थान पर चार आर.सी.सी. ह्यूम पाईप का भी प्रावधान किया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs Manihari
2. Name of Block/Road Amdabad / Bharat Prantpur to shenawadi
Masjid Tak.

A for Road

1. Damage location : 0.0 Km., 0.50 km
2. Damage Length : 0.24 km
3. Nature of Damage : Cross Cut
4. Details of Restoration :
 - i. Material being used in Restoration H.P., E/W, Sand bag, bamboo, bricks etc
 - ii. Equipment/Tools being used in Restoration Works : Tractor, JCB,
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length 0.24 km.

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/AE/EE

Executive Engineer

Rural Works Department
Works Division, Manihari

Signature


(Name of Inspector)


GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : BHARATKOL PRANPUR TO SHERSAWADI MASJID TAK
DISTRICT KATIHAR
DIVISION MANIHARI
BLOCK AMDABAD
LENGTH OF ROAD (IN KM) 0.550

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
PART - 1		
1	EARTH WORK	5.461
2	BRICK BAT	2.589
3	SAND BAG	1.388
	BAMBOO WORK	0.966
TOTAL		10.404
Add G.S.T. @ 12%		1.248
Add Labour Cess @ 1%		0.104
Add Seigniorage Fee @ 10%		0.185
Total Cost of Restoration Work =		11.941
PART - 2		
4	EARTH WORK	3.180
1	H.P.	0.323
5	BRICK BAT	1.023
5	SAND BAG	1.608
6	BAMBOO WORK	0.765
TOTAL COST OF PROJECT =		6.899
Add G.S.T. @ 12%		0.828
Add Labour Cess @ 1%		0.069
Add Seigniorage Fee @ 10%		0.242
Total Cost of Restoration Work =		8.038

11.941
8.038
19.979


J.E.
RWD


A.E.
RWD


J.E.
RWD

Technically Sanction for Rs. 19.979 Lac (Rs.)

Crore. Nineteen Lac. Ninety seven

Thousand. Nine Hundred.)Only


Superintendent
Rural Works Department
Works Circle, Purnea