



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

161

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Jhanjharpur

Estimate for Mortable of the Road from Madhubani jila antargat jhanjharpur prkhand me NH 57 smaya dhala se paswan tola hote hua bhairv astan tak sadak ki maramati or isi pathme do jagah pul nirman
FDR at Block- Jhanjharpur in Madhubani District.

TOTAL COST FOR MOTORABLE Rs.

2.50592 lac.

0.63247 lac

Submitted by:

Executive Engineer

RWD(W) Division, Jhanjharpur

तकनीकी प्रतिवेदन

पथ का नाम :- N1157 - 521971 dhg14 - p45wcu tol - dhg14 constant

प्राक्कलित राशि :- ~~2.0054 lrc~~ 0.63247 lrc

प्रमण्डल का नाम:- झंझारपुर

अंचल का नाम :- दरभंगा

योजना का नाम :- F.D.R-2245


प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक ~~N1157 - 521971 dhg14 - p45wcu tol - dhg14 constant~~ पथ के लिए तैयार किया गया है, जो

कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।


यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीड़न किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।


कनीय अभियंता


सहायक अभियंता


कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर

Estimate for Motorability of road damaged by flood from Madhubani jila antargat jhanjharpur
rkhand me NH 57 smaya dhala se paswan tola hote hua bhaiw astan tak sadak ki maramati or isi
pathme do jagah pul nirman For Year 2021

J :- NABARD


Length :- 2.43 km

Item No.	Name of Item	Unit	Quantity As per Appendix - 1	Rate	Amount
	Providing and filling brick bats in ditches/ damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	105.65 26.90	2004.96	211824.02 53532.43


$\text{Total} = 53532.43$
 $\text{Add 12 \% GST} = 6423.89$
 $\text{Add 1 \% L.C} = 535.32$
 $\text{Add S. Fee } (105.65 \times 1063.00) \times 10 \% = 11230.60$
 $\text{Total} = 63247.04$
 $\text{Say } \text{Rs. } 2,50,592.00$
 63247


 Junior Engineer
 R.W.D, Works Section,
 Jhanjharpur


 Assistant Engineer
 R.W.D, Work sub Div.
 Jhanjharpur


 Executive Engineer
 R.W.D (W) Division,
 Jhanjharpur

~~Technically Sanctioned for Rs-6~~
 कार्गोपालक अभियंता, झांझार के द्वारा
 जांचोपरान्त पतांक - 671 (सि०) दिनांक - 29/04/22 के आधार पर
 Technically Sanctioned for Rs-63247.00 (Rupees
 Sixty three thousands two hundred forty Seven). Only


 Superintending Engineer
 RWD Work Circle, Darbhanga

Abhinav
 05/05/22

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- Jhanjharpur

Name of Road :- N1752 - Smayy dehalo - paswan tal - bhainu esthan

A. For Road

1. Damage Location Chainage :- 0 km, 200 m

2. Damage Length :- 33 m

3. Nature of Damage :-

4. Details of Restoration Works

i. Materials being used in restoration works:- brick 413

ii. Equipment's/Tools being used in Restoration works:- tractor trolley

iii. Procedure taken up in Restoration works:- 26070 m

iv. Restored Length:- 33 m

B. For Bridge

1. Damage Location Chainage :-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works

i. Materials being used in restoration works:-

ii. Equipment's/Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:-

iv. Restored Length:-


C. Requirement Of New CD/ Bridges

i. Name of Road:-


ii. Location/ Chainage:-


iii. Type of CD Work/ Length required:-

"S"


25/04/22

Signature of JE/AE/EE


24/4/22
RB


Signature
(Name of Inspection)

argat jhanjhpur prkhand me NH 57 smaya dhala se paswan tola hote hua bhairv astan tak sadak ki maramati or isi

NABARD Length :- 2.43 km Block :- Jhanjharpur

- I

Measurement for restoration of Embankment and shoulder with Brick Bat
(Measurement in mtr.)

Chainage	Nos.		Length (in Mtr.)		Bldth (in Mtr.)		Thickness (in Mtr.)			Quantity	
CH. 0M	1	x	6.50	x	2.90	x	1.30	1.30	av.	= 71.53	cum
CH. 200M	1	x	8.50	x	2.70	x	0.90	0.30	av.	= 24.02	cum
Total qty.										= 105.65	cum

22.62
4.08
26.70 m³
26.70 m³

18/01/24
Junior Engineer
R.W.D, Works Section,
Jhanjharpur

05/11/21
Assistant Engineer
R.W.D, Work sub Div.
Jhanjharpur

19/4/22
Executive Engineer
R.W.D (W) Division,
Jhanjharpur

25/04/22
78

2
2014