

ABSTRACT OF COST

Division:- Triveniganj Block:- Triveniganj

Work Circle :- Madhepura

Work:- Restoration of " PWD Parsahi Sadak balram yadav ke ghar se mahadalit tola orlaha tak (Near bridge)"

Restoration Length :- 0.17 Km

Scheme Head :- Restoration (3054)

Session :- FDR (2021-22)

SI No	DESCRIPTIONS	AMOUNT (Rs)
1	RESTORATION AMOUNT OF WORK	1,358,696.00
2	GST @ 12%	163,044.00
3	L. Cess @ 1%	13,587.00
4	S. Fee (used material) @ 10%	82,939.00
	Total cost (Rs.)	1,618,266.00
	Restoration Cost (Lacks)	16.18

22/05/2022
JE

VW
AE 11.5.22

522
Executive Engineer
Rural Works Department
Work Division, Triveniganj
EE

Vide letter no- CE4(50) विविध (कार्य) 23-29/1/2019- 4849 dt 7.12.2021
Technically sanctioned for Rs 16,18,266=00 (Rs Sixteen lacks
Eighteen Thousand Two hundred Sixty six only)

27/06/22
SUPERINTENDING ENGINEER
RWD (W) CIRCLE
MADHEPURA

PWD Parsahi Sadak

Division Triveniganj

[illegible]

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, त्रिवेणीगंज

SUPERINTENDING ENGINEER
RWD (W) CIRCLE
MADHEPURA

ABSTRACT OF COST

Division:- Triveniganj Block:- Triveniganj

Work Circle :- Madhepura

Work:- Restoration of " PWD Parsahi Sadak balram yadav ke ghar se mahadalit tola orlaha tak (Near HP)"

Restoration Length :- 0.108 Km

Scheme Head :- Restoration (3054)

Session :- FDR (2021-22)

SI No	DESCRIPTIONS	AMOUNT (Rs)
1	RESTORATION AMOUNT OF WORK	2,229,871.00
2	GST @ 12%	267,585.00
3	L. Cess @ 1%	22,299.00
4	S. Fee (used material) @ 10%	47,900.00
	Total cost (Rs.)	2,567,655.00
	Restoration Cost (Lacks)	25.68

21/5/2022
JE

Vib
11.5.22
AE

21.5.22
Executive Engineer
Rural Works Department
Work Division, Triveniganj

Vide letter no. CE4(130) विविध (कार्य) 23-291/2019-4849 dt 7-12-2021
Technically sanctioned for Rs 2567655-00 (Rs Twenty five Lacks
Sixty Seven thousand Six Hundred Fifty five only)

11/10/22
SUPERINTENDING ENGINEER
RWD (W) CIRCLE
MADHEPURA

विभाग, कार्य अंचल मधेपुरा की अध्यक्षता में गठित चार सदस्यीय समिति द्वारा कार्य प्रमंडल, त्रिवेणीगंज के अंतर्गत वर्ष 2021-22 में बाढ़/ अतिवृष्टि से क्षतिग्रस्त पथों के मोटरबुल कार्य के कृत कार्य मदों की मात्रा का स्थलीय जाँच संबंधित सहायक अभियंता एवं कनिष्ठ

18	PWD Parsahi Sadak balram yadav ke ghar se mahadalit tola orlaha tak (Near HP)								Division Triveniganj		
Block:- Triveniganj											
Sl No	Work discription	Type	Sides	Nos	Length (m)	Width (m)		Depth (m)		Qty/Area (m2/m3)	unit
1	3	4	5	6	7	8	9	10	11	12	13
1	Local Sand		1	1	47.00	6.50	7.50	1.20	1.80	493.50	
			1	1	6.00	7.00	7.90	3.50	4.60	181.04	
			1	1	5.00	7.10	8.10	5.50	5.80	214.70	
			1	1	13.00	8.50	8.50	4.30	4.30	475.15	
			1	1	5.00	6.40	7.40	6.90	7.80	253.58	
			1	1	11.00	6.50	6.90	6.90	7.90	545.38	
			1	1	21.00	6.20	6.50	1.20	1.50	180.02	
Filling of local sand										2343.37	cum
2	Brick bats		1	1	6.00	5.70	5.70	0.30	0.30	10.26	
			1	1	6.00	7.50	7.50	0.30	0.30	13.50	
			1	1	6.00	5.70	5.70	0.30	0.30	10.26	
			1	1	30.00	4.80	5.00	0.30	0.60	66.15	
			1	1	6.00	5.00	5.50	0.45	0.60	16.54	
			1	1	15.00	5.50	6.00	0.45	0.60	45.28	
			1	1	13.00	5.00	5.50	0.60	0.60	40.95	
			1	1	5.00	5.40	4.70	1.10	1.10	27.78	
			1	1	11.00	4.90	5.00	0.60	0.60	32.67	
			1	1	21.00	5.20	5.50	0.45	0.60	58.98	
Total Brick bats Qty										322.37	cum
	GSB Gr-II		1	1	6	5.70	5.70	0.15	0.15	5.13	
			1	1	30	4.80	5.00	0.15	0.15	22.05	
			1	1	6	5.00	5.50	0.15	0.15	4.73	
			1	1	15	5.50	6.00	0.15	0.15	12.94	
			1	1	13	5.00	5.50	0.20	0.15	11.94	
			1	1	5	5.40	4.70	0.15	0.15	3.79	
			1	1	11	4.90	5.00	0.15	0.15	8.17	
			1	1	21	5.20	5.50	0.15	0.15	16.85	
Total GSB Gr-II Qty										85.60	cum
										15.00	m
5	Hume Pipe	1000mm dia		6	2.50						
	Empty cemnt bag		2	1	6.00	1.50	1.50	0.48		8.64	
										8.64	m3
		Hume Pipe	2	3	2.50					4.23	m3
										4.41	m3
									Qty		

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सुपौल

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बीरपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, त्रिवेणीगंज
SUPERINTENDING ENGINEER
RWD (W) CIRCLE
MADHEPURA