

ABSTRACT OF COST

Division:- Triveniganj Block:- Triveniganj
Work Circle :- Madhepura
Work:- Restoration of road from "PWD Jharkaha se Laguniya Mahadalit Tola tak (CH 300)"
Restoration Length :- 0.187 Km
Scheme Head :- Restoration (3054)
Session :- FDR (2021-22)

Sl No	DESCRIPTIONS	AMOUNT (Rs)
1	RESTORATION AMOUNT OF WORK	1,186,627.00
2	GST @ 12%	142,395.00
3	L. Cess @ 1%	11,866.00
4	S. Fee (used material) @ 10%	40,350.00
	Total cost (Rs.)	1,381,238.00
	Restoration Cost (Lacks)	13.81

20/5/2022
J.E

11.5.22
A.E

21.5.22
Executive Engineer
Rural Works Department
Work Division, Triveniganj

Vide letter no - 30304 विविध-कर्म 23-291/2019-4849 dt 7
Technical sanctioned for Rs 13,81,238:00 (Rs Thirteen Lacks
Eighty one thousand Two hundred Thirty Eight only)

27/06/22
SUPERINTENDING ENGINEER
RWD (W) CIRCLE
MADHEPURA

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक - 1890 दिनांक - 22.04.2022 द्वारा अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल मधेपुरा की अध्यक्षता में गठित चार सदस्यीय कमिटी द्वारा कार्य प्रमंडल, त्रिवेणीगंज के अंतर्गत वर्ष 2021-22 में बाढ़/ अतिवृष्टि से क्षतिग्रस्त पथों के मोटरेबुल कार्य के कृत कार्य मदों की मात्रा का स्थलीय जाँच संबंधित सहायक अभियंता एवं कनीय अभियंता के साथ समीक्षा किया गया जो निम्न है-

9	PWD Jharkaha se Laguniya Mahadalit Tola tak (CH 300)										Division Triveniganj	
Block:- Triveniganj												
Sl No	Work discription	Type	Sides	Nos	Length (m)	Width (m)		Depth (m)		Qty/Area (m2/m3)	unit	
1	3	4	5	6	7	W1	W2	D1	D2	12	13	
1	Local Sand		1	1	24.00	6.00	8.50	1.20	1.30	217.50		
			1	5	30.00	1.20	1.30	0.75	0.90	154.69		
Filling of local sand										372.19	cum	
2	Brick bats		1	1	15.00	6.00	7.90	0.75	0.90	86.01		
			1	1	15.00	7.90	5.70	0.30	0.30	30.60		
			1	1	11.00	5.70	5.70	0.30	0.30	18.81		
			1	3	30.00	3.75	3.75	0.30	0.30	101.25		
			1	1	30.00	3.75	3.75	0.30	0.30	33.75		
			1	1	26.00	3.75	3.75	0.45	0.45	43.88		
Total Brick bats Qty										314.30	cum	
3	GSB Gr-II		1	1	15	5.00	5.50	0.15	0.20	13.78		
			1	1	20	4.30	4.80	0.15	0.20	15.93		
			1	3	30	3.75	3.75	0.15	0.20	59.06		
			1	1	30	3.75	3.75	0.15	0.20	19.69		
			1	1	26	3.75	3.75	0.15	0.20	17.06		
Total GSB Gr-II Qty										125.52	cum	

आलेख
6/5/22
RE
VIL-9
06.5.22
AE

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सुपौल

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बीरपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, त्रिवेणीगंज

SUPERINTENDING ENGINEER
RWD (W) CIRCLE
MADHEPURA

ABSTRACT OF COST

Division:- Triveniganj Block:- Triveniganj
Work Circle :- Madhepura
Work:- Restoration of " PWD Jharkahas Se Laguniya Mahadalit Tola Tak (Lagunia hat)"
Restoration Length :- 0.126 Km
Scheme Head :- Restoration (3054)
Session :- FDR (2021-22)

SI No	DESCRIPTIONS	AMOUNT (Rs)
1	RESTORATION AMOUNT OF WORK	1,082,616.00
2	GST @ 12%	129,914.00
3	L. Cess @ 1%	10,826.00
4	S. Fee (used material) @ 10%	39,562.00
	Total cost (Rs.)	1,262,918.00
	Restoration Cost (Lacks)	12.63

[Signature]
J.E 10.05.2022

[Signature]
A.E 11.5.22

[Signature]
Executive Engineer
Rural Works Department
Work Division, Triveniganj

Vide letter no- 303104 (Rd) विविध (अर्थ) 23-291/2019-4849 dt-7.12.2021
Technically sanctioned for Rs. 12,62,918.00 (Rs. Twelve Lacks
Sixty Two thousand Nine Hundred Eighteen Only)

[Signature]
SUPERINTENDING ENGINEER
RWD (W) CIRCLE
MADHEPURA

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक - 1890 दिनांक - 22.04.2022 द्वारा अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल मधेपुरा की अध्यक्षता में गठित चार सदस्यीय समिती द्वारा कार्य प्रमंडल, त्रिवेणीगंज के अंतर्गत वर्ष 2021-22 में बाढ़/ अतिवृष्टि से क्षतिग्रस्त पथों के मोटरबुल कार्य के कृत कार्य मदों की मात्रा का स्थलीय जाँच संबंधित सहायक अभियंता एवं कनीय अभियंता के साथ मापी लिया गया जो निम्न है -

24 PWD Jharkahas Se Laguniya Mahadalit Tola Tak (Lagunia hat)										Division Triveniganj	
Block:- Triveniganj											
SI No	Work discription	Type	Sides	Nos	Length (m)	Width (m)		Depth (m)		Qty/Area (m2/m3)	unit
1	3	4	5	6	7	8	9	10	11	12	13
1	Local Sand		2	2	30.00	1.50	1.80	1.90	2.20	405.90	
			2	2	18.00	1.70	1.90	1.90	2.10	259.20	
			2	1	30.00	1.80	1.80	1.60	1.90	189.00	
										Filling of local sand	854.10 cum
2	Brick bats		2	1	30.00	1.50	1.90	0.15	0.20	17.85	
			2	1	22.00	1.80	1.80	0.15	0.20	13.86	
			2	1	10.00	1.50	1.50	1.50	1.50	45.00	
			2	1	36.00	2.40	2.80	0.15	0.20	32.76	
			1	1	15.00	0.50	0.60	0.15	0.20	1.44	
										Total Brick bats Qty	110.91 cum
	GSB Gr-II		1	1	15	5.60	7.50	0.20	0.25	22.11	
										Total GSB Gr-II Qty	22.11 cum
4	Geo bag		1	1	10.00	0.90	0.90	3.70	3.70	33.30	
			1	1	37.00	3.70	3.70	0.30	0.30	41.07	
			1	1	39.00	3.60	3.60	0.30	0.30	42.12	
										Total	116.49 cum
6	Bamboo Piling									102.00	Nos

06.5.22
AE

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सुपौल

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बीरपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, त्रिवेणीगंज

SUPERINTENDING ENGINEER
RWD (W) CIRCLE
MADHEPURA

ABSTRACT OF COST

Division:- Triveniganj Block:- Triveniganj

Work Circle :- Madhepura

Work:- Restoration of " PWD Jhakrkahas Se Laguniya Mahadalit Tola Tak (Near School)"

Restoration Length :- 0.076 Km

Scheme Head :- Restoration (3054)

Session :- FDR (2021-22)

Sl No	DESCRIPTIONS	AMOUNT (Rs)
1	RESTORATION AMOUNT OF WORK	1,276,115.00
2	GST @ 12%	153,134.00
3	L. Cess @ 1%	12,761.00
4	S. Fee (used material) @ 10%	51,287.00
	Total cost (Rs.)	1,493,297.00
	Restoration Cost (Lacks)	14.93

20/05/2022
J.E

11/5.22
A.E

21.5.22
Executive Engineer
Rural Works Department
Work Division, Triveniganj

Vide Letter no 403104 (R) विविध (मास) 23-29/1/2019-4849 dt 7.12.2021
Technically sanctioned for Rs 14,93,297.00 (Rs Fourteen
Lacks Ninety Three thousand Two hundred Ninety Seven only)

11/5/22
SUPERINTENDING ENGINEER
RWD (W) CIRCLE
MADHEPURA

28 PWD Jhakrkahas Se Laguniya Mahadalit Tola Tak (Near School)

Block:- Triveniganj

Viv → 6
06.5.22
AE

क. अभियंता

08/5/22

G 6.5.22

11/06/05/22

ABSTRACT OF COST

Division:- Triveniganj Block:- Triveniganj

Work Circle :- Madhepura

Work:- Restoration of "PWD Jhakrkahas Se Laguniya Mahadalit Tola Tak (@ Ch-150m)"

Restoration Length :- 0.155 Km

Scheme Head :- Restoration (3054)

Session :- FDR (2021-22)

Sl No	DESCRIPTIONS	AMOUNT (Rs)
1	RESTORATION AMOUNT OF WORK	1,913,015.00
2	GST @ 12%	229,562.00
3	L. Cess @ 1%	19,130.00
4	S. Fee (used material) @ 10%	85,605.00
	Total cost (Rs.)	2,247,312.00
	Restoration Cost (Lacks)	22.47

[Signature]
JE
14/5/2022

[Signature]
AE
11.5.22

[Signature]
Executive Engineer
Rural Works Department
Work Division, Triveniganj,

T.S. vide letter no - 303704(15) विविध (कॉस्ट), 23-291/2019 - 4849 dt 7.12.21

Technical sanctioned for Rs 22,47,312.00 (Rs Twenty Two Lacks forty seven thousand Three Hundred Twelve Only).

[Signature]
SUPERINTENDING ENGINEER
RWD (W) CIRCLE
MADHEPURA

विभाग, कार्य अंचल मधेपुरा की अध्यक्षता में गठित चार सदस्यीय समिति द्वारा कार्य प्रमंडल, त्रिवेणीगंज के अंतर्गत वर्ष 2021-22 में बाढ़/ अतिवृष्टि से क्षतिग्रस्त पथों के मोटरेबुल कार्य के कृत कार्य मदों की मात्रा का स्थलीय जाँच संबंधित सहायक अभियंता एवं कनीय अभियंता के साथ मापी लिया गया जो निम्न है -

21	PWD Jharkkahas Se Laguniya Mahadalit Tola Tak (@CH-150m)								Division Triveniganj			
Block:- Triveniganj												
SI No	Work discription	Type	Sides	Nos	Length (m)	Width (m)		Depth (m)		Qty/Area (m2/m3)	unit	
1	3	4	5	6	7	W1	W2	D1	D2	12	13	
1	Local Sand		1	1	17.00	9.50	9.50	0.90	0.90	145.35		
			1	1	47.00	5.70	5.90	0.60	0.60	163.56		
			1	1	16.00	5.90	9.40	0.60	0.60	73.44		
			1	1	25.00	1.50	1.60	0.90	0.90	34.88		
			1	1	30.00	1.20	1.50	1.30	1.30	52.65		
			2	1	20.00	1.10	1.60	1.10	1.20	62.10		
Filling of local sand										531.98	cum	
2	Brick bats		1	1	17.00	5.70	5.70	0.45	0.45	43.61		
			1	1	17.00	7.50	7.90	0.30	0.30	39.27		
			1	1	17.00	5.70	5.70	0.90	0.90	87.21		
			1	1	16.00	9.50	4.30	0.15	0.20	19.32		
			1	1	47.00	4.30	4.50	0.15	0.20	36.19		
			1	1	25.00	0.90	1.00	0.15	0.20	4.16		
			1	1	30.00	0.60	0.90	0.15	0.20	3.94		
			2	1	20.00	1.05	1.20	0.15	0.20	7.88		
		deduction (HP 1000mm dia)								241.58	cum	
			1	9		5.70		1.13	(-)	57.97	cum	
Total Brick bats Qty										183.61	cum	
	GSB Gr-II		1	1	17	5.70	5.70	0.15	0.20	16.96		
			1	1	16	9.50	4.30	0.15	0.20	19.32		
			1	1	47	4.30	4.50	0.15	0.20	36.19		
			1	1	0	3.75	3.75	0.15	0.15	0.00		
			1	1	0	5.30	6.00	0.15	0.20	0.00		
Total GSB Gr-II Qty										72.47	cum	
4	Geo bag		2	1	17.00	0.90	0.90	2.10	2.10	64.26		
			1	1	17.00	7.50	7.50	0.30	0.30	38.25		
			1	1	17.00	5.70	5.70	1.20	1.20	116.28		
			1	1	25.00	3.70	3.60	0.30	0.30	27.38		
			1	1	30.00	3.30	3.60	0.30	0.30	31.05		
			2	1	20.00	3.20	3.50	0.30	0.30	40.20		
		deduction (HP 1000mm dia)								Qty	317.42 cum	
			2	9		0.90		1.130	(-)	18.31	cum	
Total										299.11	cum	
5	Hume Pipe	1000mm dia		27	2.50					67.50	m	
6	Bamboo Piling									88.00	Nos	

2nd
6/5/22
TE
VJ
06.5.22
AE
SUPERINTENDING ENGINEER
RWD (W) CIRCLE
MADHEPURA

कार्यपालक अभियंता
ग्रामीण कार्य विभाग, मधेपुरा

कार्यपालक अभियंता

ग्रामीण कार्य विभाग, मधेपुरा

कार्यपालक अभियंता

ग्रामीण कार्य विभाग, मधेपुरा