



# ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

## BIHAR RURAL ROADS PROJECT

Bihar Rural Development Agency (BRRDA)

Head :- F.D.R.

YEAR (2021-22)

STATE  
DISTRICT  
BLOCK  
DIVISION

BIHAR  
SUPAUL  
CHHATAPUR  
TRIVENIGANJ

DETAILED ESTIMAE FOR TEMPORARY RESTORATION OF ROAD FROM  
CHUNI WORLD BANK TO CHAUDHARY TOLA (SAHPUR), GIRDHARPATTI  
HAT VIA MIRRAPATTI

|                               |    |           |
|-------------------------------|----|-----------|
| Actual Length of Road         | =  | 9.300 Km  |
| Flood affected Length of Road | =  | 0.802 Km  |
| TOTAL COST OF PAVEMENT        | Rs | 1,907,225 |
| TOTAL PROJECT COST            | Rs | 1,907,225 |

Submitted By:  
Executive Engineer  
RWD (W) Division, Triveniganj

Prepared By:  
Executive Engineer  
RWD (W) Division, Triveniganj

| S.No | District | Division    | Road Name                                                                                                                              | Length(In Km.) | Length of Damage Part Due to Flood | Tentative Restoration Amount(In Lac) | Block     |
|------|----------|-------------|----------------------------------------------------------------------------------------------------------------------------------------|----------------|------------------------------------|--------------------------------------|-----------|
| 1    | Supaul   | Triveniganj | Chunni world bank to choudhary tola(sahpur), giridharpathi hat via mirzapatti                                                          | 9.3            | 0.3                                | 60                                   | Chhatapur |
| 2    | Supaul   | Triveniganj | Mahdipur Bazar to Chhatapur (Boader)                                                                                                   | 1              | 0.25                               | 18                                   | Chhatapur |
| 3    | Supaul   | Triveniganj | 1053-101 To Narahiya (VRB)                                                                                                             | 2.585          | 0.35                               | 19                                   | Chhatapur |
| 4    | Supaul   | Triveniganj | 1. Construction of road from Lalji Chhauk Harihar Path to Subta Kachhi Road with five years maintenance                                | 11.97          | 0.3                                | 44                                   | Chhatapur |
| 5    | Supaul   | Triveniganj | 2. Construction of road from Chhatapur bus stand to Bhatta Bari Road with five years maintenance                                       | 3.18           | 0.2                                | 36                                   | Chhatapur |
| 6    | Supaul   | Triveniganj | 3. Construction of road from Chhatapur Anant Chowk to Bhatta Bari Road with five years maintenance.                                    | 1.485          | 0.1                                | 20                                   | Chhatapur |
| 7    | Supaul   | Triveniganj | 2. Construction of road from Baghumathpur to Faisya Kotli Road with five years maintenance.                                            | 9.375          | 2.12                               | 64                                   | Chhatapur |
| 8    | Supaul   | Triveniganj | 1. Construction of road from Chunni to Charney world Bank road with five year maintenance                                              | 6.345          | 0.3                                | 40                                   | Chhatapur |
| 9    | Supaul   | Triveniganj | 2. Construction of road from Chhatapur Laxmipur to kunti road with five year maintenance                                               | 7.75           | 0.3                                | 45                                   | Chhatapur |
| 10   | Supaul   | Triveniganj | 3. Construction of road from Lalit gram Railway Station to Mahadev Patti with five year maintenance                                    | 2.055          | 0.4                                | 34                                   | Chhatapur |
| 11   | Supaul   | Triveniganj | Near House of Bishwanath Thakur TO Brahman Tola, Pratapganj Pariyahi Road Middle PMGSY[SC]hool Talgaonj                                | 2              | 0.15                               | 50                                   | Chhatapur |
| 12   | Supaul   | Triveniganj | State Highway Se Ramjanki Chowk Middle School Chapin to Aarriya Sima Birpur Path Via Ayub 72 RD Subki mandal tola middle school thuthi | 8.165          | 0.4                                | 34                                   | Chhatapur |
| 13   | Supaul   | Triveniganj | Pariyahi Pradhanmantri Sadak Se Paschim Ranipatti Nahar Ke Daya Bank to Udakishunganj SHW Nahar Pul Tak                                | 5.035          | 0.15                               | 75                                   | Chhatapur |
| 14   | Supaul   | Triveniganj | Bari Masjid Jhakhargadh TO Purab Mahadalit Tola Via Chohan, Sah, Mansuri, Mahadalit Tola                                               | 2              | 0.2                                | 15                                   | Chhatapur |
| 15   | Supaul   | Triveniganj | SHW From House of Chhutharu Sahni to NH57 Naaharpul Via Mehta Mahadalit Tola.                                                          | 3.55           | 0.15                               | 12                                   | Chhatapur |
| 16   | Supaul   | Triveniganj | Jewacchpur Naya Bazar to Madhubani Sima Tak via Sarswatipur.                                                                           | 3.175          | 0.33                               | 23                                   | Chhatapur |
| 17   | Supaul   | Triveniganj | 1033-101 To Lachmipur (VR9)                                                                                                            | 4.421          | 0.2                                | 70                                   | Chhatapur |
| 18   | Supaul   | Triveniganj | 31 No Road to Darhariya Sima PMGSY via Pariyadhar                                                                                      | 3.54           | 0.15                               | 40                                   | Chhatapur |
| 19   | Supaul   | Triveniganj | Madhopur Market to West North SHW Birpur Road via Uddhampur Sima                                                                       | 1.645          | 0.06                               | 35                                   | Chhatapur |
| 20   | Supaul   | Triveniganj | SH Bus Stand Paschim Bakho Tola & Paswan Tola Hote Huye Genda Nadi Evam Mirchaiya Nadi Par Karte Huye Harripatti SH Tak                | 4.77           | 0.025                              | 15                                   | Chhatapur |
| 21   | Supaul   | Triveniganj | East of SHW Kalam Dealer House to Anand Chowk                                                                                          | 1.5            | 0.12                               | 35                                   | Chhatapur |
| 22   | Supaul   | Triveniganj | Pradhanmantri Matiyari to Brahmatra Mushhari Tola                                                                                      | 2.085          | 0.2                                | 68                                   | Chhatapur |

## 1

name of Road :- CONSTRUCTION OF ROAD CHUNNI WORLD BANK ROAD TO CHOUDHARY TOLA GIRDHARPAT

Block :- Chhatapur

~~105/102~~

गणेश २३/०९/२२  
पालक अभियंता

23/5/22

h23.522

11/22/2022

क्षेत्र अभियंता सह अध्यक्ष जॉन सी  
ग्रामीण कार्य विभाग  
कार्य अचल, मधेपुरा

# SUMMARY OF COST ESTIMATE FOR THE PROJECT

DETAILED ESTIMAE FOR TEMPORARY RESTORATION OF ROAD  
FROM CHUNI WORLD BANK TO CHAUDHARY TOLA (SAHPUR),  
GIRDHARPATTI HAT VIA MIRRAPATTI

NAME OF ROAD :-

DIVISION :- TRIVENIGANJ


BLOCK :- CHHATAPUR


Actual Length of Road :- 9.300 Km

Flood Affected Length of Road :- 0.802 Km

| Sr. No. | Description                                   | Amount (In Rs.) |
|---------|-----------------------------------------------|-----------------|
| 1       | SAND BAG                                      | 64,575.8534     |
| 2       | BRICK BATS                                    | 617,818.13      |
| 3       | BAMBOO PILE                                   | -               |
| 4       | BAMBOO SUPPLY                                 | -               |
| 5       | EC BAG                                        | -               |
| 6       | GEO BAG                                       | -               |
| 7       | GRANULAR SUB BASE                             | 961,417.78      |
| 8       | HUME PIPE                                     | -               |
|         | Total Cost =                                  | 1,643,811.76    |
|         | Add:-Labour Cess @1% amt. =                   | 16,438.12       |
|         | Add:GST@12% on amt. =                         | 197,257.41      |
|         | Add:S.F.@ 10% on Material =                   | 49,717.24       |
|         | TOTAL RESTORATION COST OF THE PROJECT IN LACS | 1,907,225       |

  
15/6/22  
Junior Engineer  
RWD (W) Division, Triveniganj

  
15/6/22  
Assistant Engineer  
RWD (W) Division, Triveniganj  
Chhatapur

  
17.6.22  
Executive Engineer  
RWD (W) Division, Triveniganj

Vide letter no 378-4 (Rd) Diler (Rd) 23-29/12/2019-4849  
dt- 07/12/2021

Technically sanctioned for Rs-1907225-00/-  
(that is nineteen lakh seven thousand two hundred  
twenty five rupees only)

  
29/06/22  
Superintending Engineer  
Rural Works Department  
Works Circle Madhet

## Details of Measurement

| कार्य का ब्यौरा<br>Deetail of Work |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | संख्या<br>No                                                                                                                              | Measurement         |                 |                | मात्रा<br>Quantity |
|------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------|---------------------|-----------------|----------------|--------------------|
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                           | लम्बाई<br>in m.     | चौड़ाई<br>in m. | ऊँचाई<br>in m. |                    |
| NAME OF ROAD :-                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | DETAILED ESTIMAE FOR TEMPORARY RESTORATION OF ROAD FROM CHUI<br>WORLD BANK TO CHAUDHARY TOLA (SAHPUR), GIRDHARPATTI HAT VIA<br>MIRRAPATTI |                     |                 |                |                    |
| Item No. 1                         | Sand filling in Foundation Trenches as per Drawing & Technical Specification                                                                                                                                                                                                                                                                                                                                                                                                                           |                                                                                                                                           |                     |                 |                |                    |
| CH-in                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 1                                                                                                                                         | 30                  | 2.000           | 0.60           | 36.000             |
| CH-in                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 1                                                                                                                                         | 10                  | 2.000           | 0.60           | 12.000             |
| CH-in                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 2                                                                                                                                         | 20                  | 2.000           | 0.60           | 48.000             |
| CH-in                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 1                                                                                                                                         | 20                  | 2.000           | 0.30           | 12.000             |
| CH-in                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 1                                                                                                                                         | 10                  | 1.800           | 0.60           | 9.000              |
| Item No. 2                         | Providing and laying of Brick bat obtained from chimney with machanical means with all spreading<br>grading to required slope and compacted at OMC to acheive required density with all complete as per the<br>direction of engineer in charge.                                                                                                                                                                                                                                                        |                                                                                                                                           |                     |                 |                | 117.000            |
| CH-in                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 1                                                                                                                                         | 30                  | 3.500           | 0.300          | 31.500             |
| CH-in                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 4                                                                                                                                         | 30                  | 3.000           | 0.450          | 162.000            |
| CH-in                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 1                                                                                                                                         | 30                  | 3.600           | 0.300          | 32.400             |
| CH-in                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 2                                                                                                                                         | 30                  | 3.800           | 0.300          | 68.400             |
| CH-in                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 1                                                                                                                                         | 30                  | 3.000           | 0.300          | 27.000             |
| Less For Pipe                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 0                                                                                                                                         | 22/7x(0.6)2x2.5 (-) |                 |                | 0.000              |
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                           | Total (in Cum)      |                 |                | 321.300            |
| Item No. 3                         | Labour for cutting 62mm to 75 mm dia bamboo piles to size and making shoes and driving etc. complete<br>job as per specification and direction of E/I                                                                                                                                                                                                                                                                                                                                                  |                                                                                                                                           |                     |                 |                |                    |
| CH-in                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 3                                                                                                                                         | 0                   |                 | 4.00           | 0.000              |
| For Bamboo pilling 1.25m           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                           | Total (in m)        |                 |                | 0.000              |
| Item No. 6                         | Supply of Bamboo at site.                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                                                                                                                                           |                     |                 |                |                    |
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                           | Total (in m)        |                 |                | 0.00               |
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                           | Total (in nos.)     |                 |                | 0.00               |
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                           |                     |                 |                | 0.00               |
| Item No. 3                         | Labour filling empty cement bags with loocal sand, stitching the bags and placing including supply of sutli<br>and EC bag etc. all complete as per approved desing, specification and direction of E/I                                                                                                                                                                                                                                                                                                 |                                                                                                                                           |                     |                 |                |                    |
| CH-in                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 1                                                                                                                                         | 0.00                | 2               | 1.50           | 0.00               |
| CH-in                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Total (in cum)                                                                                                                            |                     |                 |                | 0.00               |
| (0.034m3=1 no. of EC Bags)         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                           |                     |                 |                | 0.00               |
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                           | Total (in nos.)     |                 |                | 0.00               |
| Item No. 4                         | Providing,laying and filling Geo bags of size 1m X 0.7 m(Type A 300 GSM nonwoven) weight of bags<br>420g volume of filled bag 0.07m3. weight of filled Geo bags 126 Kg with local sand including stitching in<br>four lines by approved nylon thread with stitching machine and generator stacking and placing after<br>loading unloading and carriage with help of trolley within 150m lead all complete as per specifications<br>and direction of E/I (including Carriage of Local sand lead 0.5 km) |                                                                                                                                           |                     |                 |                |                    |
| CH-in                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 2                                                                                                                                         | 0                   | 2.00            | 0.45           | 0.00               |
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                           |                     |                 |                | 0.00               |
| (0.076m3=1 no. of Geo Bags)        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                           |                     |                 |                | 0.00               |
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                                                                           | Total (in nos.)     |                 |                | 0.00               |
| Item No. 5                         | Construction of granular sub-base by providing well graded material, spreading in uniform<br>layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place<br>method with rotavator at OMC, and compacting with smooth wheel roller to achieve the<br>desired density, complete as per Technical Specification Clause 401.(Gr-II Material)                                                                                                                                |                                                                                                                                           |                     |                 |                |                    |
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 2                                                                                                                                         | 15                  | 3.00            | 0.150          | 13.5000            |
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 1                                                                                                                                         | 18                  | 2.00            | 0.150          | 5.4000             |
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 2                                                                                                                                         | 30                  | 3.00            | 0.100          | 18.0000            |
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 2                                                                                                                                         | 30                  | 3.00            | 0.150          | 27.0000            |
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 4                                                                                                                                         | 8                   | 2.50            | 0.100          | 8.0000             |
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 4                                                                                                                                         | 2.3                 | 3.00            | 0.150          | 4.1400             |
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 5                                                                                                                                         | 15                  | 3.00            | 0.150          | 33.7500            |
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 3                                                                                                                                         | 25                  | 3.20            | 0.100          | 24.0000            |
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 2                                                                                                                                         | 25                  | 3.20            | 0.150          | 24.0000            |

|   |                                                                                                   |  |  |           |   |    |      |       |                     |
|---|---------------------------------------------------------------------------------------------------|--|--|-----------|---|----|------|-------|---------------------|
|   |                                                                                                   |  |  |           | 4 | 16 | 3.00 | 0.150 | 28.8000             |
|   |                                                                                                   |  |  |           | 6 | 12 | 2.50 | 0.100 | 18.0000             |
|   |                                                                                                   |  |  |           | 5 | 15 | 3.00 | 0.150 | 33.7500             |
|   |                                                                                                   |  |  |           | 2 | 30 | 3.00 | 0.150 | 27.0000             |
|   |                                                                                                   |  |  |           | 2 | 30 | 3.00 | 0.150 | 27.0000             |
|   |                                                                                                   |  |  |           | 2 | 30 | 3.00 | 0.150 | 27.0000             |
|   |                                                                                                   |  |  |           |   |    |      |       |                     |
| 6 | Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row(1000mm Dia). |  |  |           |   |    |      |       | Total (Cum) 319.340 |
|   |                                                                                                   |  |  | Ch.0.00km | 2 | 0  | 2.5  |       | 0.00                |
|   |                                                                                                   |  |  |           |   |    |      |       | Total (in m) 0.00   |

AR  
15/6/22  
7E

AR  
15/6/22  
AE

h.17.6.22  
Executive Engineer  
Rural Works Department  
Work Division, Triveniganj

## Calculation of Seigniorage Fees

DETAILED ESTIMAE FOR TEMPORARY RESTORATION OF ROAD FROM CHUI WORLD BANK TO  
NAME OF ROAD :- CHAUDHARY TOLA (SAHPUR), GIRDHARPATTI HAT VIA MIRRAPATTI  
BLOCK :- CHHATAPUR

| S.No | SOR NO   | DESCRIPTION OF ITEMS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | QTY    | UNIT | RATE    | AMOUNT    |
|------|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|---------|-----------|
| 1/1  | 12.3     | Sand filling in Foundation Trenches as per Drawing & Technical Specification                                                                                                                                                                                                                                                                                                                                                                                                                            |        |      |         |           |
|      |          | Sand                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 117.60 | Cum  | 116.85  | 13741.56  |
| 2.2  | A/R      | Providing & laying Brick Bat...                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |        |      |         |           |
|      |          | Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.                                                                                                                                                                                                                                                              |        |      |         |           |
|      |          | Brick Bats                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 321.30 | Cum  | 1032.00 | 331581.60 |
| 3.7  | 5.7.40.1 | Labour filling empty cement bags with loocal sand, stitching the bags and placing including supply of sutli and EC bag etc. all complete as per approved desing, specification and direction of E/I                                                                                                                                                                                                                                                                                                     |        |      |         |           |
|      |          | Sand                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 0.00   | Cum  | 116.85  | 0.00      |
| 4.8  | 5.7.40.2 | Providing, laying and filling Geo bags of size 1m X 0.7 m (Type A 300 GSM nonwoven) weight of bags 420g volume of filled bag 0.07m <sup>3</sup> weight of filled Geo bags 126 Kg with local sand including stitching in four lines by approved nylon thread with stitching machine and generator stacking and placing after loading unloading and carriage with help of trolley within 150m lead all complete as per specifications and direction of E/I (including Carriage of Local sand lead 0.5 km) |        |      |         |           |
|      |          | Sand                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 0.00   | Cum  | 116.85  | 0.00      |
| 5.9  | 401      | Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.                                                                                                                                                          |        |      |         |           |
|      |          | For Grading II Material (with Coarse Sand Screening)                                                                                                                                                                                                                                                                                                                                                                                                                                                    |        |      |         |           |
|      |          | Unit = Cum                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |        |      |         |           |
|      |          | Taking output = 300 cum                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |        |      |         |           |
|      |          | Coarse graded granular sub-base material as per Table 400.2                                                                                                                                                                                                                                                                                                                                                                                                                                             |        |      |         |           |
|      |          | 53 mm to 9.5mm @ 50 percent                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 180.00 | Cum  | 516.42  | 92955.60  |
|      |          | 9.5 mm to 2.36 mm @ 20 percent                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 72.00  | Cum  | 411.33  | 29615.76  |
|      |          | 2.36 mm below @ 30 percent (coarse Sand Screening)                                                                                                                                                                                                                                                                                                                                                                                                                                                      | 108.00 | Cum  | 185.94  | 20081.52  |
|      |          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |        |      |         | 142652.88 |
|      |          | Cost for 300 cum = a                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |        |      |         | 475.51    |
|      |          | Rate psr Cum = (a)/300                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |        | Cum  |         | 151849.24 |
|      |          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 319.34 | Cum  | 475.51  | 151849.24 |
|      |          | GSB Gr-II                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |        |      |         | 151849.24 |
|      |          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |        |      | TOTAL   | 497172.40 |
|      |          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |        |      | Say     | 49717.24  |
|      |          | Seigniorage Fees @10% of Basic Amount                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |        |      |         |           |

Ag  
15/6/22  
JE

Ag  
15/06/2022  
TAE

G.17.6.22  
EE

Executive Engineer  
Rural Development Department  
Work Division Irvinigan

## Estimate of Flood affected Road

NAME OF ROAD :- CHUI WORLD BANK TO CHAUDHARY TOLA (SAHPUR), GIRDHARPATTI BLOCK :- CHHATAPUR  
HAT VIA MIRRAPATTI

| S.No | SOR NO   | DESCRIPTION OF ITEMS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | QTY     | UNIT | RATE    | AMOUNT     |
|------|----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|------|---------|------------|
| 1    | 301.5    | Sand filling in Foundation Trenches as per Drawing & Technical Specification                                                                                                                                                                                                                                                                                                                                                                                                                              | 117.60  | Cum  | 549.11  | 64575.85   |
| 2    | A/R      | Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.                                                                                                                                                                                                                                                                | 321.30  | Cum  | 1922.87 | 617818.13  |
| 3    | 5.7.7    | Labour for cutting 62mm to 75 mm dia bamboo piles to size and making shoes and driving etc. complete job as per specification and direction of E/I                                                                                                                                                                                                                                                                                                                                                        | 0.00    | m    | 45.86   | 0.00       |
| 4    | 5.7.8    | Labour for fitting and fixing Split bamboo woven chachari in position with 20 swg G.I wire or 75 mm to 100 mm long nails alternatively including cost of G.I. wire or nails complete job as per specification and direction of E/I                                                                                                                                                                                                                                                                        | 0.00    | sqm  | 78.20   | 0.00       |
| 5    | 5.7.9    | Labour for fitting and fixing 75 mm dia bamboo runners in position at every vertical pole with 150 mm long nails or 38 swg G.I. wire including cost of G.I wire or nails complete job as per specification and direction of E/I                                                                                                                                                                                                                                                                           | 0.00    | m    | 5.31    | 0.00       |
| 6    |          | Supply of Bamboo at site.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 0.00    | nos. | 188.39  | 0.00       |
| 3    | 5.7.40.1 | Labour filling empty cement bags with loocal sand, stitching the bags and placing including supply of suttli and EC bag etc. all complete as per approved desing, specification and direction of E/I                                                                                                                                                                                                                                                                                                      | 0.00    | nos. | 36.10   | 0.00       |
| 4    |          | Providing, laying and filling Geo bags of size 1m X 0.7 m (Type A 300 GSM nonwoven) weight of bags 420g volume of filled bag 0.07m <sup>3</sup> . weight of filled Geo bags 126 Kg with local sand including stitching in four lines by approved nylon thread with stitching machine and generator stacking and placing after loading unloading and carriage with help of trolley within 150m lead all complete as per specifications and direction of E/I (including Carriage of Local sand lead 0.5 km) | 0.00    | Each | 172.18  | 0.00       |
| 5    | 401      | Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.                                                                                                                                                            | 319.340 | Cum  | 3010.64 | 961417.78  |
| 6    | 9.3      | Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Roww(1000mm Dia).                                                                                                                                                                                                                                                                                                                                                                                                        | 0.00    | m    | 4041.99 | 0.00       |
|      |          | Total                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |         |      | Rs.     | 1643811.76 |

AE  
15/6/22  
JE

AE  
15/6/2022

EE  
15/6.22

Executive Engineer  
Rural Works Department  
Work Division, Trivenigari