

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000

सत्यमेव जयते
INDIA

बिहार BIHAR

क्र.सं. 2172 11-05-2022 मुल्य साट नं. AP 045076

क्रेता का नाम एवं पता 21-7-2022 3/2/22 10/2/22 20/2/22

OFFICE OF THE EXECUTIVE ENGINEER, RURAL WORKS DEPARTMENT, LAKHISARAI

AGREEMENT NO:- 05 /MBD/2022-23

This agreement, made the 12th May Day of 2022 between Executive Engineer, RWD, Works Division, Lakhisarai, Govt. of Bihar Patna and M/s Satyandra Kr. & Co Constructions (P) LTD. G-7, Tara Tower, Exhibition Road, Patna-1.

Whereas the Employer is desirous that the Contractor execute output and performance based Rural Road Contract of the maintenance of road from MR-N/19-20/Lakhisarai/14 Package Under of Block in Lakhisarai, Suryagarha, Under M/R in Lakhisarai District and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein, at a cost of Construction Rs. 2,34,30,507 (Two Crore Thirty Four Lakh Thirty Thousand Five Hundred Seven) only & five year Maintenance cost Rs. 1,07,06,907 (One Crore Seven Lakh Six Thousand Nine Hundred Seven) only,

Sl. No.	Name of Road	Const. Cost	Maintenan ce cost	Agreement Value
1	Jhankhar Amhara Balgumar Path to Makhdumpur Path	14,32,106	7,60,588	21,92,694
2	NH-80 Jhakhar Via Balgudar, Ramnagar, Amhara	1,36,23,237	56,60,577	1,92,83,814

Satyendra Kumar and Co. Construction (P) Ltd.

21/05/2022
Director

12/05/22

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कुर्मु, ग्रामण्डल, लखीसराय
12/05/22

3	L053 (L033) to Agaiya	42,96,580	21,32,962	64,29,542
4	Arma Gramin Path	19,57,115	10,23,756	29,80,871
5	T05 to Ghoghi	21,21,469	11,29,024	32,50,493
Total		2,34,30,507	1,07,06,907	3,41,37,414

Total Cost Rs. 3,41,37,414 .00 (Three Crore Forty One Lakh Thirty Seven Thousand Four Hundred Fourteen) only

NOW THIS AGREEMENT WITNESSTH as follows:

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the condition of contract hereinafter referred to and they shall be deemed to from and be read and construed as part of this agreement.
2. In consideration of the payment to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all aspects with the provisions of the contract.
3. The Employer hereby covenants to pay the contractor in consideration of the Execution adcompletion of the works and the remedying the defects hear in Contract price or such other sum as may become payable under the provision of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be ready and construed as part of this Agreement viz
 - a. Latter of Acceptance
 - b. Contractor's Bid
 - c. Section VI –General Conditions
 - d. Section VII- Particular Condition
 - e. Section V – Technical Specification (General and Supplementary Technical Specification
 - f. Appendix A – Drawings
 - g. Section IV – Works Schedule
 - h. Quality plan for output and performance based road contract as per clause A14.1 of the technical specifications
 - i. Appendices of the contract
 - j. Addenda issued during bid period
 - k. Any other relevant documents listed in the particular conditions together with any post bid correspondence.

In witness whereof the parties thereto have caused this agreement to be executed the day and year first before written

Satyendra Kumar and Co. Construction (P) Ltd.

[Signature]
15/03/22
Director

[Signature]
12/05/22

[Signature]
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, लखीसराय

12/5/22

-:Contractor's BID :-

Attached separately

**NAME OF WORK:- MR-N/19-20 Lakhisarai/14 of Block in Lakhisarai,
Suryagarha, Under Lakhisarai District.**

District:- Lakhisarai

Block :- Lakhisarai, Suryagarha

Sl. No	Name of Road	Length (km)	Cost of Construction (Rs. In lacks)	Maintenance cost (Rs. In lacks)
1.	MR-N/19-20 Lakhisarai/14	12.317	234.30507	107.06907
Total		12.317	234.30507	107.06907

Satyendra Kumar and Co. Construction (P) Ltd.

Director

12/05/22
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
मुख्यालय, लखीसराय
12.5.22

OFFICE OF THE EXECUTIVE ENGINEER
RURAL WORKS DEPARTMENT, WORKS DIVISION, LAKHISARAI

AGREEMENT NO:-05/MBD/2022-23

**NAME OF WORK: - MR-N/19-20 Lakhisarai/14 of Block in Lakhisarai,
Suryagarha, Under Lakhisarai District.**

**NAME OF AGENCY: - M/s Satyendra Kr. & Co Constructions (P) LTD.
G-7, Tara Tower, Exhibition Road, Patna-1.**

**Reference :- Engineer in Chief
R.W.D works Bihar, Patna
Vide Letter No. 1724 . Date :- 12.04.2022**

**AGREEMENT AMOUNT – Main work:- 2,34,30,507.00
Maintenance work:- 1,07,06,907.00
Total Amount: - 3,41,37,414.00**

**Performance Security :- Deposited @ 2 % Next 8 % deducted from Bill
Date of Completion :- 12th May 2022
Date of Agreement :- 11th February 2023
No. of Item of Work :- As per B.O.Q (Nos)
Rate Quoted :- 2.40 % below (Two Point Four Zero percent below)**

Contractor Signature

**Executive Engineer
RWD, Works Division, Lakhisarai**

Satyendra Kumar and Co. Construction (P) Ltd.


Director




कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कृष्ण प्रमण्डल, लखीसराय
12-5-22

OFFICE OF THE EXECUTIVE ENGINEER
R.W.D.(W)DIVISION, LAKHISARAI

Letter no.....631...../

Lakhisarai, Date.....11.05.2022.....

From,

Executive Engineer
Rural Work Department,
Works Division, Lakhisarai

To

M/s Satyendra Kr. & Co Constructions (P) LTD.
Engineers & Contractors G-7, Tara Tower,
Exhibition Road, Patna-1.

Sub :- Letter for acceptance for Const. of Road Form MR-N/19-20 Lakhisarai/14.

Dear Sir,

This is notify you that the Employer, namely Executive Engineer, R.W.D. (W) Division, Lakhisarai cum PIU BRRDA has accepted your Bid dated for execution of the Const. of Road Form MR-N/19-20 Lakhisarai/14 and routine maintenance of the works for five years for the Contract Price of Rupees 3,41,37,414/- (Rs. Three Crore Forty One Lacs Thirty Seven Thousand Four Hundred Fourteen) only as corrected and modified in accordance with the instructions to Bidders is hereby accepted.


You are hereby requested to furnish Performance Security, (and additional security for unbalanced bids in terms of ITB Clause 27.3 and clause 27.4) [where applicable] in the form detailed in Cl. 32 of ITB for an amount of Rs. 2,60,000/- (Rupees Two Lakh Sixty thousand) only within 10 days of the receipt of this letter of acceptance valid up to 45 days from the date of expiry of Defects Liability Period i.e. up to..... and sign the contract, failing which action as stated in Cl.32.3 of ITB will be taken. "If the performance Security is in the form of a Bank Guarantee, the period of validity of Bank Guarantee could be one year initially, however, the Contractor would get this Bank Guarantee extended in such a way that an amount equal to requisite performance security is always available with employer until 45 days after the lapse of Defect liability period."

Letter of Acceptance

Satyendra Kumar and Co. Construction (P) Ltd.

Director

Yours faithfully,


Executive Engineer
R.W.D.(W)Division,
Lakhisarai
11-05-22

बिहार सरकार
ग्रामीण कार्य विभाग

पत्रांक- मु0अ0-4(मु0)-निविदा-09-152/2019 - पार्ट - 5.1724653 पटना, दिनांक-12/4/2022
प्रेषक,

अशोक कुमार मिश्रा,
अभियंता प्रमुख,
ग्रामीण कार्य विभाग,
पटना, बिहार।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल- लखीसराय एवं झंझारपुर।

विषय:- शीर्ष 3054 अंतर्गत दिनांक-04.04.2022 को सम्पन्न विभागीय निविदा समिति की बैठक की कार्यवाही के संबंध में।

महाराज,

उपर्युक्त विषयांकित विभागीय समिति की बैठक की कार्यवाही संलग्न कर भेजते हुए निदेश दिया जाता है कि आवंटित कार्यों के त्वरित कार्यान्वयन हेतु सफल निविदाकारों को 24 घंटे के भीतर Letter of Acceptance (LOA) निर्गत / उपलब्ध कराना सुनिश्चित करेंगे।

निदेश है कि जिन - जिन निविदाकार को आपके द्वारा Letter of Acceptance (LOA) निर्गत किया जा रहा है उसकी एक प्रति ज्ञापन लगाकर नोडल पदाधिकारी 3054 को मेल के द्वारा उपलब्ध कराना सुनिश्चित करें।

एकरारनामा की विवरणी MIS पर Upload कराना भी सुनिश्चित किया जाय। इस प्रगति से भी नोडल पदाधिकारी 3054 को अवगत कराना सुनिश्चित करेंगे।

निर्धारित समय सीमा में निर्दिष्ट कार्य का पूरा किया जाना अनिवार्य है।

अनु0:- यथोक्त।

विश्वासभाजन

(अशोक कुमार मिश्रा)
अभियंता प्रमुख

ज्ञापांक:- मु0अ0-4(मु0)-निविदा-09-152/2019 - पार्ट - 5.1724 (अ3) पटना, दिनांक-12/4/2022
प्रतिलिपि:- अनु0 के साथ मुख्य अभियंता -2, एवं 3 ग्रामीण कार्य विभाग, बिहार, पटना/अधीक्षक अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, मुंगेर एवं दरभंगा को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।

ज्ञापांक:- मु0अ0-4(मु0)-निविदा-09-152/2019 - पार्ट - 5.1724 (अनु) पटना, दिनांक-12/4/2022
प्रतिलिपि:- IT प्रबंधक, ग्रामीण कार्य विभाग को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित।

अभियंता प्रमुख

बिहार सरकार
ग्रामीण कार्य विभाग

दिनांक:- 4/4/2022 को सम्पन्न विभागीय निविदा समिति की बैठक की कार्यवाही

उपस्थिति :-

श्री पंकज कुमार पाल, सचिव, ग्रामीण कार्य विभाग
ई० अशोक कुमार मिश्रा, अभियंता प्रमुख, ग्रामीण कार्य विभाग।
ई० अमरेन्द्र कुमार सिन्हा, मुख्य अभियंता-2
ई० निर्मल कुमार, मुख्य अभियंता-3
श्री आमीर नैय्यर, आंतरिक वित्तीय सलाहकार, ग्रामीण कार्य विभाग।

2. बैठक में शीर्ष 3054 योजनान्तर्गत E-tendering के माध्यम से प्राप्त की गयी 02 निविदाओं के तकनीकी बीडों पर अभियंता प्रमुख की अध्यक्षता में गठित तकनीकी बीड समिति द्वारा तकनीकी बीड में योग्य किये गये निविदाकारों के वित्तीय बीड के प्रस्ताव पर विचार हेतु निविदा समिति के समक्ष उपस्थापित किया गया, जिन पर सम्यक विचारोपरांत निम्नवत् निर्णय लिया गया :-

SL No.	Division	Package No./ Tender Id	Date of Tender Received	AA Amount (in Lacs)	Total No. of Bidders	No. of Tech. Qualified Bidders	Bidder's Name	Bid Amount (in Lacs)	Quoted Rate (%)	Tender Award Amount (in Lacs)	Remarks
1	Lalhiara	MR-N/19-20 Lalhiara/54 (Tender ID-111228)	01.07.2021	578.386	3	2	Satyendra Kumar and Co. Construction Pvt. Ltd. (Bid ID-472364)	349.76859	(-) 2.40	341.31414	युक्त राशि पर निर्णय करा गया
							Subesh Kumar (Bid ID-472950)		(-) 0.07		
2	Banjarhar	MR-N/19-20 Banjarhar/54 (Tender ID-114895)	03.12.2021	376.993	1	1	Pankaj Jha (Bid ID-489257)	418.81089	(-) 0.11	418.34800	युक्त राशि पर निर्णय करा गया

3. स्वीकृत निविदाओं के कार्य आवंटन आदेश निम्नांकित शर्तें पर निर्गत किए जाते हैं।
- इन योजनाओं पर सक्षम प्राधिकार द्वारा प्रशासनिक अनुमोदन तथा तकनीकी स्वीकृति प्रदान की गयी है एवं परिमाण विपत्र अनुमोदित है।
 - वांछित अग्रघन की राशि MBD/SBD के अनुरूप है।
पैकेज संख्या, रोड का नाम, परिमाण विपत्र की राशि, तकनीकी स्वीकृति की राशि, संवेदक द्वारा उद्धृत दर, परक्रमित दर, Bid Capacity आदि सही है।
 - संवेदक Defaulter/ काली सूची/ कार्यों को लंबित रखने वाले संवेदकों की सूची में नहीं है।
4. एकरारनामा के पूर्व संबंधित कार्यपालक अभियंता निविदा में सभी अभिलेख की मूल प्रति से सत्यापित कर संतुष्ट हो लेंगे।
5. निविदा समिति द्वारा सर्वसम्मति से कॉलम 3 में वर्णित पैकेज सं० एवं कॉलम 8 में वर्णित निविदाकारों द्वारा कॉलम 10 में वर्णित दर पर कॉलम 11 में वर्णित राशि पर कार्य करने की स्वीकृति दी जाती है।
6. संबंधित अधीक्षण अभियंता एकरारनामा (GCC) की सभी कंडिकाओं के अनुपालन सुनिश्चित कराने हेतु नियमित अन्तराल पर कार्यों का भौतिक पर्यवेक्षण करेंगे।
7. निविदा निष्पादन के क्रम में किसी प्रकार की त्रुटि पाये जाने पर मुख्यालय को सूचित किया जाए।
8. कार्य आवंटन आदेश में संवेदक का निबंधन संख्या, पूर्ण पता एवं दूरभाष संख्या अवश्य अंकित किया जाए।

Satyendra Kumar and Co. Construction (P) Ltd.

Director


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमुख लखीसराय

12-5-22


Scanned by CamScanner

9. कार्यपालक अभियंता यह सुनिश्चित करेंगे कि MBD के ITB की कंडिका 17.2(c) के आलोक में Earnest Money/ Security Deposit/ Performance Security के रूप में दिए गए Bank Guarantee बिहार में अवस्थित राष्ट्रीय/अनुसूचित बैंकों द्वारा ही निर्गत हो तथा विहित अवधि के लिए मान्य हो, साथ ही संबंधित शाखा से सत्यापित किया गया हो।
10. परिमाण विपत्र की दर से कम उद्धृत दर वाले निविदाकार के लिए Additional Performance Guarantee का प्रावधान पथ निर्माण विभाग की अधिसूचना सं०-447 (एस) दिनांक 16.01.2020 एवं विभागीय पत्रांक-292 (अनु०), दिनांक 16.01.2020 के आलोक में एकरारनामा के पूर्व संबंधित कार्यपालक अभियंता जमा कराना सुनिश्चित करेंगे।


(आमीर नैय्यर)
आंतरिक वित्तीय सलाहकार
ग्रामीण कार्य विभाग।



(अमरेन्द्र कुमार सिन्हा)
मुख्य अभियंता-2
ग्रामीण कार्य विभाग।


(निर्मल कुमार)
मुख्य अभियंता-3
ग्रामीण कार्य विभाग।


(अशोक कुमार मिश्रा)
अभियंता प्रमुख
ग्रामीण कार्य विभाग।


(पंकज कुमार पाल)
सचिव
ग्रामीण कार्य विभाग।




कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, ~~सुखीसराय~~
12-5-22

Name of Work: Construction of Road & CD Works for Jharkhar Amhera Belgumer Path To Mahdumpur Path
in Lakhisarai Block Under M/R 3054

Contract No: Civil Works/

PRINT

HELP

Bidder Name:	SCHEDULE OF WORKS				Excess (+)	%
Sl. No.	Description of work	No. or Qty.	Unit	Figure	Estimated Rate	AMOUNT Rs. P
1	Clearing and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 303.1	0.170	Hect	51101.12	Rupees Fifty One Thousand One Hundred & One and Paise Twelve Only	8667.19
2	Construction of Subgrade and Earthen Shoulders :- Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1	498.000	Cum	189.41	Rupees One Hundred & Eighty Nine and Paise Forty One Only	94326.18
3	Granular Sub-base with Well Graded Material (Table 400.1) :- Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, making by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	11.440	Cum	1289.91	Rupees One Thousand Two Hundred & Eighty Nine and Paise Ninety One Only	14756.57
4	WBM Grading 2 :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 402.	10.870	Cum	2409.06	Rupees Two Thousand Four Hundred & Nine and Paise Six Only	26186.48
5	WBM Grading 3 :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 402.	17.020	Cum	1993.92	Rupees One Thousand Nine Hundred & Ninety Three and Paise Ninety Two Only	33936.52
6	Prime Coat :- Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	226.970	Sqm	42.35	Rupees Forty Two and Paise Thirty Five Only	9612.18
7	Patch work over WBM using Mix seal surface for bituminous and Existing CC Pavement :- Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 503.	249.470	Sqm	165.07	Rupees One Hundred & Sixty Five and Paise Seven Only	41180.01
8	Tack Coat :- Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydrolac broom as per technical specification clause 503.	3468.650	Sqm	14.40	Rupees Fourteen and Paise Forty Only	49951.44
9	Semi-Dense Bituminous Concrete :- Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 506 complete in all respects.	80.490	Cum	9380.88	Rupees Nine Thousand Three Hundred & Eighty and Paise Sixty Nine Only	755051.74
10	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC 8 lying in position including painting and printing, etc as per drawing and technical specification clause 1703. Km stone	2.000	Each	2068.94	Rupees Two Thousand & Sixty Eight and Paise Ninety Four Only	4137.88

Signature of Tenderer with seal

Satyendra Kumar and Co. Construction (P) Ltd.

(Signature)
Director

Scanned by CamScanner

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमुख, सुपौल

Inviting Authority: Engg-in Chief RWD Patna

VALIDATE

Name of Work: Construction of Road & CD Works for Jharkhar Anshu Balgumar Path To Makhumpur Path in Lakhisarai Block Under M/R 3054

Contract No: Civil Works

Bidder Name:

Excess (+)

%

Sl. No.	Description of work	No. or Qty	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
11	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC-8 fixing in position including painting and printing etc as per drawing and technical specification clause 1703, 200 m stone	4.000	Each	583.63	Rupees Five Hundred & Eighty Three and Paise Sixty Three Only	2334.52
12	Direction and Place Identification signs with size more than 0.9 sqm size board - Retro-reflectors Traffic Signs Providing and erecting direction and place identification retro-reflectors sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701 2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron post 75 mm x 75 mm x 6 mm, 2 Nos firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause	1.920	Sqm	12209.36	Rupees Twelve Thousand Two Hundred & Nine and Paise Thirty Six Only	23441.97
13	Providing and fixing of retro-reflectors cautionary, mandatory and informatory sign as per IRC-67 made of encapsulated lens type reflective sheeting vide Clause 1701 2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 (600	7.000	Each	3545.20	Rupees Three Thousand Five Hundred & Forty Five and Paise Twenty Only	24816.40
14	Providing and fixing of retro-reflectors cautionary, mandatory and informatory sign as per IRC-67 made of encapsulated lens type reflective sheeting vide Clause 1701 2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 (600 mm	4.000	Each	3674.78	Rupees Three Thousand Six Hundred & Seventy Four and Paise Seventy Eight Only	14699.12
15	Providing and fixing of retro-reflectors cautionary, mandatory and informatory sign as per IRC-67 made of encapsulated lens type reflective sheeting vide Clause 1701 2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 (600 mm	2.000	Each	3545.68	Rupees Three Thousand Five Hundred & Forty Five and Paise Sixty Six Only	7091.32
16	Providing and fixing of retro-reflectors cautionary, mandatory and informatory sign as per IRC-67 made of encapsulated lens type reflective sheeting vide Clause 1701 2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 (900 mm	2.000	Each	7538.46	Rupees Seven Thousand Five Hundred & Thirty Eight and Paise Forty Six Only	15076.92
17	Providing and laying Rumble Strip with road studs and Thermoplastic Compound with Reflecting Glass Beads on Bituminous Surface	7.500	Sqm	735.03	Rupees Seven Hundred & Thirty Five and Paise Three Only	5512.73
18	Boundary Pillar/Guard Post - Reinforced cement concrete M15 grade boundary pillar/local stone of standard design as per IRC-25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	8.000	Each	512.34	Rupees Five Hundred & Twelve and Paise Thirty Four Only	4098.72
19	Printing New Letters and Figures of any Shade - Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	352.000	per cm height per letter	0.53	Rupees and Paise Fifty Three Only	186.56

Signature of Tenderer with seal

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, लखीसराय

Satyendra Kumar and Co. Construction (P) Ltd.

Director

Scanned by CamScanner

Name of Work: Construction of Road & CD Works for Jharkhar Amhara Balgumar Path To Makdumpur Path
in Lakhisarai Block Under M/R 3054

Contract No: Civil Works

VALIDATE

PRINT

HELP

Bidder Name:

Excess (+)

%

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
20	Planting of Trees and their Maintenance for one Year :- Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/slugde manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	14.000	Each	819.92	Rupees Eight Hundred & Nineteen and Paise Ninety Two Only	11478.88
21	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface :- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 The finished surface to be level, uniform and free from cracks and holes	170.000	Sqm	735.03	Rupees Seven Hundred & Thirty Five and Paise Three Only	124955.10
22	(I) Providing and Fixing 'Logo' of Maintenance Project :- Providing and fixing of typical informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	2.000	Each	9508.88	Rupees Nine Thousand Five Hundred & Eight and Paise Eighty Eight Only	19017.76
Cost of Construction :-						1290536.19
Add 12% GST						154864.34
Add 1% Labour Cess						12905.36
Seigniorage Fee 10% on Basic Cost of Mines Material						9015.91
Total Cost of Construction :-						1467321.80
23	5 Year Maintenance Cost	20.00	Quarterly	34,197.45	Rupees Thirty Four Thousand One Hundred & Ninety Seven and Paise Forty Five Only	683949.00
Cost of Maintenance :-						683949.00
Add 12% GST						82073.88
Add 1% Labour Cess						6839.49
Seigniorage Fee 10% on Basic Cost of Mines Material						6428.46
Total Cost of Maintenance :-						779290.83
Total Cost of Project Including Five Year Maintenance :-						2246612.63
Quoted Rate in Words		Rupees Fourteen Lakh Sixty Seven Thousand Three Hundred & Twenty One and Paise Eighty Only				

22.01.22
E-1

13/05/22

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, लुखीसराय

Satyendra Kumar and Co. Construction (P) Ltd.

Director

Scanned by CamScanner