



804
28-8-2029
AG 383453
SUPPLEMENTARY AGREEMENT FROM

Chapra -2

Agreement No.

Rate :-

Date of Start :-

12/12/22

Date of Completion :-

Time Allowed - Month

This agreement made the between **RURAL WORKS DEPARTMENT (Govt. of Bihar)** Authorized address at 5th floor, Vishweshwaraiya Bhawan, Jawaharal Nehru Marg, Patna-800013, Executive Engineer, R.W.D., Works Division, Chapra - 2 (herein after called "the Employer") of the one part and **Shivcon E State Pvt. Ltd., At. - Madho Bihari Lane, Salempur, Dist. - Saran (Chapra)** (herein after called "the Contractor" of the one part.)

PAN No. :- AANCS0861R

GST No. :- 10AANCS0861R1ZY

Whereas the Employer is desirous that the Contractor execute Output and Performance based मुख्यमंत्री ग्राम संपर्क योजना (NDB) BRICS अंतर्गत (Package No. - MMGSY-NDB-BRRP-129-Chapra-2) Tender ID - 82274, BID ID - 372207

Sl. No.	Block	Package No.	Name of Road	Main Work Amount	Maintenance Amount	Grand Total
1	Jasapur Jalalpur	MMGSY-NDB-BRRP-129-Chapra-2	Panchayat Eshwan Ashok Nagar Se Barka Gawn Kakarhat.	23909742.00	1995211.00	25904953.00
			Total Rs.	23909742.00	1995211.00	25904953.00

(hereinafter called "the Works") and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein, **0.09% Below**, at a Cost of Main Work Rs. 23909742.00 + Maintenance Work Rs. 1995211.00 Grand Total Rs. 2,59,04,953.00 (Two Crore Fifty Nine Lakh Four Thousand Nine Hundred Fifty Three only)

NOW THIS AGREEMENT WITNESS as follows :

- In this Agreement, Works and expression shall have the same meanings as are respectively assigned to them in the conditions of contract hereinafter referred to and they shall be deemed to form and be read and construed as part of this Agreement.
- In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the

For

Shivcon Estates Pvt. Ltd.

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, छपरा-2

- Works and remedy any defects therein in conformity in all aspects with the provisions of the contract.
3. The Employer hereby covenants to pay the Contractor in consideration the Execution and completion of the Works and the remedying the defects wherein Contract Price or such other sum as may become payable under the provision of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be ready and construed as part of this Agreement viz.
- (i) Letter of Acceptance
 - (ii) Contractor's Bid
 - (iii) Section VI – General Conditions,
 - (iv) Section VII – Particular Conditions
 - (v) Section V- Technical Specifications (General and Supplementary Technical Specifications)
 - (vi) Appendix A - Drawings
 - (vii) Section IV – Works Schedule
 - (viii) Quality Plan for Output and Performance Based Road Contract as per Clause A14.1 of the Technical Specifications.
 - (ix) Appendices to the Contract
 - (x) Addenda issued during bid period
 - (xi) Any other relevant documents listed in the Particular Conditions together with any post bid correspondence.

In Witness where of the parties there to have caused this agreement to be executed the day and year first before written.

The common Seal of Employer

Was here into affix in Presence of (i)

(ii)


Signed Sealed and Delivered by the said to

Shivcon E State Pvt. Ltd., At. – Madho Bihari Lane, Salempur, Dist. - Saran (Chapra)

In the presence of (i)

(ii)

Binding Signature of Employer
For


Shivcon E State Pvt. Ltd.

Binding Signature of contractors


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, छपरा-2
ACD
28/6/17

अधीक्षण अभियन्ता का कार्यालय
ग्रामीण कार्य विभाग, कार्य अंचल, छपरा।

पत्रांक: ...634...

छपरा, दिनांक...15/6/21.....

प्रेषक,

अधीक्षण अभियन्ता,
ग्रामीण कार्य विभाग,
कार्य अंचल, छपरा।

सेवा में,

कार्यपालक अभियन्ता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, छपरा-2

विषय :- मुख्यमंत्री ग्राम संपर्क योजना (NDB) BRICS योजनान्तर्गत पुनरीक्षित परिमाण विपत्र अनुमोदनोपरान्त लौटाने के संबंध में।

प्रसंग :- आपका पत्रांक 1069 अनु0 दिनांक 12.06.2021

महाशय,

उपर्युक्त विषय के संबंध में कहना है, कि मुख्यमंत्री ग्राम संपर्क योजना (NDB) BRICS 01 (एक) पथ का पुनरीक्षित परिमाण विपत्र अनुमोदनोपरान्त अग्रेतर कारवाई हेतु भेजा जा रहा है। जो निम्नलिखित है :-

क्र० सं०	पथ का नाम	प्राक्कलित राशि (लाख में)
1	Panchyat Bhawan Ashok Nagar Se Barka Gawn Kakar hat.	2,59,28,289


अनु० :- परिमाण विपत्र एक प्रति में।

विश्वासभाजन


अधीक्षण अभियन्ता,
ग्रामीण कार्य विभाग,
कार्य अंचल, छपरा।

For 
Shivcon Estates Pvt. Ltd.


कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, छपरा-2


28/6/21

Miting Authority: Engg-in Chief RWD Patna

Work : Panchyat Bhawan Ashok Nagar Se Barka Gawn Kakar hat.

act No: Civil Works/

SCHEDULE OF WORKS						
Sl. No.	Description of work	No. or Qty.	Unit	Excess (+)		AMOUNT Rs.
				Figure	Words	
1	Setting Out Setting Out as MORD Specification 100 Item Nos (i), (ii), (iii) & (iv) Construction of Reference & Working Benchmarks	4.00	nos	3883.52	Rupees Three Thousand Eight Hundred Eighty Three And Paise Fifty Two Only	15534.09
2	Construction of Reference Pillars/Burjees	17.00	nos	1792.60	Rupees One Thousand Seven	30474.19
3	Clearing and Grubbing Road Land Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300 mm, removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150 mm in thickness as per Technical Specification Clause 201. By Manual Means In area of non-thorny jungle	1.46	Hect.	49739.47	Rupees Forty Nine Thousand Seven Hundred Thirty Nine And Paise Forty Seven Only	72768.84
4	Excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross-sections, and transporting to the embankment location with a lift upto 1.5 m and lead upto 1000 m as per Technical Specification Clause 302.3	190.63	Cum	82.01	Rupees Eighty Two And Paise One Only	15634.62
5	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m, transporting to the site spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m & 100 m as per Technical Specification Clause 301.5. For 1000 m lead @ 30 %	1291.18	Cum	187.23	Rupees One Hundred Eighty Seven And Paise Twenty Three Only	241742.03
6	Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m, transporting to the site spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m & 100 m as per Technical Specification Clause 301.5. For 100 m lead @ 70 %	3012.74	Cum	142.39	Rupees One Hundred Forty Two And Paise Thirty Nine Only	428984.13
7	Construction of Subgrade Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1. Construction of subgrade	2280.29	Cum	189.11	Rupees One Hundred Eighty Nine And Paise Eleven Only	431218.74
8	Granular Sub-base with Well Graded Material (Table 400.1) Construction of granular sub-base by providing well graded material (Crushed Stone Aggregates and Sand), spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with three wheel 80-100 kN static roller capacity to achieve the desired density, complete as per Technical Specification Clause 401. Grading I Material.	2315.03	Cum	2777.74	Rupees Two Thousand Seven Hundred Seventy Seven And Paise Seventy Four Only	6430548.11

For
Shircon Estates Pvt. Ltd.

कार्यपालक अभियंता
सड़क मधीन कार्य विभाग
नगर कार्य प्रमंडल, छपरा-2

Sl. No.	Description of Work	Unit	Quantity	Rate	Amount	Remarks
10	M Grading 3 Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405. (A) By Manual Means	Cum	1122.45	3/69.81	Rupees Three Thousand Seven Hundred Sixty Nine And Paise Eighty One Only	629357.58
11	Prime Coat (Low Porosity) Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0kg/sqm using mechanical means as per Technical Specification Clause 502	Sqm	11532.38	54.57	Rupees Fifty Four And Paise Fifty Seven Only	213764.38
12	Tack Coat Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25-0.30kg per sqm on the prepared granular surfaces treated with primer & cleaned with Hydraulic broom as per Technical Specification Clause 503. Mix Seal Surfacing Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509	Sqm	11532.38	18.54	Rupees Eighteen And Paise Fifty Four Only	2985466.75
13	Cement Concrete Pavement M30 Construction of un-reinforced, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and water finishing to lines and grade as per drawing and Technical Specification Clause 1501.	Cum	702.50	7637.71	Rupees Seven Thousand Six Hundred Thirty Seven And Paise Seventy One Only	5365449.61
14	Hard Shouldering Laying brick soling layer on prepared sub-grade with brick on end edging according to lines, graded and cross-section shown on the drawing filling joints with sand and earth, spreading 25mm thick layer of earth over brick soling, watering and rolling the same with three wheel road roller 80-100 kn as per Technical specification clause 412.	Sqm	582.50	472.80	Rupees Four Hundred Seventy Two And Paise Eighty Only	275403.60
15	Kilometre Stone Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703	Each	1.00	4627.55	Rupees Four Thousand Six Hundred Twenty Seven And Paise Fifty Five Only	4627.55
16	Kilometre Stone Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703 Ordinary Kilometer Stone (Precast)	Each	5.00	2550.51	Rupees Two Thousand Five Hundred Fifty And Paise Fifty One Only	12752.56

कार्यपालक अभियंता
सड़क विभाग
कार्य प्रमंडल, छपरा-2

For
Shivcon Estates Pvt. Ltd.

	Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 in position including painting and printing, etc as per drawing and Technical Specification Clause 03 200 m stone (precast) MMGSY BRICS (NDB) Sign Board Providing and fixing of typical MMGSY BRICS (NDB) Informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	17.00	Each	665.97	Rupees Six Hundred Sixty Five And Paise Ninety Seven Only	11321.55
		3.00	Each	10199.47	Rupees Ten Thousand One Hundred Ninety Nine And Paise Forty Seven Only	30598.40
19	Retro-reflectors Traffic Signs Providing and fixing of retro-reflectors cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 600 mm equilateral & triangle.	18.00	Each	4537.40	Rupees Four Thousand Five Hundred Thirty Seven And Paise Forty Only	81673.16
20	Retro-reflectors Traffic Signs Providing and fixing of retro-reflectors cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 600 mm side circle.	10.00	Each	5789.89	Rupees Five Thousand Seven Hundred Eighty Nine And Paise Eighty Nine Only	57898.85
21	Retro-reflectors Traffic Signs Providing and fixing of retro-reflectors cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 600 mm x 450 mm rectangular	6.00	Each	5661.68	Rupees Five Thousand Six Hundred Sixty One And Paise Sixty Eight Only	33970.07
22	Boundary Pillar Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	34.00	Each	576.26	Rupees Five Hundred Seventy Six And Paise Twenty Six Only	19592.93
23	Road Marking with Hot Applied Thermoplastic Compound with Reflectors Glass Beads on Bituminous Surface & Cement Concrete Pavement Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes	603.00	Sqm	850.93	Rupees Eight Hundred Fifty And Paise Ninety Three Only	513110.24

For
Shirton Estates Pvt. Ltd.

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
नारायण प्रमंडल, छपरा-2

Marking with Hot Applied Thermoplastic Compound with Reflectors Glass Beads on
 Continuous Surface & Cement Concrete Pavement Providing and laying of hot applied thermoplastic
 compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area, thickness of 2.5
 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform
 and free from streaks and holes.

26	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	93.15	Cum	261.90	Rupees Two Hundred Sixty One And Paise Ninety Only	24396.27
27	Type B (First Class) Bedding Laying (First Class) bedding on well compacted Local sand, approved material.	10.65	Cum	459.68	Rupees Four Hundred Fifty Nine And Paise Sixty Eight Only	4895.56
28	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC M-15	8.10	Cum	5862.05	Rupees Five Thousand Eight Hundred Sixty Two And Paise Five Only	47482.61
29	Head wall in Brick masonry work in cement mortar (1:4) in substructure complete excepting pointing and plastering, as per drawing and technical specification Clauses 602, 603, 604, 1202 & 1204	70.10	cum	5619.07	Rupees Five Thousand Six Hundred Nineteen And Paise Seven Only	393897.12
30	Providing and laying RCC pipe NP3 (600 mm dia) Providing and laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets clauses 1106	37.50	M	3190.42	Rupees Three Thousand One Hundred Ninety And Paise Forty Two Only	119640.81
31	Plastering with CM 1:4 Plastering with CM 1:4 15mm thick on brickwork in substructure as per technical specification clause 613.4 & 1204	70.10	sqm	158.33	Rupees One Hundred Fifty Eight And Paise Thirty Three Only	11099.24
32	Painting on Concrete/Steel Surfaces with Epox Painting two coats including prime coat with epoxy paint of approved brand on concrete/steel surfaces after through cleaning of surface to give an even shade as per drawing and Technical Specification Clause 1701	70.10	sqm	133.70	Rupees One Hundred Thirty Three And Paise Seventy Only	9372.40
33	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. i) Upto 3 m depth	96.01	cum	261.90	Rupees Two Hundred Sixty One And Paise Ninety Only	25145.32
34	PCC GRADE M15 : Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203	12.00	cum	5862.05	Rupees Five Thousand Eight Hundred Sixty Two And Paise	70344.60
35	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (PCC M - 20)	60.93	cum	6625.38	Rupees Six Thousand Six Hundred Twenty Five And Paise	403684.27
36	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 (PCC - M20)	40.87	cum	6852.23	Rupees Six Thousand Eight Hundred Fifty Two And Paise	280050.80
37	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7	24.00	nos	96.48	Rupees Ninety Six And Paise Forty Eight Only	2315.58
38	(RCC GRADE M-20) Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204	3.84	cum	6852.23	Rupees Six Thousand Eight Hundred Fifty Two And Paise	26312.58
39	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202	0.07	ton	69726.07	Rupees Sixty Nine Thousand Seven Hundred Twenty Six And Paise Seven Only	4880.82
39	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 a) With Local Sand	72.00	cum	459.68	Rupees Four Hundred Fifty Nine And Paise Sixty Eight Only	33096.76

कार्यपत्रक अभियंता
 राज्य सार्वजनिक कार्य विभाग
 राज्य प्रमंडल, छपरा-2

Shri Ram State Pvt. Ltd.

... with smaller size towards the soil and bigger size towards the wall and providing over the surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8

	firm with smaller size towards the soil and bigger size towards the wall and providing over the surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8	10.00	m	449.16	Rupees Four Hundred Forty Nine And Paise Sixteen Only	4491.57	
	Providing PCC M-20 architectural coping on the top of wing wall, return wall etc. complete as per drawing and technical specification Clauses 615, 710 and 1204.3.11	6.48	Cum	7982.28	Rupees Seven Thousand Nine Hundred Eighty Two And Paise	51725.19	
	R.C.C.- M25 Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5	0.70	ton	70755.30	Rupees Seventy Thousand Seven Hundred Fifty Five And Paise Thirty Only	49528.71	
43	Supplying, fitting, and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications Clauses 1002, 1010 and 1202	15.00	m	37.04	Rupees Thirty Seven And Paise Four Only	555.66	
44	Providing and filling joint sealing compound as per drawing and technical specification with coarse sand and 6 % bitumen by weight	1.00	Year	142756.98	Rupees One Lakh(s) Forty Two	142756.98	
45	Maintenance for 1st year	1.00	Year	174383.88	Rupees One Lakh(s) Seventy	174383.88	
46	Maintenance for 2nd year	1.00	Year	447749.64	Rupees Four Lakh(s) Forty	447749.64	
47	Maintenance for 3rd year	1.00	Year	564813.82	Rupees Five Lakh(s) Sixty Four	564813.82	
48	Maintenance for 4th year	1.00	Year	667305.01	Rupees Six Lakh(s) Sixty Seven	667305.01	
49	Maintenance for 5th year					25928289.49	
Total Estimated Cost in Figures					25928289.49	25928289.00	
Quoted Amount							
Quoted Rate in Words							
Rupees Two Crore Fifty Nine Lakh(s) Twenty Eight Thousand Two Hundred Eighty Nine Only							

मधुबनी 21/6/21
 (J.E)
 Revised B.O.B. approved for Rs. 2,59,28,289/- (Rupees two crores fifty nine lakhs twenty eight thousand two hundred and eighty nine only).
 Him Laksh twenty Eight thousand four hundred and eighty nine only.

District Engineer
 (Sponsoring) Deptt.
 Rural (Works) Chapra
 Works Circle,

For
 Shivcon Pvt. Ltd.

WJLW
 2/9/21