

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपय

THOUSAND RUPEES

1000

1000

INDIA



नं. 193/0 दि. 18/08/2021 को श्री सुबेश कुमार (पुनः)
 एवं श्री ए. ए. सिंह (पुनः) के बीच
 कार्य/समय का कार्य करार का
 9000 (नौ हजार) रुपये का
 9410 X 9 - 9000 को

AL 281876



OFFICE OF THE EXECUTIVE ENGINEER
 RURAL WORKS DEPARTMENT, WORKS DIVISION, LAKHISARAI

AGREEMENT NO:- 07/MBD/2021-22

This agreement, made the 18th August day of 2021 between Executive Engineer, RWD, Works Division, Lakhisarai, Govt. of Bihar Patna and Sri Subesh Kumar, Karyanand Nagar, Lakhisarai, Bihar.

Whereas the Employer is desirous that the Contractor execute output and performance based Rural Road contract for the maintenance of road from MR-N/19-20/Lakhisarai/11 Package Under M/R in Lakhisarai District

SI	Name of Road	Block	Length (in KM)	Const. Cost.	Maint. Cost.	Agree. Value
1	T02 Balahpur More to T06 Khutukpar More	Chanan	6.200	9158854	4615446	13774300

(Signature)

(Signature)

(Signature)
 18-8-21
 Executive Engineer
 Rural Works Department
 Work Division, Lakhisarai
 18-8-21

2	To4 Pratappur to Sadai Bigha	Barhiya	4.060	10558914	3773014	15003388
	Total		8.260	19717768	8388460	28106228

and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein, at a cost of Construction Rs. 1,97,17,768.00 (Three Crore Eleven Lakh Fifty Nine Thousand Five Hundred Eighteen) only & five year Maintenance cost Rs. 83,88,460.00 (Sixty Two Lakh Sixty Eight Thousand Ninety Four) only total cost **Rs. 2,81,06,228.00 (Two Crore Eighty One Lakh Six Thousand Two Hundred Twenty Eight) only**

NOW THIS AGREEMENT WITNESSTH as follows:

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the condition of contract hereinafter referred to and they shall be deemed to from and be read and construed as part of this agreement.
2. In consideration of the payment to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all aspects with the provisions of the contract.
3. The Employer hereby covenants to pay the contractor in consideration of the Execution adcompletion of the works and the remedying the defects hear in Contract price or such other sum as may become payable under the provision of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be ready and construed as part of this Agreement viz
 1. Letter of Acceptance
 2. Contractor's Bid
 3. Section VI -General Conditions
 4. Section VII- Particular Condition
 5. Section V - Technical Specification (General and Supplementary Technical Specification
 6. Appendix A - Drawings
 7. Section IV - Works Schedule
 8. Quality plan for output and performance based road contract as per clause A14.1 of the technical specifications
 9. Appendices of the contract
 10. Addenda issued during bid period
 11. Any other relevant documents listed in the particular conditions together with any post bid correspondence.

In witness whereof the parties thereto have caused this agreement to be executed the day and year first before written

[Signature]

[Signature]

[Signature]
18.8.2021
Executive Engineer
Rural Works Department
Work Division, Lakhisarai
Rakshita
18.8.21

OFFICE OF THE EXECUTIVE ENGINEER
RURAL WORKS DEPARTMENT, WORKS DIVISION, LAKHISARAI

AGREEMENT NO:- 07/MBD/2021-22

**NAME OF WORK: - MR-N/19-20/Lakhisarai/11 Package Under M/R in
Lakhisarai District**

NAME OF AGENCY: - Sri Subesh Kumar,
Karyanand Nagar, Purani Bazar,
Lakhisarai.

Reference :- Engineer in Chief
R.W.D Bihar, Patna
Vide Letter No. 3206 Date :- 11.08.2021

AGREEMENT AMOUNT – Main work:- 1,97,17,768.00
Maintenance work:- 83,88,460.00
Total Amount: - 2,81,06,228.00


Performance Security: - Deposited @ 2 % Next 8 % deducted from Bill

Date of Commencement :- 18th August 2021

Date of Completion :- 17th May 2022

No. of Item of Work :- As per B.O.Q (Nos)

Rate Quoted :- 0.00% below (Zero point f Zero Zero percent below)


Contractor Signature


18/8/21


Executive Engineer
Rural Works Department
Work Division, Lakhisarai
Rakshit
18-8-21



Name of Work: Construction of Road & CD Works for T02 Bataspur More To T06 (Khutukpar More) In Chanan Block Under M/R (3)

PRINT

Contract: Civil Works

HELP

Bidder Name: Excess (+) %

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P.
				Figure	Words	
1	Cleaning and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 201.1 and direction of E/I	1.06	Hect.	49464.05	Rupees Forty Nine Thousand Four Hundred & Sixty Four and Paise Five Only	52431.89
2	<u>Construction of Subgrade & Earthen Shoulder</u> Construction of subgrade & earthen shoulders with approved material obtained from borrow pits with all lifts and lead, transporting to site, spreading, grading to required slope and compacted to meet requirement of Tables 300.2 with lead upto 1000m as per Technical Specification Clause 301.4.1	2382.00	Cum.	181.11	Rupees One Hundred & Eighty One and Paise Eleven Only	431404.02
3	<u>Granular Sub-base with Well Graded Material (Table 400.1) Gr-I</u> Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with three wheel 80-100 kN static roller capacity to achieve the desired density, complete as per Technical Specification Clause 401	89.62	Cum	1536.98	Rupees One Thousand Five Hundred & Thirty Six and Paise Ninety Eight Only	137744.15
4	<u>WBM Grading 2</u> Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405.	86.75	Cum	2770.80	Rupees Two Thousand Seven Hundred & Seventy and Paise Eighty Only	245636.50
5	<u>WBM Grading 3</u> Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.	137.02	Cum	2401.26	Rupees Two Thousand Four Hundred & One and Paise Twenty Six Only	329012.84
6	<u>Prime Coat (Low porosity)</u> Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502.	513.81	Sqm	41.71	Rupees Forty One and Paise Seventy One Only	21431.15
7	<u>Tack coat</u> Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydrioc broom as per technical specification clause 503	20737.56	Sqm	14.27	Rupees Fourteen and Paise Twenty Seven Only	295824.98

Signature of Tenderer with seal

Executive Engineer
Rural Works Department
Work Division, Lakhisarai



Name of Work: Construction of Road & CD Works for T02 Bataspur More To T06 (Khutukpar More) In Chanan Block Under M/R (3)



Contract: Civil Works/



Bidder Name:


Excess (+)

%

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
8	Mix seal surface wist waste plastic :- Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509.	663.81	Sqm	198.15	Rupees One Hundred & Ninety Eight and Paise Fifteen Only	131533.95
9	Semi-Dense Bituminous Concrete :- Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects.	501.85	Cum	9576.15	Rupees Nine Thousand Five Hundred & Seventy Six and Paise Fifteen Only	4805790.68
10	Construction of un-reinforced plain cement thickness as per design, over a prepared sub base with 43 grade cement or any other type as per clause 1501.2.2 M 30 grade coarse and fine aggregate maximum size of aggregate not exceeding 25mm, mixed in a concrete of not less than 0.2cum capacity and appropriate weigh batcher using approved mix design laid in approved	45.21	Nos	6080.50	Rupees Six Thousand & Eighty and Paise Fifty Only	280979.91
11	Kilometre Stone Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703 5th km stone	1.00	Nos	3832.18	Rupees Three Thousand Eight Hundred & Thirty Two and Paise Eighteen Only	3832.18
12	Kilometre Stone Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703 Ordinary Kilometer Stone (Precast)	5.00	Nos	2003.87	Rupees Two Thousand & Three and Paise Eighty Seven Only	10019.35
13	Kilometre Stone Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703 200 m stone (precast)	26.00	Nos	578.60	Rupees Five Hundred & Seventy Eight and Paise Sixty Only	15043.60
14	Direction and Place Identification signs with size more than 0.9 sqm size board Retro-reflectorised Traffic Signs Providing and erecting direction and place identification retro-reflectorised sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos. firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause 1701.	1.92	Sqm	12285.48	Rupees Twelve Thousand Two Hundred & Eighty Five and Paise Forty Eight Only	23589.12

Signature of Tenderer with seal

Executive Engineer
Rural Works Department
Rural Works Division, Lakhisarai



PRINT

Name of Work: Construction of Road & CD Works for T02 Bataspur More To T06 (Khutukpar More) in Chanan Block Under M/R (3)

Contract No.: Civil Works

HELP

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
15	Retro-reflectorised Traffic Signs :- Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 600 mm equilateral & triangle	19.00	Nos	3546.09	Rupees Three Thousand Five Hundred & Forty Six and Paise Nine Only	67375.71
16	Retro-reflectorised Traffic Signs :- Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 600 mm circular	8.00	Nos	3579.81	Rupees Three Thousand Six Hundred & Seventy Nine and Paise Eighty One Only	29438.48
17	Retro-reflectorised Traffic Signs :- Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 600 mm x 450 mm rectangular	3.00	Nos	3549.40	Rupees Three Thousand Five Hundred & Forty Nine and Paise Forty Only	10648.20
18	Retro-reflectorised Traffic Signs :- Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 900 mm octagon stop board	2.00	Nos	7582.12	Rupees Seven Thousand Five Hundred & Eighty Two and Paise Twelve Only	15164.24
19	Boundary Pillar/Guard Post Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC:25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	48.00	Nos	508.34	Rupees Five Hundred & Eight and Paise Thirty Four Only	24400.32
20	Printing New Letters and Figures of any Shade :- Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	352.00	per cm height per letter	0.51	Rupees and Paise Fifty Only	177.76
21	Planting of Trees and their Maintenance for one Year Planting of trees by the road side (Avenue trees) in 0.60 m dia holes, 1 m deep dug in the ground, mixing the soil with decayed farm yard/sludge manure, planting the saplings, backfilling the trench, watering, fixing the tree guard and maintaining the plants for one year	26.50	Each	798.20	Rupees Seven Hundred & Ninety Eight and Paise Twenty Only	21152.30

Signature of Tenderer with seal

Executive Engineer
Rural Works Department
Work Division, Lakhisarai

Tender Inviting Authority: Engg-In Chief RWD Patna

Name of Work: Construction of Road & CD Works for T02 Bataspur More To T06 (Khutukpar More) In Chanan Block Under M/R (3)

Contract No: Civil Works/

Excess (+)

%

Bidder

Name:

SCHEDULE OF WORKS

Estimated Rate

AMOUNT
Rs. p

Sl. No.	Description of work	No. or Qty.	Unit	Figure	Words	AMOUNT Rs. p
22	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area. thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes. FOR BT	1060.00	Sqm	882.99	Rupees Eight Hundred & Eighty Two and Paise Ninety Nine Only	935965.40
23	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 gms per sqm area. thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes. for pcc	30.00	Sqm	968.17	Rupees Nine Hundred & Sixty Eight and Paise Seventeen Only	29045.10
24	Providing and fixing of typical MMGSY informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	3.00	Nos	9346.28	Rupees Nine Thousand Three Hundred & Forty Six and Paise Twenty Eight Only	28038.84
25	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	17.28	Cum	6189.84	Rupees Six Thousand One Hundred & Eighty Nine and Paise Eighty Four Only	106960.44
26	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	120.96	Cum	153.47	Rupees One Hundred & Fifty Three and Paise Forty Seven Only	18563.73
27	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	351.36	Sqm	95.63	Rupees Ninety Five and Paise Sixty Three Only	33600.58

Cost of Construction :- 8105180.58

Add 1% Labour Cess 81051.81

Add 12% GST 972621.67

Total Cost of Construction :- 9158854.05



Executive Engineer
Rural Works Department
Work Division, Lakhisarai

18.8.21

Signature of Tenderer with seal

Tender Inviting Authority: Engg-in Chief RWD Patna

☒ VALIDATE

Name of Work: Construction of Road & CD Works for T02 Batespur More To T06 (Khutukpar More) In Chanan Block Under M/R (3)

☐ PRINT

Contract: 3: Civil Works/

☐ HELP

Bidder Name:

Excess (+)

%

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
28	Five Year Routine Maintenance	20.00	Quarterly	2,04,211.45 208000.70	Rupees Two Lakh Eight Thousand Six Hundred & Fifty Nine and Paise Seventy Only	4084433.00 4173194.00
				40,84,433 =	Cost of Maintenance :-	4173194.00
				40,84,433 =	Add 1% Labour Cess	41731.94
				49,13,276 =	Add 12% GST	500783.28
				46,15,409 =	Total Cost of Maintenance :-	4715709.22
					Total Cost of Project Including Five Year Maintenance :-	13874563.27
Quoted Rate in Words				Rupees One Crore Thirty Eight Lakh Seventy Four Thousand Five Hundred & Sixty Three and Paise Twenty Seven Only		

Say - ~~1,38,74,563.00~~
1,37,74,300.00

18/08/11

18.8.21
Executive Engineer
Rural Works Department
Work Division, Lakhisarai

18.8.21

Signature of Tenderer with seal

E. E. Letter No. 262 Dt. 5.3.2020
 Construction Cost Rs. 91,58,854.00
 5 yrs. Maintenance Cost Rs. ~~47,15,709.00~~ 46,15,409
 Total Cost Rs. ~~1,38,74,563.00~~ 1,37,74,263
 BOC Rs. ~~1,38,74,600.00~~ 1,37,74,300.00
 (Rupee: One crore thirty eight lakh
Seventy four thousand three hundred only)
 including 5 yrs Maintenance Vide
 Item no. 01 to 28

4/-
 5/3/20
 Superintending Engineer
 Rural Works Department
 Works Circle, Munger
 5.3.2020

Executive Engineer
 Rural Works Department
 Work Division, East Champaran

बिहार सरकार ग्रामीण कार्य विभाग

दिनांक- 06/08/2021 को सम्पन्न विभागीय निविदा समिति की बैठक की कार्यवाही उपस्थिति:-

श्री पंकज कुमार पाल, सचिव, ग्रामीण कार्य विभाग।

ई0 अशोक कुमार मिश्रा, अभियंता प्रमुख, ग्रामीण कार्य विभाग।

ई0 अमरेन्द्र कुमार सिन्हा, मुख्य अभियंता-2

ई0 कमलेश चौधरी, मुख्य अभियंता-3

श्री आमीर नैय्यर, आंतरिक वित्तीय सलाहकार, ग्रामीण कार्य विभाग।

2 बैठक में मुख्य शीर्ष 3054 अंतर्गत e-tendering के माध्यम से प्राप्त की गयी पुनर्निविदा में एकल निविदा के तकनीकी बीड पर संबंधित मुख्य अभियंता की अध्यक्षता में गठित तकनीकी बीड समिति द्वारा तकनीकी बीड में योग्य किये गये निविदाकार के वित्तीय बीड के प्रस्ताव पर विचार हेतु विभागीय निविदा समिति के समक्ष उपस्थापित किया गया है। पुनर्निविदा पर सम्यक् विचारोपरान्त निम्नवत् निर्णय लिया गया:-

SL No	Division	Package No / Tender Id	Date of Tender Received	AA Amount (in lacs)	Total Bidders	No. of Tech. Qualified Bidders	Bidder's Name	Bid Amount (In lacs)	Quoted Rate (%)	Tender Award Amount (In Lacs)	Remarks
1	2	3	4	5	6	7	8	9	10	11	12
1	Lakhisarai	MR-N/19-20 Lakhisarai/03 (Tender Id-106725)	15.02.2021	253.64000	1	1	Ganesh Sai Contractor and Construction Pvt. Ltd. (Bid ID - 451961)	252.65092	(-) 0.02	252.60039	पुनर्निविदा। अतः एकल निविदा स्वीकृत।
2	Lakhisarai	MR-N/19-20 Lakhisarai/11 (Tender Id-106727)	15.02.2021	300.50700	1	1	Subesh Kumar (Bid ID - 454285)	281.06228	0.00	281.06228	पुनर्निविदा। अतः एकल निविदा स्वीकृत।
3	Araria	MR-N/19-20 Araria/11 (Tender Id-102578)	22.12.2020	274.30100	1	1	Dev Brothers Construction Pvt. Ltd. (Bid ID - 441291)	193.49828	0.00	193.49828	पुनर्निविदा। अतः एकल निविदा स्वीकृत।
4	Madhubani	MR-N/19-20 Madhubani/17 (Tender Id-94133)	16.06.2020	340.11900	5	1	Ajay Kumar (Bid ID - 407634)	339.57058	(-) 0.55	337.70294	पुनर्निविदा। अतः एकल निविदा स्वीकृत।

3. उक्त कार्यों की तकनीकी बीड का निष्पादन मुख्य अभियंता-2 एवं मुख्य अभियंता-3 की अध्यक्षता में गठित तकनीकी बीड समिति द्वारा की गई है।

4 मुख्य अभियंता-2 एवं मुख्य अभियंता-3 अपने स्तर से भली- भौति जाँच लेगें की संवेदक

Defaulter/कोई कार्यों को लंबित रखने वाले संवेदक की सूची में नहीं है।


5. स्वीकृत्यादेश निर्गत करने से पूर्व मुख्य अभियंता अपने स्तर से संतुष्ट हो लेंगे कि इन योजना पर सक्षम प्राधिकार द्वारा तकनीकी स्वीकृति प्रदान की गयी है एवं परिमाण विपत्र अनुमोदित है।


6. कार्यपालक अभियंता, कार्य प्रमण्डल, लखीसराय, अररिया एवं मधौरा, एम0बी0डी0 के प्रावधानों के अनुरूप सफल एकल निविदाकार से एकरारनामा करने से पूर्व वांछित Performance Guarantee की राशि जमा कराना सुनिश्चित करेंगे।

तदनुसार निविदा समिति द्वारा सर्वसम्मति से बिहार लोक निर्माण संहिता भाग-1 के नियम-163 के आलोक में तालिका में वर्णित निविदा पर सहमति दी जाती है।


6/8/21

(आमीर नैय्यर)
आंतरिक वित्तीय सलाहकार
ग्रामीण कार्य विभाग।


(अमरेन्द्र कुमार सिन्हा)
मुख्य अभियंता-2
ग्रामीण कार्य विभाग।


6/8/21
(कमलेश चौधरी)
मुख्य अभियंता-3,
ग्रामीण कार्य विभाग।



6/8/21
(अशोक कुमार मिश्रा)
अभियंता प्रमुख,
ग्रामीण कार्य विभाग।


(पंकज कुमार पाल)
सचिव
ग्रामीण कार्य विभाग।

ज्ञापांक:- मु0अ0-4(मु0) निविदा-09-61/2021 3206

पटना, दिनांक-11/8/2021

प्रतिलिपि:- मुख्य अभियंता-2, एवं मुख्य अभियंता-3 ग्रामीण कार्य विभाग को अग्रेतर कार्रवाई हेतु प्रेषित।


11/8/21
अभियंता प्रमुख
ग्रामीण कार्य विभाग।



18-8-21




बिहार सरकार
कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, लखीसराय

प्रामाणित किया जाता है कि 3054(MR)/ नई अनुरक्षण नीति 2018 योजनान्तर्गत T02_Bataspur_More - T06_Khutukpur_More पथ का निर्माण कार्य पूर्ण कर दिया गया है, जिसमें कनीय अभियंता द्वारा मापी पुस्त संख्या 697 में दर्ज सभी मदों की मापी जॉच शत प्रतिशत की गई एवं सहायक अभियंता के द्वारा इस 50 प्रतिशत की गई तथा कार्यपालक अभियंता के द्वारा 10 प्रतिशत मापी की जॉच की गई, जो गुणवत्ता पूर्ण एवं विशिष्टियों के अनुरूप है।


21.11.22
कनीय अभियंता


21.11.22
सहायक अभियंता



21.11.22
कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल लखीसराय

बिहार सरकार
कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, लखीसराय

प्रामाणित किया जाता है कि 3054(MR)/ नई अनुरक्षण नीति 2018 के अन्तर्गत निर्मित T02_Bataspur_More - T06_Khutukpur_More पथ की कुल लम्बाई 6.200 कि०मी० है, जिसमें केवल 2.930 कि०मी० में कार्य पूर्ण हो सका क्योंकि आगे आरेखन पथ निर्माण विभाग को हस्तांतरित किया गया है। केवल निर्मित लम्बाई 2.930 कि०मी० के लिए राशि की अधियाचना की जा रही है।


21/11/22
जे

UH
21/11/22
जे


कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल लखीसराय