

(100)

Construction of Road With 5 Year maintenance Road from Package No-MR-N/2019-20 Belsand/03 Under M/R 3054 scheme And the employer has accepted the bid by The Contractor for the execution and completion of such works and remedying of any defects therein at a cost of rupees - 2,81,30,742.00 (Two Crore Eighty One lacs Thirty thousand Seven Hundred Fourty Two only)

NOW THIS AGREEMENT WITNESSETH as follows :

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the conditions of contract thereafter referred to, and they shall be form and be read and constructed as part of this agreement.
2. In consideration of the payments to made by the Employer to the Contractor as herein after mentioned, the contractor hereby covenants with Employer to execute and complete the works and remedy any defects therein in conformity I all aspects with the provisions of the contract.
3. The Employer hereby covenants to pay the contractor in consideration of the execution and completion of the works and the remedying the defects wherein the contract price or such other sum as may become payable under the provisions of contract at the times and in the manner prescribed by the contract.
4. The following documents shall be deemed to form and be read and constructed as part of this agreement , viz.
 - (i) Letter of Acceptance
 - (ii) Notice to proceed with the works
 - (iii) Contractor's Bid
 - (iv) Contract Data
 - (v) Special condition of contract and general conditions of contract.
 - (vi) Specifications

अमरसुन्दर

29/7/20
कार्यपालक अभिप्राय
ग्रामीण कार्य विभाग
कार्य प्रमण्डल बेलसन्द
29/07/2020

(vii) Drawings

(viii) Bill of Quantities and

(ix) Any other document listed in the contract Data as froming part the contract

In witness, where of the parties there to have caused this Agreement to be executed the day and year first before written.

The common seal of

Was hereunto affixed in the presence of

Signed, sealed and Delivered by the said

In the presence of

Binding signature of Employer

Binding signature of contractor.



29/7/20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
काठमाडौं
29/07/2020

AGREEMENT

1. Agreement No. :- MBD / 2020-21
2. Name of Work :- Construction of Road With 5 Year maintenance of Package No-MR-N/2019-20 Belsand/03 Under M/R 3054 scheme.
3. Name of Agency :- Amresh Kumar
Village+Post- Rasalpur, P.S- Dumra
Distt- Sitamarhi.
4. Construction Cost :- 2,16,86,612 = 0
5. Maintenance Cost :- 64,44,130 = 0
- Total :- 2,81,30,742 = 0
6. Performance Security Deposit :- BG - 17,35,200 = 0
7. B.G. No. / Bank :- Bank of India.
8. Work Allotted rate :- (-) 10% below.
9. The Employer shall retain S.D. of (8 %) of the amount from each payment due to the contractor until completion of the whole of the construction work. No security deposit / retention shall be retained from the payment for routine maintenance of work.
10. Date of written order to commence :- 29.07.2020
11. Time required for the work from date of written order to commence :- (09) Nine months
12. Total No. of Items :- 70 Nos.

Note : SBD Rules Terms and condition will be applicable.


Contractor


Executive Engineer
R.W.D., Works Division
Belsand

29/07/2020

57

Ordering Authority: Engg-in Chief RWD Patna

Name of Work: Construction of Road & CD Works from Dumrabana To Bhataulia Under MR

Contract No: Civil Works/

Bidder Name:		Excess (+)		%
--------------	--	--------------	--	---

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1.00	Cleaning and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or transported upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per Technical Specification Clause 201.1 and direction of E/I	0.84	ha	49496.70	Rupees Forty Nine Thousand Four Hundred Ninety Six And Paise Seventy Only	41577 23
2.00	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1.	1764.00	Cum	176.75	Rupees One Hundred Seventy Six And Paise Seventy Five Only	311787 00
3.00	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	188.98	Cum	2063.18	Rupees Two Thousand Sixty Three And Paise Eighteen Only	389895 75
4.00	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 50-100 kN static roller in stages to binder grade and camber, applying and spreading, crushable screening to fill-up the voids of coarse aggregate, watering and compacting to the required density following-2 as per Technical Specification Clause 405	146.56	Cum	3695.82	Rupees Three Thousand Six Hundred Ninety Five And Paise Eighty Two Only	541659 38

अमर कुमार

29/7/20
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रबंधन बलुआड
29/07/2020

No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMC F
				Figure	Words	
28.00	Construction of un-reinforced, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501 2.2 M-30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing); spreading the concrete with shovel, taked, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding emps, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14 days, using curing compound (where specified) and water finishing to lines and grade as per drawing and Technical Specification Clause 1501	20.43	Cum	7638.14	Rupees Seven Thousand Six Hundred Thirty Eight And Paise Fourteen Only	156047.20
29.00	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 500 and 1208.4	11.52	Cum	5286.93	Rupees Five Thousand Two Hundred Sixty Six And Paise Ninety Three Only	60675.03
30.00	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	80.64	Sqm	190.65	Rupees One Hundred Ninety And Paise Sixty Five Only	15374.01
31.00	Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	234.24	Sqm	95.63	Rupees Ninety Five And Paise Sixty Three Only	22400.37
32.00	Maintenance for 1st year	1.00	Year	104420.00	Rupees One Lakh(s) Four Thousand Four Hundred Twenty Only	104420.00
33.00	Maintenance for 2nd year	1.00	Year	383098.00	Rupees Three Lakh(s) Eighty Three Thousand	383098.00
34.00	Maintenance for 3rd year	1.00	Year	461966.00	Rupees Four Lakh(s) Sixty One Thousand Nine Hundred Sixty Six Only	461966.00
35.00	Maintenance for 4th year	1.00	Year	508423.00	Rupees Five Lakh(s) Eight Thousand Four Hundred Twenty Three Only	508423.00
36.00	Maintenance for 5th year	1.00	Year	1186350.00	Rupees Eleven Lakh(s) Eighty Six Thousand Three Hundred Fifty Only	1186350.00

अभिलेख

29/7/20
काय प्रमण्डल
29/7/20

(91)

Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
			Figure	Words	
Total Estimated Cost in Figures					1,33,77,497.95
37	1% Labour				1,33,774.98
38	12% GST				16,05,299.75
Quoted Amount				1,51,16,572.68	1,51,16,572.68
Quoted Rate in Words			Rupees One Crore Fifty One Lakh(s) Sixteen Thousand Five Hundred Seventy Two And Paise Sixty Eight Only		

MS
Co
EL

Approved 39 (thirty nine) items

Valuing Rs. 1,51,16,572.68 (Rs. one crore fifty one thousand five hundred seventy two and 68 paise)
is Corrected

S. E.

R W D WORKS CIRCLE
SITAMARHI

कार्यपालक अभियंता
राजीव कार्य विभाग
कार्य प्रणाली केन्द्र

29/07/2020

अमर उमर