



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

BIHAR RURAL ROADS PROJECT

Bihar Rural Development Agency (BRRDA)

Head :- F.D.R.

YEAR (2021-22)

STATE
DISTRICT
BLOCK
DIVISION

BIHAR
SUPAUL
CHHATAPUR
TRIVENIGANJ

**DETAILED ESTIMAE FOR TEMPORARY RESTORATION OF
ROAD FROM NEAR HOUSE OF BISWANATH THAKUR TO
BRAHMAN TOLA PRATAPGANJ PRIYAH ROAD LALGANJ**

Flood affected Length of Road	=	0.660 Km
TOTAL COST OF PAVEMENT	Rs	1,164,231
TOTAL PROJECT COST	Rs	1,164,231

Submitted By:
Executive Engineer
RWD (W) Division, Triveniganj

Prepared By:
Executive Engineer
RWD (W) Division, Triveniganj

Sl.No	District	Division	Road Name	Length(In Km.)	Length of Damage Part Due to Flood	Tentative Restoration Amount(In Lac)	Block
1	Supaul	Triveniganj	Chunni world bank to choudhary tola(sahpur), girdharipatti hat via mirrapatti.	9.3	0.3	60	Chhatapur
2	Supaul	Triveniganj	Mahdipur Bazar to Chatapur (Boader)	1	0.25	18	Chhatapur
3	Supaul	Triveniganj	L053-T01 To Narahiya (VR8)	2.585	0.35	19	Chhatapur
4	Supaul	Triveniganj	1.Construction of road from Lalji Chauk Harihar Path to Sohta Kachni Road with five years maintenance	11.97	0.3	44	Chhatapur
5	Supaul	Triveniganj	2.Construction of road from Chhatapur bus stand to Bhatta Bari Road with five years maintenance	3.18	0.2	36	Chhatapur
6	Supaul	Triveniganj	3. Construction of road from ChhatapurAnant Chowkto Bhatta Bari Road with five years maintenance.	1.485	0.1	20	Chhatapur
7	Supaul	Triveniganj	2 Construction of road from Raghunathpurto Faisya Kothi Road with five years maintenance.	9.375	2.12	64	Chhatapur
8	Supaul	Triveniganj	1.Construction of road from Chunni to Charney world Bank road with filve year maintenance	6.345	0.3	40	Chhatapur
9	Supaul	Triveniganj	2. Construction of road from Chhatapur Laxmipur to kunti road with five year maintenance	7.75	0.3	45	Chhatapur
10	Supaul	Triveniganj	3. Construction of road from Lalit gram Railway Station to Mahadev Patti with five year maintenance	2.055	0.4	34	Chhatapur
11	Supaul	Triveniganj	Near House of Bishwanath Thakur TO Brahaman Tola, Prataoganj Pariyahi Road Middle MMGSY[SC]hool (Lalganj)	2	0.15	50	Chhatapur
12	Supaul	Triveniganj	State Highway Se Ramjanki Chowk Middle School Chapin to Aariya Sima Birpur Path Via Ayub 72 RD Subki mandal tola middle school thuthi	8.165	0.4	34	Chhatapur
13	Supaul	Triveniganj	Pariyahi Pradhanmantri Sadak Se Pachim Ranipatti Nahar Ke Daya Bank to Udakishunganj SHW Nahar Pul Tak	5.035	0.15	75	Chhatapur
14	Supaul	Triveniganj	Bari Maszid Jhakhargadh TO Purab Mahadalit Tola Via Chohan, Sah, Mansuri, Mahadalit Tola	2	0.2	15	Chhatapur
15	Supaul	Triveniganj	SHW From House of Chhutharu Sahni to NH57 Naaharpul Via Mehta Mahadalit Tola.	3.55	0.15	12	Chhatapur
16	Supaul	Triveniganj	Jewacchpur Naya Bazar to Madhubani Sima Tak via Sarawatipur.	3.175	0.33	23	Chhatapur
17	Supaul	Triveniganj	L033-T01 To Lachmipur (VR9)	4.421	0.2	70	Chhatapur
18	Supaul	Triveniganj	31 No Road to Darhariya Sima PMGSY via Pariyadhar	3.54	0.15	40	Chhatapur
19	Supaul	Triveniganj	Madhopur Market to West North SHW Birpur Road via Uddhampur Sima	1.645	0.06	35	Chhatapur
20	Supaul	Triveniganj	SH Bus Stand Paschim Bakho Tola & Paswan Tola Hote Huye Genda Nadi Evam Mirchaiya Nadi Par Karte Huye Harripatti SH Tak	4.77	0.025	15	Chhatapur
21	Supaul	Triveniganj	East of SHW Kalam Dealer House to Anand Chowk	1.5	0.12	35	Chhatapur
22	Supaul	Triveniganj	Pradhanmantri Matiyani to Brahamotra Mushhari Tola	2.085	0.2	68	Chhatapur

जॉच प्रतिवेदन

13

ग्रा प्रमुख ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक-1890 दिनांक-22.04.2022 द्वारा अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, मधेपुरा की अध्यक्षता में गठित चार सदस्यीय द्वारा कार्य प्रमंडल, त्रिवेणीगंज के अंतर्गत वर्ष 2021-22 में बाढ़/अतिवृष्टि से क्षतिग्रस्त फलों के मोटरबुल कार्य के कृत कार्य मंदी की मात्रा का स्थलीय जॉच संबंधित सहायक अभियंता एवं अभियंता के साथ मापी लिया गया जो निम्न है :-

Location of Road :- NEAR HOUSE OF BISWANATH THKUR TO BRAHAMAN TOLA PARTAPGANJ PRIYAH ROAD LALGANJ.
Location Name :- Rural Works Department, Works Division, Triveniganj
Location :- Chhatapur

No.	Items of Works	Nos.	L (m)	B (m)	D (m) IN (Av.)	Quantity (m ³)
1	Construction of granular sub-base					
		4	30.0	3.8	0.15	67.50
		3	30.0	3.8	0.15	50.63
		8	25.0	3.0	0.15	90.00
		4	25.0	3.0	0.15	45.00
		5	30.0	3.8	0.15	84.38
					TOTAL=	337.50

23/5/22

23/05/2022
M.B.

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, सुपौल।

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बीरपुर।

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, त्रिवेणीगंज

कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, त्रिवेणीगंज समिति के जॉच प्रतिवेदन के अनुसार POST FACTO M.B. एवं POST FACTO प्राक्कलन तैयार कराकर सक्षम कार को अग्रतर कार्रवाई हेतु शीघ्र भेजें।

23/5/22

अधीक्षण अभियंता सह अध्यक्ष जॉच समिति
ग्रामीण कार्य विभाग
कार्य अंचल, मधेपुरा

SUMMARY OF COST ESTIMATE FOR THE PROJECT


NAME OF ROAD :- DETAILED ESTIMAE FOR TEMPRORY RESTORATION OF
ROAD FROM NEAR HOUSE OF BISWANATH THAKUR TO
BRAHMAN TOLA PRATAPGANJ PRIYAH ROAD LALGANJ


DIVISION :- TRIVENIGANJ


BLOCK :- CHHATAPUR

Flood Affected Length of Road :- 0.660 Km

Sr. No.	Description	Amount (In Rs.)
1	SAND BAG	-
2	BRICK BATS	-
3	EC BAG	-
4	GEO BAG	-
5	GRANULAR SUB BASE	1,016,091.00
6	HUME PIPE	-
	Total Cost =	1,016,091.00
	Add:-Labour Cess @1% amt. =	10,160.91
	Add:GST@12% on amt. =	121,930.92
	Add:S.F.@ 10% on Material =	16,048.45
	TOTAL RESTORATION COST OF THE PROJECT IN LACS	1,164,231



15/6/22
Junior Engineer
RWD (W) Division, Triveniganj


15/06/2022
Assistant Engineer
RWD (W) Division, Triveniganj
Chhatapur


11/7/22
Executive Engineer
RWD (W) Division, Triveniganj

Vide letter no 3110-4 (550) विविध कार्य - 23-29/2019-4849
dt 07/12/2024

Technically sanctioned for Rs 1164231.00/-
(Eleven lakh sixty four thousand two hundred thirty one only)


29/06/22
Superintending Engineer
Rural Works Department
Works Circle, Madhe

Details of Measurement

कार्य का ब्योरा Deatail of Work		संख्या No.	Measurement			मात्रा Quantity
			लम्बाई in m.	चौड़ाई In m.	In m.	
DETAILED ESTIMATE FOR TEMPORARY RESTORATION OF ROAD FROM NEAR HOUSE OF BISWANATH THAKUR TO BRAHMAN TOLA BRATADGANI DRIVAHU ROAD LALGANI						
NAME OF ROAD :-						
Item No. 1	Sand filling in Foundation Trenches as per Drawing & Technical Specification					
CH:-in		1	0	0.000	0.40	0.000
						0.000
Item No. 2	Providing and laying of Brick bat obtained from chimney with machedical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.					
CH:-in		2	0	3.750	0.150	0.000
CH:-in		2	0	3.750	0.150	0.000
						0.000
			Total (in Cum)			0.000
Item No. 3	Labour filling empty cement bags with loocal sand, stitching the bags and placing including supply of sutli and EC bag etc. all complete as per approved desing, specification and direction of E/I					
CH:-in		0	20	1.75	0.9	0.00
			Total (in cum)			0.00
	(0.034m3=1 no. of EC Bags)					0.00
			Total (in nos.)			0.00
Item No. 4	Providing, laying and filling Geo bags of size 1m X 0.7 m (Type A 300 GSM nonwoven) weight of bags 420g volume of filled bag 0.07m3. weight of filled Geo bags 126 Kg with local sand including stitching in four lines by approved nylon thread with stitching machine and generator stacking and placing after loading unloading and carriage with help of trolley within 150m lead all complete as per specifications and direction of E/I (including Carriage of Local sand lead 0.5 km)					
CH:-in		2	0	1.20	0.6	0.00
						0.00
	(0.076m3=1 no. of Geo Bags)					0.00
			Total (in nos.)			0.00
Item No. 5	Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause					
		4	30	3.75	0.150	67.5000
		3	30	3.75	0.150	50.6250
		8	25	3.00	0.150	90.0000
		4	25	3.00	0.150	45.0000
		5	30	3.75	0.150	84.3750
					Total (Cum)	337.500
Item No. 6	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row(1000mm Dia).					
Ch.0.00km		4	0	2.5		0.00
					Total (in m)	0.00

AP
15/6/22
7E

AP
15/06/2022
AE

Signature
Executive Engineer
Rural Works Department
Work Division, Triveniganj

Estimate of Flood affected Road

NAME OF ROAD :-

NEAR HOUSE OF BISWANATH THAKUR TO BRAHMAN TOLA
PRATAPGANJ PRIYAH ROAD LALGANJ

BLOCK :-

CHHATAPUR

S.No	SOR NO	DESCRIPTION OF ITEMS	QTY	UNIT	RATE	AMOUNT
1	301.5	Sand filling in Foundation Trenches as per Drawing & Technical Specification	0.00	Cum	549.11	0.00
2	A/R	Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.	0.00	Cum	1922.87	0.00
3	5.7.40.1	Labour filling empty cement bags with loocal sand, stitching the bags and placing including supply of sutli and EC bag etc. all complete as per approved desing, specification and direction of E/I	0.00	nos.	36.10	0.00
4		Providing, laying and filling Geo bags of size 1m X 0.7 m (Type A 300 GSM nonwoven) weight of bags 420g volume of filled bag 0.07m ³ . weight of filled Geo bags 126 Kg with local sand including stitching in four lines by approved nylon thread with stitching machine and generator stacking and placing after loading unloading and carriage with help of trolley within 150m lead all complete as per specifications and direction of E/I (including Carriage of Local sand lead 0.5 km)	0.00	Each	172.18	0.00
5	401	Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.	337.500	Cum	3010.64	1016091.00
6	9.3	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Roww(1000mm Dia).	0.00	m	4041.99	0.00
		Total			Rs.	1016091.00

AP
15/6/22
JE

AP
15/06/2022
AE

Signature
EE

Executive Engineer
Rural Works Department
Work Division, Triveniganj

Calculation of Seigniorage Fees

NAME OF ROAD :- BISWANATH THAKUR TO BRAHMAN TOLA PRATAPGANJ PRIYAH ROAD LALGANJ
BLOCK :- CHHATAPUR

DETAILED ESTIMAE FOR TEMPORARY RESTORATION OF ROAD FROM NEAR HOUSE OF

S.No	SOR NO	DESCRIPTION OF ITEMS	QTY	UNIT	RATE	AMOUNT
11	12.3	Sand filling in Foundation Trenches as per Drawing & Technical Specification				
		Sand	0.00	Cum	116.85	0.00
22	A/R	Providing & laying Brick Bat....				
		Providing and laying of Brick bat obtained from chimney with machanical means with all spreading, grading to required slope and compacted at OMC to acheive required density with all complete as per the direction of engineer in charge.				
		Brick Bats	0.00	Cum	1032.00	0.00
37	5.7.40.1	Labour filling empty cement bags with loocal sand, stitching the bags and placing including supply of sutli and EC bag etc. all complete as per approved desing, specification and direction of E/I				
		Sand	0.00	Cum	116.85	0.00
48	5.7.40.2	Providing, laying and filling Geo bags of size 1m X 0.7 m (Type A 300 GSM nonwoven) weight of bags 420g volume of filled bag 0.07m ³ . weight of filled Geo bags 126 Kg with local sand including stitching in four lines by approved nylon thread with stitching machine and generator stacking and placing after loading unloading and carriage with help of trolley within 150m lead all complete as per specifications and direction of E/I (including Carriage of Local sand lead 0.5 km)				
		Sand	0.00	Cum	116.85	0.00
59	401	Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.				
		For Grading II Material (with Coarse Sand Screening)				
		Unit = Cum				
		Taking output = 300 cum				
		Coarse graded granular sub-base material as per Table 400.2				
		53 mm to 9.5mm @ 50 percent	180.00	Cum	516.42	92955.60
		9.5 mm to 2.36 mm @ 20 percent	72.00	Cum	411.33	29615.76
		2.36 mm below @ 30 percent (coarse Sand Screening)	108.00	Cum	185.94	20081.52
		Cost for 300 cum = a				142652.88
		Rate psr Cum = (a)/300		Cum		475.51
			337.50	Cum	475.51	160484.49
		GSB Gr-II				160484.49
					TOTAL	160484.49
		Seigniorage Fees @10% of Basic Amount			Say	16048.45

AP
1576122

JE

AP
1576122

AE

EE

Signature

Executive Engineer
Rural Works Department
Work Division, Triveniganj