

बिहार सरकार
कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, लखीसराय

पत्रांक:- 641
सेवा में,

लखीसराय/ दिनांक:- 12-05-2022

M/s Satyendra Kr. and
Co. Construction (P) Ltd.

विषय:- शीर्ष M/R योजनान्तर्गत M/R-IV-18-20 Lakhisarai/114
निर्माण कार्य का कार्यादेश।

प्रसंग:- अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना का पत्रांक 1224 दिनांक 12-04-22
महाशय,

उपर्युक्त विषयक प्रासांगिक पत्र के आलोक में योजना का निर्माण कार्य हेतु आपके द्वारा
एकरारनामा संख्या- 05 M.B. D/12-23 सम्पन्न किया जा चुका है। तदनुसार कार्य प्रारंभ करने की
तिथि 12-05-22 एवं समाप्ति तिथि- 11-02-2023 है।

अतः आप संबंधित सहायक अभियंता एवं कनीय अभियंता, ग्रामीण कार्य विभाग, कार्य अवर
प्रमंडल/प्रशाखा, ~~पटना/प्रशाखा~~ से निरंतर सम्पर्क कर निर्धारित तिथि दिनांक- 11-02-2023 तक
प्राक्कलन के अनुरूप गुणवत्ता एवं विशिष्टियों के अनुरूप कार्य सम्पन्न करावें तथा कार्य प्रारंभ के पूर्व मध्य
एवं अन्त का फोटोग्राफी कार्य तालिका (Work Program) कनीय अभियंता एवं सहायक अभियंता के माध्यम
से अधोहस्ताक्षरी के कार्यालय को उपलब्ध कराना सुनिश्चित करेंगे।

विश्वासभाजन


12/05/22


12/5/22

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
प्रमंडल लखीसराय
12-05-22

पत्रांक :- 641 लखीसराय/ दिनांक:- 12-05-2022

प्रतिलिपि:- सहायक अभियंता एवं कनीय अभियंता, ग्रामीण कार्य विभाग, कार्य अवर प्रमंडल/प्रशाखा, ~~लखीसराय~~
को एकरारनामा के अभिप्रमाणित प्रति के साथ सूचनार्थ एवं एकरारनामा के अनुरूप कार्य प्रारंभ करवाना
सूनिश्चित करने हेतु प्रेषित। कार्य प्रारंभ के पूर्व मध्य एवं अंत कर निर्माण स्थल का फोटोग्राफी एवं कार्य
तालिका (Work Program) लेना सुनिश्चित करेंगे।


12/05/22


12/5/22

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
प्रमंडल लखीसराय
12-05-22

पत्रांक :- 641 लखीसराय/ दिनांक:- 15-02-22


प्रतिलिपि:- कार्यपालक अभियंता, क्षेत्रीय प्रयोगशाला, ग्रामीण कार्य विभाग, भागलपुर को एकरारनामा की प्रति
के साथ सूचनार्थ एवं आवश्यक कार्रवाई हेतु समर्पित।


12/05/22


12/5/22

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
प्रमंडल लखीसराय
12-05-22

Satyendra Kumar and Co. Construction (P) Ltd.


Director

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये

रु.1000

ONE THOUSAND RUPEES

Rs.1000

बिहार BIHAR

क्र.सं. ११७७

11-05-2022

मूल्य

साट नं.

AP 045076

क्रेता का नाम एवं पता

श्री १७७७ ११-०५-२०२२

११-०५-२०२२

OFFICE OF THE EXECUTIVE ENGINEER, RURAL WORKS DEPARTMENT, LAKHISARAI

AGREEMENT NO:- 05 /MBD/2022-23

This agreement, made the 12th May Day of 2022 between Executive Engineer, RWD, Works Division, Lakhisarai, Govt. of Bihar Patna and M/s Satyandra Kr. & Co Constructions (P) LTD. G-7, Tara Tower, Exhibition Road, Patna-1.

Whereas the Employer is desirous that the Contractor execute output and performance based Rural Road Contract of the maintenance of road from MR-N/19-20/Lakhisarai/14 Package Under of Block in Lakhisarai, Suryagarha, Under M/R in Lakhisarai District and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein, at a cost of Construction Rs. 2,34,30,507 (Two Crore Thirty Four Lakh Thirty Thousand Five Hundred Seven) only & five year Maintenance cost Rs. 1,07,06,907 (One Crore Seven Lakh Six Thousand Nine Hundred Seven) only,

Sl. No.	Name of Road	Const. Cost	Maintenan ce cost	Agreement Value
1	Jhankhar Amhara Balgumar Path to Makhdumpur Path	14,32,106	7,60,588	21,92,694
2	NH-80 Jhakhar Via Balgudar, Ramnagar, Amhara	1,36,23,237	56,60,577	1,92,83,814

Satyendra Kumar and Co. Construction (P) Ltd.

१२/०५/२०२२
Director

१४/०५/२२

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कुम्भग्रामण्डल, लखीसराय
१२/०५/२२

3	L053 (L033) to Agaiya	42,96,580	21,32,962	64,29,542
4	Arma Gramin Path	19,57,115	10,23,756	29,80,871
5	T05 to Ghoghi	21,21,469	11,29,024	32,50,493
Total		2,34,30,507	1,07,06,907	3,41,37,414

Total Cost Rs. 3,41,37,414 .00 (Three Crore Forty One Lakh Thirty Seven Thousand Four Hundred Fourteen) only

NOW THIS AGREEMENT WITNESSTH as follows:

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the condition of contract hereinafter referred to and they shall be deemed to from and be read and construed as part of this agreement.
2. In consideration of the payment to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all aspects with the provisions of the contract.
3. The Employer hereby covenants to pay the contractor in consideration of the Execution adcompletion of the works and the remedying the defects hear in Contract price or such other sum as may become payable under the provision of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be ready and construed as part of this Agreement viz
 - a. Latter of Acceptance
 - b. Contractor's Bid
 - c. Section VI –General Conditions
 - d. Section VII- Particular Condition
 - e. Section V – Technical Specification (General and Supplementary Technical Specification
 - f. Appendix A – Drawings
 - g. Section IV – Works Schedule
 - h. Quality plan for output and performance based road contract as per clause A14.1 of the technical specifications
 - i. Appendices of the contract
 - j. Addenda issued during bid period
 - k. Any other relevant documents listed in the particular conditions together with any post bid correspondence.

In witness whereof the parties thereto have caused this agreement to be executed the day and year first before written

Iyendra Kumar and Co. Construction (P) Ltd.

[Signature]
15/03/22
Director

[Signature]
14/05/22

[Signature]
12.5.22
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, लखीसराय
12522

OFFICE OF THE EXECUTIVE ENGINEER
RURALWORKS DEPARTMENT, WORKS DIVISION, LAKHISARAI

AGREEMENT NO:-05/MBD/2022-23

**NAME OF WORK: - MR-N/19-20 Lakhisarai/14 of Block in Lakhisarai,
Suryagarha, Under Lakhisarai District.**

**NAME OF AGENCY: - M/s Satyandra Kr. & Co Constructions (P) LTD.
G-7, Tara Tower, Exhibition Road, Patna-1.**

**Reference :- Engineer in Chief
R.W.D works Bihar, Patna
Vide Letter No. 1724 . Date :- 12.04.2022**

**AGREEMENT AMOUNT – Main work:- 2,34,30,507.00
Maintenance work:- 1,07,06,907.00
Total Amount: - 3,41,37,414.00**

**Performance Security :- Deposited @ 2 % Next 8 % deducted from Bill
Date of Completion :- 12th May 2022
Date of Agreement :- 11th February 2023
No. of Item of Work :- As per B.O.Q (Nos)
Rate Quoted :- 2.40 % below (Two Point Four Zero percent below)**


Contractor Signature

**Executive Engineer
RWD, Works Division, Lakhisarai**

Satyendra Kumar and Co. Construction (P) Ltd.


Director




कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कृषि प्रमण्डल, लखीसराय
12-5-22

OFFICE OF THE EXECUTIVE ENGINEER
R.W.D.(W)DIVISION, LAKHISARAI

Letter no. 631

Lakhisarai, Date 11.05.2022

From,

Executive Engineer
Rural Work Department,
Works Division, Lakhisarai

To

M/s Satyendra Kr. & Co Constructions (P) LTD.
Engineers & Contractors G-7, Tara Tower,
Exhibition Road, Patna-1.

Sub :- Letter for acceptance for Const. of Road Form MR-N/19-20 Lakhisarai/14.

Dear Sir,

This is notify you that the Employer, namely Executive Engineer, R.W.D. (W) Division, Lakhisarai cum PIU BRRDA has accepted your Bid dated for execution of the Const. of Road Form MR-N/19-20 Lakhisarai/14 and routine maintenance of the works for five years for the Contract Price of Rupees 3,41,37,414/- (Rs. Three Crore Forty One Lacs Thirty Seven Thousand Four Hundred Fourteen) only as corrected and modified in accordance with the instructions to Bidders is hereby accepted.

You are hereby requested to furnish Performance Security, (and additional security for unbalanced bids in terms of ITB Clause 27.3 and clause 27.4) [where applicable] in the form detailed in Cl. 32 of ITB for an amount of Rs. 2,60,000/- (Rupees Two Lakh Sixty Thousand) only within 10 days of the receipt of this letter of acceptance valid up to 45 days from the date of expiry of Defects Liability Period i.e. up to and sign the contract, failing which action as stated in Cl.32.3 of ITB will be taken. "If the performance Security is in the form of a Bank Guarantee, the period of validity of Bank Guarantee could be one year initially, however, the Contractor would get this Bank Guarantee extended in such a way that an amount equal to requisite performance security is always available with employer until 45 days after the lapse of Defect liability period."


Letter of Acceptance

Satyendra Kumar and Co. Construction (P) Ltd



Director

Yours faithfully,



Executive Engineer
R.W.D.(W)Division,
3rd Lakhisarai

11-05-22

Name of Work: Construction of Road & CD Works for L053 (L033) To Agalya in Chanan Block Under M/R 3054

PRINT

HELP

Contract No: Civil Works/

Bidder
Name:

Excess (+)

%

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P.
				Figure	Words	
1	Cleaning and Grubbing Road Land (By manual means) including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300mm, removals of stumps of such trees cut earlier & disposal of unserviceable materials & stacking of serviceable materials to be used or auctioned upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150mm in thickness as per technical specification clause 303.1	0.510	Hect	51101.12	Rupees Fifty One Thousand One Hundred & One and Paise Twelve Only	26061.57
2	Construction of Subgrade and Earthen Shoulders - Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1	1315.980	Cum	189.41	Rupees One Hundred & Eighty Nine and Paise Forty One Only	249259.77
3	Granular Sub-base with Well Graded Material (Table 400.1) - Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401	39.570	Cum	1501.45	Rupees One Thousand Five Hundred & One and Paise Forty Five Only	59412.38
4	WBM Grading 2 - Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 401	47.680	Cum	2758.62	Rupees Two Thousand Seven Hundred & Fifty Eight and Paise Sixty Two Only	131531.00
5	WBM Grading 3 - Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 401	74.400	Cum	2393.31	Rupees Two Thousand Three Hundred & Ninety Three and Paise Thirty One Only	178062.26
6	Prime Coat - Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 kg/sqm using mechanical means as per Technical Specification Clause 502	992.000	Sqm	42.72	Rupees Forty Two and Paise Seventy Two Only	42378.24
7	Patch work over WBM using Mix seal surface for bituminous and Existing CC Pavement - Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.9 mm (Type-A) or 13.2 mm to 0.9 mm (Type-B) aggregates using penetration grade bitumen to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 503	1041.500	Sqm	164.55	Rupees One Hundred & Sixty Four and Paise Fifty Five Only	171378.83
8	Tack Coat - Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared granular surface treated with Primer and cleaned with hydrioc broom as per technical specification clause 503	10688.260	Sqm	14.52	Rupees Fourteen and Paise Fifty Two Only	155193.54
9	Semi-Dense Bituminous Concrete - Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 506 complete in all respects.	241.170	Cum	9362.93	Rupees Nine Thousand Three Hundred & Sixty Two and Paise Ninety Three Only	2258057.83
10	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC 8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703. Km Stone	3.000	Each	2041.72	Rupees Two Thousand & Forty One and Paise Seventy Two Only	6125.16

Signature of Tenderer with seal

Name of Work: Construction of Road & CD Works for L053 (L033) To: Agalya in Chanan Block Under M/R 3054

PRINT

HELP

Contract No: Civil Works/

Bidder Name:

Excess (+)

%

SCHEDULE OF WORKS

Estimated Rate

AMOUNT
Rs. P

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		
				Figure	Words	
11	Reinforced cement concrete M15 grade kilometre local stone of standard design as per IRC 8 fixing in position including painting and printing, etc as per drawing and technical specification clause 1703, 200 m stone.	11 000	Each	579 09	Rupees Five Hundred & Seventy Nine and Paise Nine Only	6369 99
12	Direction and Place Identification signs with size more than 0.9 sqm size board - Retro-reflectonised Traffic Signs Providing and erecting direction and place identification retro-reflectonised sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701 2 3 fixed over aluminium sheeting, 2 mm thick with area exceeding 0.9 sqm supported on mild steel angle iron posts 75 mm x 75 mm x 6 mm, 2 Nos firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per approved drawing and Technical Specification Clause	1 920	Sqm	12192.17	Rupees Twelve Thousand One Hundred & Ninety Two and Paise Seventeen Only	23458 97
13	Providing and fixing of retro-reflectonised cautionary, mandatory and informatory sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701 2 3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 (600	15 000	Each	3532.30	Rupees Three Thousand Five Hundred & Thirty Two and Paise Thirty Only	52954 50
14	Providing and fixing of retro-reflectonised cautionary, mandatory and informatory sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701 2 3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 (600 mm	8 000	Each	3661.89	Rupees Three Thousand Six Hundred & Sixty One and Paise Eighty Nine Only	29295 12
15	Providing and fixing of retro-reflectonised cautionary, mandatory and informatory sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701 2 3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 (600 mm	3 000	Each	3532 77	Rupees Three Thousand Five Hundred & Thirty Two and Paise Seventy Seven Only	10558 31
16	Providing and fixing of retro-reflectonised cautionary, mandatory and informatory sign as per IRC 67 made of encapsulated lens type reflective sheeting vide Clause 1701 2 3 fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm x 450 mm x 600 mm, 600 mm below ground level as per drawings and Technical Specification Clause 801 (900 mm	2 000	Each	7525 56	Rupees Seven Thousand Five Hundred & Twenty Five and Paise Fifty Six Only	15051 12
17	Boundary Pillar/Guard Post - Reinforced cement concrete M15 grade boundary pillars/local stone of standard design as per IRC 25, fixed in position including finishing and lettering but excluding painting as per drawing and Technical Specification Clause 1704	56 000	Each	510 35	Rupees Five Hundred & Ten and Paise Thirty Five Only	28579 60
18	Printing New Letters and Figures of any Shade - Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawings and Technical Specification Clause 1701	352 000	height per	0 53	Rupees and Paise Fifty Three Only	185 56
19	Road Marking with Hot Applied Thermoplastic Compound with Reflectors using Glass Beads on Bituminous Surface - Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectors using glass beads @ 250 gms per sqm area thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC 35 The finished surface to be level, uniform and free from	509 400	Sqm	735 03	Rupees Seven Hundred & Thirty Five and Paise Three Only	374424 28


Signature of Tenderer with seal

Satyendra Kumar and Co. Construction (P) Ltd.

Director

Scanned by CamScanner

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमणिका लखीसराय



Name of Work: Construction of Road & CD Works for L053 (L033) To Agalya in Chanan Block Under M/R 3054

PRINT

HELP

Contract No: Civil Works/

Bidder
Name:

Excess (+)

%

SCHEDULE OF WORKS

Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
20	(i) Providing and Fixing 'Logo' of Maintenance Project :- Providing and fixing of typical informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm thick, top and middle plate duly welded with MS flat iron 25mm x 5m size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm of 12 SWG steel plate tube. All M S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1	2.000	Each	9483.09	Rupees Nine Thousand Four Hundred & Eighty Three and Paise Nine Only	18966.18
21	Plastering with cement mortar (1:4) on brick work in sub-structure as per Technical Specifications	40.320	Sqm	141.73	Rupees One Hundred & Forty One and Paise Seventy Three Only	5714.55
22	Brick masonry work in cement mortar 1:3 in parapet excluding pointing and plastering as per drawing and technical specifications Clauses 600, 900 and 1208.4	5.760	Cum	5768.17	Rupees Five Thousand Seven Hundred & Sixty Eight and Paise Seventeen Only	33224.66
23	Painting Two Coats on New Concrete Surfaces :- Painting two coats including primer coat after filling the surface with synthetic enamel paint in all shades on new, plastered / concrete surfaces as per drawing and Technical Specification Clause 1701	40.320	Sqm	98.05	Rupees Ninety Eight and Paise Five Only	3953.38
Cost of Construction :-						3880217.79
Add 12% GST						465626.13
Add 1% Labour Cess						38802.18
Seigniorage Fee 10% on Basic Cost of Mines Material						17587.54
Total Cost of Construction :-						4402233.64
24	5 Year Maintenance Cost	20.00	Quarterly	95,880.80	Rupees Ninety Five Thousand Eight Hundred & Eighty and Paise Eighty Only	1917616.00
Cost of Maintenance :-						1917616.00
Add 12% GST						230113.92
Add 1% Labour Cess						19176.16
Seigniorage Fee 10% on Basic Cost of Mines Material						18505.89
Total Cost of Maintenance :-						2185411.97
Total Cost of Project Including Five Year Maintenance :-						6587645.61
Quoted Rate in Words		Rupees Forty Four Lakh Two Thousand Two Hundred & Thirty Three and Paise Sixty Four Only				

Signature of Tenderer with seal

Satyendra Kumar and Co. Construction (P) Ltd.

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, लखनऊ

12.5.22